					DEPARTMEN	IT OF N	FORM:  OF UTAH  NATURAL RESOURCES  L, GAS AND MINING  AMENDED REPORT									
		APP	LICATION F	OR	PERMIT TO DRII	LL				1. WELL NAME and		<b>R</b> 2-3604BS				
2. TYPE (	OF WORK	RILL NEW WELL (	REENTE	R P&	A WELL DEEL	PEN WEL	3. FIELD OR WILDCAT NATURAL BUTTES									
4. TYPE (		Gas			ed Methane Well: NO		5. UNIT or COMMUNITIZATION AGREEMENT NAME									
6. NAME	OF OPERATOR	2			GAS ONSHORE, L.P.			7. OPERATOR PHONE								
8. ADDRE	ESS OF OPERA	TOR			enver, CO, 80217			720 929-6515  9. OPERATOR E-MAIL julie.jacobson@anadarko.com								
	RAL LEASE N	UMBER	O. BOX 17377	9, D	11. MINERAL OWN	NERSHI			_	12. SURFACE OWN		wanada ko				
	L, INDIAN, OF	ML-22650			FEDERAL IN	NDIAN \Bigg	STATE (	FEE			DIAN 🦲	٠	_	FEE 🔵		
13. NAMI	E OF SURFACE	OWNER (if box :	12 = 'fee')							14. SURFACE OWNI	ER PHO	NE (if box	12 = 'fe	ee')		
15. ADDF	RESS OF SURF	ACE OWNER (if b	ox 12 = 'fee')	)						16. SURFACE OWNI	ER E-MA	IL (if box	12 = 'fe	ee')		
	AN ALLOTTEE 2 = 'INDIAN')	OR TRIBE NAME			18. INTEND TO CO MULTIPLE FORMA YES (Submit	TIONS	GLE PRODUCT		-	19. SLANT  VERTICAL DIR	RECTION	AL 📵 I	HORIZON	ITAL 🛑		
20. LOC	ATION OF WE	LL		FO	OTAGES	Q	TR-QTR	SECT	ION	TOWNSHIP	R	ANGE	МЕ	RIDIAN		
LOCATIO	ON AT SURFAC	CE	125	0 FS	SL 2103 FEL	1	SWSE	36	5	9.0 S	2	2.0 E		S		
Top of U	Ippermost Pro	ducing Zone	41	5 FS	L 1814 FEL		SWSE	36	5	9.0 S	2	2.0 E		S		
At Total	Depth		41	5 FS	L 1814 FEL		SWSE	36	5	9.0 S 2		22.0 E S		S		
21. COUN	NTY	UINTAH			22. DISTANCE TO		ST LEASE LIN 415	IE (Feet)		23. NUMBER OF AC		DRILLING 40	UNIT			
					25. DISTANCE TO (Applied For Drilli	ng or Co	26. PROPOSED DEPTH MD: 8695 TVD: 8560									
27. ELEV	ATION - GROU	JND LEVEL 4973			28. BOND NUMBER	BOND NUMBER  29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPR 22013542  Permit #43-8496						LICABLE				
					Hole, Casing				n							
String Surf	Hole Size	Casing Size 8.625	<b>Length</b> 0 - 2190		8.0 J-55 L		Max Mu			Cement		Sacks 180	Yield 1.15	Weight 15.8		
Suri	11	6.025	0 - 2190		.6.0 J-55 L	IAC	0.2	2		Type V Class G		270	1.15	15.8		
Prod	7.875	4.5	0 - 8695	1	1.6 I-80 L	T&C	12.	.5	Pren	nium Lite High Stre	ngth	270	3.38	11.0		
										50/50 Poz		1190	1.31	14.3		
						ATTAC	HMENTS									
	VERIFY T	HE FOLLOWIN	G ARE ATTA	СН	ED IN ACCORDA	NCE W	ITH THE U	TAH OIL	AND (	GAS CONSERVATI	ON GE	NERAL R	ULES			
<b>⊮</b> w	ELL PLAT OR	MAP PREPARED E	BY LICENSED	SUR	VEYOR OR ENGINE	ER	<b>№</b> сом	IPLETE DR	RILLING	S PLAN						
AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE) FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER																
DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY TOPOGRAPHICAL MAP																
<b>NAME</b> G	NAME Gina Becker TITLE Regulatory Analyst II PHONE 720 929-6086															
SIGNAT	URE			D.	ATE 05/14/2011				EMAIL	_ gina.becker@anadarl	ko.com					
	MBER ASSIGN 047516040			A	PPROVAL				Bi	00 4111						
									Perr	nit Manager						

NBU 922-36O Pad Drilling Program
1 of 4

#### Kerr-McGee Oil & Gas Onshore, L.P.

#### NBU 922-36O4BS

 Surface:
 1250 FSL / 2103 FEL
 SWSE

 BHL:
 415 FSL / 1814 FEL
 SWSE

Section 36 T9S R22E

Unitah County, Utah Mineral Lease: ML-22650

#### **ONSHORE ORDER NO. 1**

#### **DRILLING PROGRAM**

#### 1. & 2. <u>Estimated Tops of Important Geologic Markers</u>: <u>Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations</u>:

<u>Formation</u>	<u>Depth</u>	Resource
Uinta	0 - Surface	
Green River	1101	
Birds Nest	1369	Water
Mahogany	1736	Water
Wasatch	4164	Gas
Mesaverde	6333	Gas
MVU2	7343	Gas
MVL1	7924	Gas
TVD	8560	
TD	8695	

#### 3. <u>Pressure Control Equipment</u> (Schematic Attached)

Please refer to the attached Drilling Program

#### 4. <u>Proposed Casing & Cementing Program:</u>

Please refer to the attached Drilling Program

#### 5. <u>Drilling Fluids Program</u>:

Please refer to the attached Drilling Program

#### 6. <u>Evaluation Program</u>:

Please refer to the attached Drilling Program

NBU 922-36O Pad Drilling Program 2 of 4

#### 7. Abnormal Conditions:

Maximum anticipated bottom hole pressure calculated at 8560' TVD, approximately equals 5,650 psi 0.64 psi/ft = actual bottomhole gradient

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 3,583 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

#### **8.** Anticipated Starting Dates:

Drilling is planned to commence immediately upon approval of this application.

#### 9. <u>Variances:</u>

Please refer to the attached Drilling Program. Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- Blowout Prevention Equipment (BOPE) requirements;
- Mud program requirements; and
- Special drilling operation (surface equipment placement) requirements associated with air drilling.

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

#### Background

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

NBU 922-36O Pad Drilling Program 3 of 4

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 11 inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 11 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 8-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

#### Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

#### Variance for Mud Material Requirements

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

#### Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and

NBU 922-36O Pad Drilling Program 4 of 4

on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

#### Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.


#### **Other Information:**

Please refer to the attached Drilling Program.



# KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM

COMPANY NAME KERR-McGEE OIL & GAS ONSHORE LP DATE May 13, 2011 NBU 922-36O4BS WELL NAME TD 8,560' TVD 8,695' MD **FIELD** Natural Buttes **COUNTY** Uintah STATE Utah FINISHED ELEVATION 4972.9 SURFACE LOCATION **SWSE** 1250 FSL 2103 FEL Sec 36 T 9S R 22E Latitude: 39.988703 Longitude: -109.3857 **NAD 83** BTM HOLE LOCATION SWSE 415 FSL 1814 FEL Sec 36 T 9S R 22E Latitude: 39.98641 -109.384657 **NAD 83** Longitude: OBJECTIVE ZONE(S) Wasatch/Mesaverde





#### KERR-McGEE OIL & GAS ONSHORE LP

#### **DRILLING PROGRAM**

CASING PROGRAI	<u>VI</u>	DESIGN FACTORS									
										LTC	втс
	SIZE	INT	ERVAL		WT.	GR.	CPLG.	BURST	COLLA	PSE	TENSION
CONDUCTOR	14"	(	0-40'								
								3,390	1,880	348,000	N/A
SURFACE	8-5/8"	0	to	2,190	28.00	IJ-55	LTC	2.47	1.83	6.48	N/A
								7,780	6,350	279,000	367,000
PRODUCTION	4-1/2"	0	to	8,695	11.60	I-80	LTC/BTC	1.11	1.14	3.42	4.50

**Surface Casing:** 

(Burst Assumptions: TD = 12.5 ppg) 0.73 psi/ft = frac gradient @ surface shoe

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @ 7000 psi) 0.64 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

#### **CEMENT PROGRAM**

1		DECODINE OF	0.1.01/0	= 1/0=00		_	MIEL S
	FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGH	IT .	YIELD
SURFACE LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80		1.15
Option 1		+ 0.25 pps flocele					
TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80		1.15
		+ 2% CaCl + 0.25 pps flocele					
SURFACE		NOTE: If well will circulate water to	surface,	option 2 wil	l be utilized		
Option 2 LEAD	1,690'	65/35 Poz + 6% Gel + 10 pps gilsonite	160	35%	11.00		3.82
		+ 0.25 pps Flocele + 3% salt BWOW					
TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80		1.15
		+ 0.25 pps flocele					
TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80		1.15
PRODUCTION LEAD	3,655'	Premium Lite II +0.25 pps	270	20%	11.00		3.38
		celloflake + 5 pps gilsonite + 10% gel					
		+ 0.5% extender					
TAIL	5,040'	50/50 Poz/G + 10% salt + 2% gel	1,190	35%	14.30		1.31
		+ 0.1% R-3					

<sup>\*</sup>Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

#### **FLOAT EQUIPMENT & CENTRALIZERS**

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. No centralizers will be used.

#### ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

	<del>-</del>	Nick Spance / Emile Goodwin		
ORILLING	ENGINEER:		DATE:	
	Most rigs have PVT System for n	nud monitoring. If no PVT is available, visual monitoring will be utilized.		
	Surveys will be taken at 1,000' m	inimum intervals.		
	and lower kelly valves.			


DRILLING SUPERINTENDENT:

Kenny Gathings / Lovel Young


DATE:

<sup>\*</sup>Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

EXHIBIT A NBU 922-3604BS



SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK



			SURFACE POS	ITION							В	отто	M HOLE			
WELL NAME	NAD			NAD27					NAE				NAD27			
NIDIT	LATITUDE	LONGITUE					TAGES	<b>LATITUDE</b> 39°59'20.772"		<b>LONGITUDE</b> 109°23'07.287"		<b>LATITUDE LONGITUDE</b> 39°59'20.896" 109°23'04.836"		FOOTAGES		
NBU 922-36J4CS	39°59'19.313" 39.988698°	109°23'10.6 109.386281°			'08.160" 5600°		1 ' FSL 5 ' FEL	39°59'2 39.9891		1	!3'07.287"  85357°		9'20.896" 39138°		°23'04.836" .384677°	1409' FSL 1816' FEL
NBU	39°59'19.277"	109°23'10.7	31" 39°59'19.	401" 109°23	108.280"	1257	7' FSL	39°59'1	7.502"	109°2	3'07.259"	39°59	9'17.626"	109	°23'04.808"	1078' FSL
922-36O1BS NBU	39.988688° 39°59'19.242"	109.386314° 109°23'10.8			5633° '08.400"		5' FEL 4' FSL	39.9881 39°59'2			85350° !3'07.302"		38229° 9'24.166"		.384669° °23'04.851"	1815' FEL 1740' FSL
922-36J4BS	39.988678°	109*23*10.8					4' FEL	39.9900			85362°		90046°		.384681°	1740 FSL 1816 FEL
NBU	39°59'19.207"	109°23'10.9			'08.520"		D' FSL	39°59'1			3'07.216"				°23'04.765"	415' FSL
922-36O4BS NBU	39.988669° 39°59'19.172"	109.386381° 109°23'11.0			<u>5700°</u> '08.641"		3' FEL 7' FSL	39.9863 39°59'2			85338° !3'07.227"		36410° 9'27.437"		<u>.384657°</u> °23'04.776"	1814' FEL 2071' FSL
922-36J1CS	39.988659°	109 23 11.0 109.386414°					7 FEL	39.9909		1	85341°		90955°	1.00	.384660°	1809' FEL
NBU	39°59'18.765"	109°23'11.1		1.00 =0	'08.697"		5' FSL									
922-36O	39.988546°	109.386430°		1.03130			7' FEL	D :::			1					
WELL NAME	NORTH	EAST	WELL NAME	IVE COORD  NORTH	EAS		WELL		NOR		EAST	l w	/ELL NAM	IE	NORTH	EAST
NBU	148.0'		NBU				NBU	IVANIE					BU			293.1
922-36J4CS			922-36O1BS	-179.5	270.	5	922-36	5J4BS	486	.1"	275.9		2-36O4B	s	-835.3	293.1
WELL NAME	NORTH	EAST											Ç			
NBU 922-36J1CS	824.21	300.21											%			
Kerr-Mc	THE SE $\frac{1}{4}$ OF S.L.B.&M. W GLOBAL PO	ARINGS IS: SECTION 3 HICH IS TA SITIONING DNS TO BE.	FHE EAST LIF 66, T9S, R22E, KKEN FROM 6 SATELLITE AR N00°15'0	8"W. \$69°07''. AZ=24°	1	BUS	\$ 60 \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	922:36/48	36,85	0' 10'		1=60 0°13		198	13.56/19.16 Hom Hole,	139° 8.62°,
1099 1	8th Street - De	nver, Colora	do 80202													
	L PAD - N				+	6	09				BERLI NEFRIN			SUI	(4: RVEYINC	35) 789-1365 i. INC.
WELL	<b>PAD INTE</b>	RFERENC	CE PLAT												L, UTAH 840	
	WELLS - NBU				CONSI	ULTIN	NG. 110	С		E SURV			JRVEYED B			SHEET NO:
	922-36O1BS,				2155 No				09-0		A / N I -	150	VACIED R	, i : M	.3.0.	<u></u>
	22-36O4BS		-				82801		DATI	E DRAV 7 <b>-</b> 10	vin:	DI	RAWN BY:	E.M.	S.	6
	TED IN SECTION				Phone						1" = 60'	Di	ate Last Rev	vised:	:	•
5.L.B.&	km., UINTAF	COUNTY	, υτΑΠ.		rax 3	W1-67	4-0182			J. 1LL.	. 55					6 OF 17

EXISTING GRADE @ CENTER OF WELL PAD = 4972.8' FINISHED GRADE ELEVATION = 4968.01 **CUT SLOPES = 1.5:1** FILL SLOPES = 1.5:1**TOTAL WELL PAD AREA = 3.63 ACRES TOTAL DAMAGE AREA = 6.38 ACRES SHRINKAGE FACTOR = 1.10 SWELL FACTOR = 1.00** 

# Kerr-McGee Oil & Gas Onshore, LP

1099 18th Street - Denver, Colorado 80202

## **WELL PAD - NBU 922-36O**

**WELL PAD - LOCATION LAYOUT** NBU 922-36J4CS, NBU 922-36O1BS, NBU 922-36J4BS, NBU 922-36O4BS & NBU 922-36J1CS LOCATED IN SECTION 36, T9S, R22E, S.L.B.&M., UINTAH COUNTY, UTAH



2155 North Main Street

Sheridan, WY 82801

Phone 307-674-0609 Fax 307-674-0182

## WELL PAD QUANTITIES

TOTAL CUT FOR WELL PAD = 14.706 C.Y. TOTAL FILL FOR WELL PAD = 10,805 C.Y. TOPSOIL @ 6" DEPTH = 2.115 C.Y.EXCESS MATERIAL = 3,901 C.Y.

## **RESERVE PIT QUANTITIES**

**TOTAL CUT FOR RESERVE PIT** +/- 11,020 C.Y. **RESERVE PIT CAPACITY (2' OF FREEBOARD)** +/- 42,290 BARRELS

## **TIMBERLINE**

ENGINEERING & LAND SURVEYING, INC. 209 NORTH 300 WEST - VERNAL, UTAH 84078

(435) 789-1365


**SCALE:** 

**REVISED:** 

# **EXISTING WELL LOCATION**



PROPOSED WELL LOCATION PROPOSED BOTTOM HOLE LOCATION EXISTING CONTOURS (2' INTERVAL) PROPOSED CONTOURS (21 INTERVAL) — PPL — PROPOSED PIPELINE






60<sup>1</sup> HORIZONTAL E


21 CONTOURS

1"=60' DATE: 12/3/10 SHEET NO:

7 OF 17



# **CROSS SECTION A-A'**



# Kerr-McGee Oil & Gas Onshore, LP


1099 18th Street - Denver, Colorado 80202

**WELL PAD - NBU 922-36O** 

**WELL PAD - CROSS SECTIONS** NBU 922-36J4CS, NBU 922-36O1BS, NBU 922-36J4BS, NBU 922-36O4BS & NBU 922-36J1CS LOCATED IN SECTION 36, T9S, R22E, S.L.B.&M., UINTAH COUNTY, UTAH



**CONSULTING, LLC** 2155 North Main Street Sheridan, WY 82801 Phone 307-674-0609 Fax 307-674-0182



**TIMBERLINE** 

ENGINEERING & LAND SURVEYING, INC. 209 NORTH 300 WEST - VERNAL, UTAH 84078

١	Scale:	1"=100'	Date:	12/3/10	SHEET NO:	
	REVISED:				8	8 OF 1




PHOTO VIEW: FROM PIT CORNER D TO LOCATION STAKE

**CAMERA ANGLE: NORTHWESTERLY** 



PHOTO VIEW: FROM EXISTING ACCESS ROAD

**CAMERA ANGLE: SOUTHERLY** 

#### Kerr-McGee Oil & Gas Onshore, LP 1099 18th Street - Denver, Colorado 80202

,

# WELL PAD - NBU 922-36O

LOCATION PHOTOS
NBU 922-36J4CS,
NBU 922-36O1BS, NBU 922-36J4BS,
NBU 922-36O4BS & NBU 922-36J1CS
LOCATED IN SECTION 36, T9S, R22E,
S.L.B.&M., UINTAH COUNTY, UTAH.



# CONSULTING, LLC


2155 North Main Street Sheridan WY 82801 Phone 307-674-0609 Fax 307-674-0182


#### TIMBERLINE


(435) 789-1365


ENGINEERING & LAND SURVEYING, INC. 209 NORTH 300 WEST - VERNAL, UTAH 84078


20711011111300	WEST - VERTILE, CITATIO	010
DATE PHOTOS TAKEN: 11-17-10	PHOTOS TAKEN BY: M.S.B.	SHEET NO:
DATE DRAWN: 11-17-10	DRAWN BY: E.M.S.	10
Date Last Revised:		10 OF 17














Kerr-McGee Oil & Gas Onshore, LP WELL PAD – NBU 922-36O WELLS – NBU 922-36J4CS, NBU 922-36O1BS, NBU 922-36J4BS, NBU 922-36O4BS & NBU 922-36J1CS Section 36, T9S, R22E, S.L.B.&M.

From the intersection of U.S. Highway 40 and 500 East Street in Vernal, Utah, proceed in an easterly then southerly direction along U.S. Highway 40 approximately 3.3 miles to the junction of State Highway 45. Exit right and proceed in a southerly direction along State Highway 45 approximately 20.2 miles to the junction of the Glen Bench Road (County B Road 3260). Exit right and proceed in a southwesterly direction along the Glen Bench Road approximately 14.4 miles to the intersection of the Fidlar Road (County B Road 3410) which road intersection is approximately 400 feet northeast of the Mountain Fuel Bridge at the White River. Exit left and proceed in a southeasterly direction along the Fidlar Road approximately 4.4 miles to the intersection of the Seven Sisters Road (County B Road 3420). Exit right and proceed in a southerly, then southeasterly direction along the Seven Sisters Road approximately 2.4 miles to a service road to the southwest. Exit right and proceed in a southwesterly, then northerly, then southwesterly direction along the service road approximately 0.8 miles to an access road to the southeast. Exit left and proceed in a southeasterly, then southwesterly direction along the access road approximately 0.1 miles to the proposed well pad.

Total distance from Vernal, Utah to the proposed well location is approximately 45.6 miles in a southerly direction.

API Well Number: 430475160400@oject: Uintah County, UT UTM12 Scientific Drilling

Rocky Mountain Operations

Site: NBU 922-360 PAD

Well: NBU 922-36O4BS


Wellbore: OH

Design: PLAN #1 2-7-11 RHS



WELL DETAILS: NBU 922-3604BS GL 4968 & KB 4 +N/-S 0.00 Northing Easting 2092599.82 Longitude 109° 23' 8.520 W 14526025.01 39° 59' 19.331 N DESIGN TARGET DETAILS +N/-S -835.15 +E/-W 292.23 Northing 14525195.28 Easting 2092907.13 Longitude 109° 23' 4.765 W Shape Circle (Radius: 25.00) Latitude 8560.00 11.076 N - plan hits target center

Azimuths to True North Magnetic North: 11.07 Magnetic Field Strength: 52373.8snT Dip Angle: 65.89° Date: 02/07/2011 Model: IGRF2010





# **Kerr McGee Oil and Gas Onshore LP**

Uintah County, UT UTM12 NBU 922-360 PAD NBU 922-3604BS

ОН

Plan: PLAN #1 2-7-11 RHS

# **Standard Planning Report**

07 February, 2011





### SDI Planning Report



EDM5000-RobertS-Local Database:

Company: Kerr McGee Oil and Gas Onshore LP

Uintah County, UT UTM12 Project:

Site: NBU 922-360 PAD NBU 922-36O4BS Well:

Wellbore: OH

Design: PLAN #1 2-7-11 RHS Local Co-ordinate Reference:

**Survey Calculation Method:** 

**TVD Reference:** 

North Reference:

GI 4968 & KB 4 @ 4972.00ft (ASSUMED)

GL 4968 & KB 4 MD Reference:

@ 4972.00ft (ASSUMED)

Well NBU 922-36O4BS

Minimum Curvature

Mean Sea Level

Uintah County, UT UTM12 **Project** 

Map System: Universal Transverse Mercator (US Survey Feet) System Datum:

NAD 1927 - Western US Geo Datum: Zone 12N (114 W to 108 W) Map Zone:

NBU 922-360 PAD, SECTION 36 T9S R22E Site

Northing: 14,526,021.20 usft Site Position: 39° 59' 19.295 N Latitude: From: Lat/Long Easting: 2,092,590.64 usft Longitude: 109° 23' 8.639 W

0.00 ft Slot Radius: 13.200 in **Grid Convergence:** 1.04° **Position Uncertainty:** 

Well NBU 922-36O4BS, 1250 FSL 2103 FEL

**Well Position** 3.64 ft 14.526.025.01 usft 39° 59' 19 331 N +N/-S Northing: Latitude:

+E/-W 9.25 ft Easting: 2,092,599.82 usft Longitude: 109° 23' 8.520 W

**Position Uncertainty** 0.00 ft Wellhead Elevation: Ground Level: 4.968.00 ft

ОН Wellbore Field Strength Magnetics **Model Name** Sample Date Declination Dip Angle (°) (°) (nT) IGRF2010 02/07/2011 11.07 65.89 52,374

PLAN #1 2-7-11 RHS Design Audit Notes: PLAN 0.00 Version: Phase: Tie On Depth: Vertical Section: Depth From (TVD) +N/-S +E/-W Direction

(ft) (ft) (ft) (°) 0.00 160.71 0.00 0.00

**Plan Sections** Measured Vertical Dogleg Build Turn Depth Inclination Azimuth Depth +N/-S +E/-W Rate Rate Rate **TFO** (°/100ft) (°/100ft) (°/100ft) (ft) (°) (°) (ft) (ft) (ft) **Target** (°) 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 300.00 0.00 0.00 300.00 0.00 0.00 0.00 0.00 0.00 0.00 20.00 160.71 1,279.82 -163.07 57.06 2.00 2.00 0.00 160.71 1,300.00 2,876.71 20.00 160.71 2,761.44 -672.08 235.17 0.00 0.00 0.00 0.00 3,876.71 0.00 0.00 3,741.26 -835 15 292.23 2 00 -2.00 0.00 180.00 8,695.46 0.00 0.00 8,560.00 -835.15 292.23 0.00 0.00 0.00 0.00 PBHL\_NBU 922-36O4



# **SDI**Planning Report



Database: EDM5000-RobertS-Local

Company: Kerr McGee Oil and Gas Onshore LP

Project: Uintah County, UT UTM12

 Site:
 NBU 922-36O PAD

 Well:
 NBU 922-36O4BS

Wellbore: OH

Design: PLAN #1 2-7-11 RHS

Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference:

**Survey Calculation Method:** 

Well NBU 922-36O4BS

GL 4968 & KB 4

@ 4972.00ft (ASSUMED)

GL 4968 & KB 4

@ 4972.00ft (ASSUMED)

True

Minimum Curvature

ned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
Start Build	2.00								
400.00	2.00	160.71	399.98	-1.65	0.58	1.75	2.00	2.00	0.00
500.00	4.00	160.71	499.84	-6.59	2.30	6.98	2.00	2.00	0.00
600.00	6.00	160.71	599.45	-14.81	5.18	15.69	2.00	2.00	0.00
700.00	8.00	160.71	698.70	-26.32	9.21	27.88	2.00	2.00	0.00
800.00	10.00	160.71	797.47	-41.08	14.37	43.52	2.00	2.00	0.00
900.00	12.00	160.71	895.62	-59.09	20.68	62.60	2.00	2.00	0.00
1,000.00	14.00	160.71	993.06	-80.32	28.11	85.10	2.00	2.00	0.00
1,100.00	16.00	160.71	1,089.64	-104.75	36.65	110.98	2.00	2.00	0.00
1,111.82	16.24	160.71	1,101.00	-107.85	37.74	114.26	2.00	2.00	0.00
GREEN RIV	ER								
1,200.00	18.00	160.71	1,185.27	-132.34	46.31	140.21	2.00	2.00	0.00
1,300.00	20.00	160.71	1,279.82	-163.07	57.06	172.77	2.00	2.00	0.00
Start 1576.7	'1 hold at 1300.00	MD							
4 400 00	22.22	100 71	4 070 70	405.00	20.00	222.27	0.00	0.00	0.00
1,400.00	20.00	160.71	1,373.78	-195.36	68.36	206.97	0.00	0.00	0.00
1,500.00	20.00	160.71	1,467.75	-227.64	79.65	241.17	0.00	0.00	0.00
1,600.00	20.00	160.71	1,561.72	-259.92	90.95	275.37	0.00	0.00	0.00
1,700.00	20.00	160.71	1,655.69	-292.20	102.24	309.58	0.00	0.00	0.00
1,800.00	20.00	160.71	1,749.66	-324.49	113.54	343.78	0.00	0.00	0.00
1,900.00	20.00	160.71	1,843.63	-356.77	124.84	377.98	0.00	0.00	0.00
2,000.00	20.00	160.71	1,937.60	-389.05	136.13	412.18	0.00	0.00	0.00
2,100.00	20.00	160.71	2,031.57	-421.34	147.43	446.38	0.00	0.00	0.00
2,200.00	20.00	160.71	2,125.54	-453.62	158.72	480.59	0.00	0.00	0.00
2,264.34	20.00	160.71	2,186.00	-474.39	165.99	502.59	0.00	0.00	0.00
8 5/8"									
0.000.00	22.22	100 71	0.040.54	405.00	470.00	511.70	0.00	0.00	0.00
2,300.00	20.00	160.71	2,219.51	-485.90	170.02	514.79	0.00	0.00	0.00
2,400.00	20.00	160.71	2,313.48	-518.18	181.32	548.99	0.00	0.00	0.00
2,500.00	20.00	160.71	2,407.45	-550.47	192.61	583.19	0.00	0.00	0.00
2,600.00	20.00	160.71	2,501.42	-582.75	203.91	617.39	0.00	0.00	0.00
2,700.00	20.00	160.71	2,595.39	-615.03	215.20	651.60	0.00	0.00	0.00
2,800.00	20.00	160.71	2,689.35	-647.31	226.50	685.80	0.00	0.00	0.00
2,876.71	20.00	160.71	2,761.44	-672.08	235.17	712.04	0.00	0.00	0.00
Start Drop -	2.00								
2,900.00	19.53	160.71	2,783.36	-679.51	237.77	719.91	2.00	-2.00	0.00
3,000.00	17.53	160.71	2,878.16	-709.52	248.26	751.70	2.00	-2.00	0.00
3,100.00	15.53	160.71	2,974.02	-736.38	257.66	780.15	2.00	-2.00	0.00
3,200.00	13.53	160.71	3,070.82	760.06	265.05	805.25	2.00	-2.00	0.00
3,200.00	11.53		3,070.82	-760.06	265.95	805.25 826.95		-2.00 -2.00	
		160.71	3,168.43	-780.55 707.80	273.12	826.95 845.23	2.00		0.00
3,400.00 3,500.00	9.53 7.53	160.71 160.71	3,266.74 3,365.63	-797.80 -811.81	279.16 284.06	845.23 860.07	2.00 2.00	-2.00 -2.00	0.00 0.00
3,600.00	7.53 5.53	160.71	3,365.63 3,464.97	-811.81 -822.55	284.06 287.82	860.07 871.45	2.00	-2.00 -2.00	0.00
3,700.00	3.53	160.71	3,564.66	-830.01	290.43	879.35	2.00	-2.00	0.00
3,800.00	1.53	160.71	3,664.55	-834.18	291.89	883.78	2.00	-2.00	0.00
3,876.71	0.00	0.00	3,741.26	-835.15	292.23	884.80	2.00	-2.00	0.00
Start 4818.7	'4 hold at 3876.71	1 MD							
3,900.00	0.00	0.00	3,764.54	-835.15	292.23	884.80	0.00	0.00	0.00
4.000.00	0.00	0.00	3,864.54	-835.15	292.23	884.80	0.00	0.00	0.00



# **SDI**Planning Report



Database: EDM5000-RobertS-Local

Company: Kerr McGee Oil and Gas Onshore LP

Project: Uintah County, UT UTM12

 Site:
 NBU 922-36O PAD

 Well:
 NBU 922-36O4BS

Wellbore: OH

Design: PLAN #1 2-7-11 RHS

Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference:

**Survey Calculation Method:** 

Well NBU 922-36O4BS

GL 4968 & KB 4

@ 4972.00ft (ASSUMED) GL 4968 & KB 4

@ 4972.00ft (ASSUMED) True

Minimum Curvature

nned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
4,100.00	0.00	0.00	3,964.54	-835.15	292.23	884.80	0.00	0.00	0.00
4,200.00	0.00	0.00	4,064.54	-835.15	292.23	884.80	0.00	0.00	0.00
4,299.46	0.00	0.00	4,164.00	-835.15	292.23	884.80	0.00	0.00	0.00
WASATCH									
4,300.00	0.00	0.00	4,164.54	-835.15	292.23	884.80	0.00	0.00	0.00
4,400.00	0.00	0.00	4,264.54	-835.15	292.23	884.80	0.00	0.00	0.00
4,500.00	0.00	0.00	4,364.54	-835.15	292.23	884.80	0.00	0.00	0.00
4,600.00	0.00	0.00	4,464.54	-835.15	292.23	884.80	0.00	0.00	0.00
4,700.00	0.00	0.00	4,564.54	-835.15	292.23	884.80	0.00	0.00	0.00
4,800.00	0.00	0.00	4,664.54	-835.15	292.23	884.80	0.00	0.00	0.00
4,900.00	0.00	0.00	4,764.54	-835.15	292.23	884.80	0.00	0.00	0.00
5,000.00	0.00	0.00	4,864.54	-835.15	292.23	884.80	0.00	0.00	0.00
5,100.00	0.00	0.00	4,964.54	-835.15	292.23	884.80	0.00	0.00	0.00
5,200.00	0.00	0.00	5,064.54	-835.15	292.23	884.80	0.00	0.00	0.00
5,300.00	0.00	0.00	5,164.54	-835.15	292.23	884.80	0.00	0.00	0.00
5,400.00	0.00	0.00	5,264.54	-835.15	292.23	884.80	0.00	0.00	0.00
5,500.00	0.00	0.00	5,364.54	-835.15	292.23	884.80	0.00	0.00	0.00
5,600.00	0.00	0.00	5,464.54	-835.15	292.23	884.80	0.00	0.00	0.00
5,700.00	0.00	0.00	5,564.54	-835.15	292.23	884.80	0.00	0.00	0.00
5,800.00	0.00	0.00	5,664.54	-835.15	292.23	884.80	0.00	0.00	0.00
5,900.00	0.00	0.00	5,764.54	-835.15	292.23	884.80	0.00	0.00	0.00
0.000.00	0.00	0.00	F 004 F4	025.45		004.00	0.00	0.00	0.00
6,000.00	0.00	0.00	5,864.54	-835.15	292.23	884.80	0.00	0.00	0.00
6,100.00 6,200.00	0.00	0.00	5,964.54 6,064.54	-835.15	292.23 292.23	884.80 884.80	0.00	0.00	0.00
6,300.00	0.00 0.00	0.00	,	-835.15	292.23 292.23		0.00 0.00	0.00	0.00
6,400.00	0.00	0.00 0.00	6,164.54 6,264.54	-835.15 -835.15	292.23	884.80 884.80	0.00	0.00 0.00	0.00 0.00
0,400.00	0.00		0,204.54				0.00	0.00	0.00
6,468.46	0.00	0.00	6,333.00	-835.15	292.23	884.80	0.00	0.00	0.00
MESAVERD									
6,500.00	0.00	0.00	6,364.54	-835.15	292.23	884.80	0.00	0.00	0.00
6,600.00	0.00	0.00	6,464.54	-835.15	292.23	884.80	0.00	0.00	0.00
6,700.00	0.00	0.00	6,564.54	-835.15	292.23	884.80	0.00	0.00	0.00
6,800.00	0.00	0.00	6,664.54	-835.15	292.23	884.80	0.00	0.00	0.00
6,900.00	0.00	0.00	6,764.54	-835.15	292.23	884.80	0.00	0.00	0.00
7,000.00	0.00	0.00	6,864.54	-835.15	292.23	884.80	0.00	0.00	0.00
7,100.00	0.00	0.00	6,964.54	-835.15	292.23	884.80	0.00	0.00	0.00
7,200.00	0.00	0.00	7,064.54	-835.15	292.23	884.80	0.00	0.00	0.00
7,300.00	0.00	0.00	7,164.54	-835.15	292.23	884.80	0.00	0.00	0.00
7,400.00	0.00	0.00	7,264.54	-835.15	292.23	884.80	0.00	0.00	0.00
,	0.00	0.00	,		292.23 292.23	884.80 884.80	0.00	0.00	0.00
7,500.00 7,600.00	0.00	0.00	7,364.54 7,464.54	-835.15 -835.15	292.23 292.23	884.80 884.80	0.00	0.00	0.00
7,700.00	0.00	0.00	7,464.54 7,564.54	-835.15 -835.15	292.23	884.80	0.00	0.00	0.00
7,700.00	0.00	0.00	7,564.54 7,664.54	-835.15 -835.15	292.23	884.80	0.00	0.00	0.00
*									
7,900.00	0.00	0.00	7,764.54	-835.15	292.23	884.80	0.00	0.00	0.00
8,000.00	0.00	0.00	7,864.54	-835.15	292.23	884.80	0.00	0.00	0.00
8,100.00	0.00	0.00	7,964.54	-835.15	292.23	884.80	0.00	0.00	0.00
8,200.00	0.00	0.00	8,064.54	-835.15	292.23	884.80	0.00	0.00	0.00
8,300.00	0.00	0.00	8,164.54	-835.15	292.23	884.80	0.00	0.00	0.00
8,400.00	0.00	0.00	8,264.54	-835.15	292.23	884.80	0.00	0.00	0.00
8,500.00	0.00	0.00	8,364.54	-835.15	292.23	884.80	0.00	0.00	0.00
8,600.00	0.00	0.00	8,464.54	-835.15	292.23	884.80	0.00	0.00	0.00
8,695.46	0.00	0.00	8,560.00	-835.15	292.23	884.80	0.00	0.00	0.00
5,000.70	6 - PBHL NBU 9		5,500.00	230.10	_00	551.00	0.00	0.00	0.00



### SDI Planning Report



Database: Company: EDM5000-RobertS-Local

Kerr McGee Oil and Gas Onshore LP

Project:

Uintah County, UT UTM12

Site:

NBU 922-360 PAD

Well: NBU 922-36O4BS

Wellbore:

Design: PLAN #1 2-7-11 RHS Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference:

**Survey Calculation Method:** 

Well NBU 922-36O4BS

GL 4968 & KB 4

@ 4972.00ft (ASSUMED)

GL 4968 & KB 4

@ 4972.00ft (ASSUMED)

Minimum Curvature

**Planned Survey** 

Measured Vertical Vertical Dogleg Build Turn Depth Depth +N/-S +E/-W Section Rate Rate Rate Inclination Azimuth (°/100ft) (°/100ft) (°/100ft) (ft) (ft) (ft) (ft) (ft) (°) (°)

**Design Targets Target Name** - hit/miss target Dip Dir. TVD +N/-S +E/-W Northing Easting Dip Angle - Shape (°) (°) (ft) (ft) (ft) (usft) (usft) Latitude Longitude PBHL\_NBU 922-36O4B 0.00 0.00 8,560.00 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W plan hits target centerCircle (radius 25.00)

**Casing Points** Measured Vertical Casing Hole Depth Depth Diameter Diameter (ft) (ft) (in) (in) Name 8 5/8" 8.625 2,264.34 2,186.00 11.000

**Formations** Measured Vertical Dip Depth Depth Dip Direction (ft) (ft) (°) Name Lithology (°) 1,111.82 1,101.00 **GREEN RIVER** 4,299.46 4,164.00 WASATCH 6,468.46 6,333.00 MESAVERDE

Plan Annotations				
Measured	Vertical	Local Coor	dinates	
Depth	Depth	+N/-S	+E/-W	
(ft)	(ft)	(ft)	(ft)	Comment
300.00	300.00	0.00	0.00	Start Build 2.00
1,300.00	1,279.82	-163.07	57.06	Start 1576.71 hold at 1300.00 MD
2,876.71	2,761.44	-672.08	235.17	Start Drop -2.00
3,876.71	3,741.26	-835.15	292.23	Start 4818.74 hold at 3876.71 MD
8,695.46	8,560.00	-835.15	292.23	TD at 8695.46



# **Kerr McGee Oil and Gas Onshore LP**

Uintah County, UT UTM12 NBU 922-360 PAD NBU 922-3604BS

OH

Plan: PLAN #1 2-7-11 RHS

# **Survey Report - Geographic**

07 February, 2011





### SDI Survey Report - Geographic



160.71

Kerr McGee Oil and Gas Onshore LP Company:

Uintah County, UT UTM12 Project:

Site: NBU 922-360 PAD

NBU 922-36O4BS Well:

Wellbore:

PLAN #1 2-7-11 RHS Design:

Local Co-ordinate Reference:

**TVD Reference:** 

MD Reference:

Database:

Well NBU 922-36O4BS GL 4968 & KB 4

@ 4972.00ft (ASSUMED)

GL 4968 & KB 4

@ 4972.00ft (ASSUMED)

North Reference: True

**Survey Calculation Method:** 

Minimum Curvature EDM5000-RobertS-Local

Uintah County, UT UTM12 **Project** 

Map System: Universal Transverse Mercator (US Survey Feet)

NAD 1927 - Western US

Geo Datum: Zone 12N (114 W to 108 W) Map Zone:

Mean Sea Level System Datum:

Site NBU 922-360 PAD, SECTION 36 T9S R22E

Northing: 14,526,021.20 usft 39° 59' 19.295 N Site Position: Latitude: Easting: Lat/Long 2,092,590.64 usft Longitude: 109° 23' 8.639 W From:

0.00 ft **Position Uncertainty:** Slot Radius: 13.200 in Grid Convergence: 1.04 °

Well NBU 922-36O4BS, 1250 FSL 2103 FEL **Well Position** +N/-S 0.00 ft Northing: 14,526,025.01 usft Latitude: 39° 59' 19.331 N +E/-W 0.00 ft Easting: 2,092,599.82 usft Longitude: 109° 23' 8.520 W **Position Uncertainty** 0.00 ft Wellhead Elevation: Ground Level: 4,968.00 ft

ОН Wellbore Declination Field Strength Magnetics Model Name Sample Date Dip Angle (°) (°) (nT) IGRF2010 02/07/2011 11.07 65.89 52,374

PLAN #1 2-7-11 RHS Design Audit Notes: Version: Phase: **PLAN** Tie On Depth: 0.00 Depth From (TVD) +N/-S Direction Vertical Section: +E/-W (ft) (ft) (ft) (°) 0.00

0.00

0.00

02/07/2011 **Survey Tool Program** Date From То (ft) (ft) Survey (Wellbore) **Tool Name** Description 0.00 8,695.46 PLAN #1 2-7-11 RHS (OH) MWD SDI MWD - Standard ver 1.0.1

Planned Survey	•								
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
0.00	0.00	0.00	0.00	0.00	0.00	14,526,025.01	2,092,599.82	39° 59' 19.331 N	109° 23' 8.520 W
100.00	0.00	0.00	100.00	0.00	0.00	14,526,025.01	2,092,599.82	39° 59' 19.331 N	109° 23' 8.520 W
200.00	0.00	0.00	200.00	0.00	0.00	14,526,025.01	2,092,599.82	39° 59' 19.331 N	109° 23' 8.520 W
300.00	0.00	0.00	300.00	0.00	0.00	14,526,025.01	2,092,599.82	39° 59' 19.331 N	109° 23' 8.520 W
Start Bu	ild 2.00								
400.00	2.00	160.71	399.98	-1.65	0.58	14,526,023.38	2,092,600.43	39° 59' 19.315 N	109° 23' 8.513 W
500.00	4.00	160.71	499.84	-6.59	2.30	14,526,018.47	2,092,602.24	39° 59' 19.266 N	109° 23' 8.490 W
600.00	6.00	160.71	599.45	-14.81	5.18	14,526,010.30	2,092,605.27	39° 59' 19.184 N	109° 23' 8.453 W
700.00	8.00	160.71	698.70	-26.32	9.21	14,525,998.87	2,092,609.50	39° 59' 19.071 N	109° 23' 8.402 W
800.00	10.00	160.71	797.47	-41.08	14.37	14,525,984.20	2,092,614.94	39° 59' 18.925 N	109° 23' 8.335 W



# **SDI**Survey Report - Geographic



Company: Kerr McGee Oil and Gas Onshore LP

Project: Uintah County, UT UTM12

Site: NBU 922-360 PAD

Well: NBU 922-36O4BS

Wellbore: OH

Design: PLAN #1 2-7-11 RHS

Local Co-ordinate Reference:

TVD Reference:

MD Reference:

Well NBU 922-36O4BS GL 4968 & KB 4

@ 4972.00ft (ASSUMED) GL 4968 & KB 4

@ 4972.00ft (ASSUMED)

Minimum Curvature

North Reference: True

Survey Calculation Method:

Database: EDM5000-RobertS-Local

Planned Survey	lanned Survey								
Measured Depth (ft)	Inclination	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
						, ,			
900.00 1,000.00 1,100.00	12.00 14.00 16.00	160.71 160.71 160.71	895.62 993.06 1,089.64	-59.09 -80.32 -104.75	20.68 28.11 36.65	14,525,966.31 14,525,945.21 14,525,920.94	2,092,621.56 2,092,629.37 2,092,638.36	39° 59' 18.747 N 39° 59' 18.537 N 39° 59' 18.295 N	109° 23' 8.254 W 109° 23' 8.159 W 109° 23' 8.049 W
1,111.82	16.24	160.71	1,101.00	-107.85	37.74	14,525,917.87	2,092,639.50	39° 59' 18.265 N	109° 23' 8.035 W
GREEN I									
1,200.00	18.00	160.71	1,185.27	-132.34	46.31	14,525,893.53	2,092,648.52	39° 59' 18.023 N	109° 23' 7.925 W
1,300.00	20.00	160.71	1,279.82	-163.07	57.06	14,525,863.00	2,092,659.82	39° 59' 17.719 N	109° 23' 7.787 W
	'6.71 hold at 1		4 070 70	405.00	22.22	44 505 000 00	0.000.074.70	000 501 47 400 11	4000 001 7 0 40 144
1,400.00	20.00	160.71	1,373.78	-195.36	68.36	14,525,830.93	2,092,671.70	39° 59' 17.400 N	109° 23' 7.642 W
1,500.00	20.00	160.71	1,467.75	-227.64	79.65	14,525,798.85	2,092,683.58	39° 59' 17.081 N	109° 23' 7.497 W
1,600.00 1,700.00	20.00 20.00	160.71 160.71	1,561.72 1,655.69	-259.92 -292.20	90.95 102.24	14,525,766.78 14,525,734.71	2,092,695.46 2,092,707.34	39° 59' 16.762 N 39° 59' 16.443 N	109° 23' 7.351 W 109° 23' 7.206 W
1,800.00	20.00	160.71	1,749.66	-324.49	113.54	14,525,702.63	2,092,719.22	39° 59' 16.124 N	109° 23' 7.260 W
1,900.00	20.00	160.71	1,843.63	-356.77	124.84	14,525,670.56	2,092,731.10	39° 59' 15.804 N	109° 23' 6.916 W
2,000.00	20.00	160.71	1,937.60	-389.05	136.13	14,525,638.49	2,092,742.98	39° 59' 15.485 N	109° 23' 6.771 W
2,100.00	20.00	160.71	2,031.57	-421.34	147.43	14,525,606.42	2,092,754.85	39° 59' 15.166 N	109° 23' 6.626 W
2,200.00	20.00	160.71	2,125.54	-453.62	158.72	14,525,574.34	2,092,766.73	39° 59' 14.847 N	109° 23' 6.481 W
2,264.34	20.00	160.71	2,186.00	-474.39	165.99	14,525,553.71	2,092,774.38	39° 59' 14.642 N	109° 23' 6.387 W
8 5/8"									
2,300.00	20.00	160.71	2,219.51	-485.90	170.02	14,525,542.27	2,092,778.61	39° 59' 14.528 N	109° 23' 6.335 W
2,400.00	20.00	160.71	2,313.48	-518.18	181.32	14,525,510.20	2,092,790.49	39° 59' 14.209 N	109° 23' 6.190 W
2,500.00	20.00	160.71	2,407.45	-550.47	192.61	14,525,478.12	2,092,802.37	39° 59' 13.890 N	109° 23' 6.045 W
2,600.00	20.00	160.71	2,501.42	-582.75	203.91	14,525,446.05	2,092,814.25	39° 59' 13.571 N	109° 23' 5.900 W
2,700.00	20.00	160.71	2,595.39	-615.03	215.20	14,525,413.98	2,092,826.13	39° 59' 13.252 N	109° 23' 5.755 W
2,800.00	20.00	160.71	2,689.35	-647.31	226.50	14,525,381.91	2,092,838.01	39° 59' 12.933 N	109° 23' 5.610 W
2,876.71	20.00	160.71	2,761.44	-672.08	235.17	14,525,357.30	2,092,847.12	39° 59' 12.688 N	109° 23' 5.498 W
Start Dro	p -2.00								
2,900.00	19.53	160.71	2,783.36	-679.51	237.77	14,525,349.92	2,092,849.85	39° 59' 12.614 N	109° 23' 5.465 W
3,000.00	17.53	160.71	2,878.16	-709.52	248.26	14,525,320.11	2,092,860.89	39° 59' 12.318 N	109° 23' 5.330 W
3,100.00	15.53	160.71	2,974.02	-736.38	257.66	14,525,293.42	2,092,870.78	39° 59' 12.052 N	109° 23' 5.209 W
3,200.00	13.53	160.71	3,070.82	-760.06	265.95	14,525,269.89	2,092,879.49	39° 59' 11.818 N	109° 23' 5.103 W
3,300.00	11.53	160.71	3,168.43	-780.55 -707.00	273.12	14,525,249.54	2,092,887.03	39° 59' 11.616 N	109° 23' 5.011 W
3,400.00	9.53	160.71	3,266.74 3,365.63	-797.80	279.16	14,525,232.40	2,092,893.38	39° 59' 11.445 N	109° 23' 4.933 W
3,500.00 3,600.00	7.53 5.53	160.71 160.71	3,365.63 3,464.97	-811.81 -822.55	284.06 287.82	14,525,218.48	2,092,898.53 2,092,902.48	39° 59' 11.307 N 39° 59' 11.201 N	109° 23' 4.870 W 109° 23' 4.822 W
3,700.00	3.53	160.71	3,564.66	-830.01	290.43	14,525,207.81 14,525,200.40	2,092,902.48	39° 59' 11.127 N	109° 23' 4.788 W
3,800.00	1.53	160.71	3,664.55	-834.18	291.89	14,525,196.25	2,092,906.77	39° 59' 11.086 N	109° 23' 4.770 W
3,876.71	0.00	0.00	3,741.26	-835.15	292.23	14,525,195.29	2,092,907.12	39° 59' 11.076 N	109° 23' 4.765 W
	8.74 hold at 3		5,. 11.25	550.10		,020,100.20	_,00_,007.12	33 33 11.07014	.55 25 1.755 **
3,900.00	0.00	0.00	3,764.54	-835.15	292.23	14,525,195.29	2,092,907.12	39° 59' 11.076 N	109° 23' 4.765 W
4,000.00	0.00	0.00	3,864.54	-835.15	292.23	14,525,195.29	2,092,907.12	39° 59' 11.076 N	109° 23' 4.765 W
4,100.00	0.00	0.00	3,964.54	-835.15	292.23	14,525,195.29	2,092,907.12	39° 59' 11.076 N	109° 23' 4.765 W
4,200.00	0.00	0.00	4,064.54	-835.15	292.23	14,525,195.29	2,092,907.12	39° 59' 11.076 N	109° 23' 4.765 W
4,299.46	0.00	0.00	4,164.00	-835.15	292.23	14,525,195.29	2,092,907.12	39° 59' 11.076 N	109° 23' 4.765 W
WASATO	СН								
4,300.00	0.00	0.00	4,164.54	-835.15	292.23	14,525,195.29	2,092,907.12	39° 59' 11.076 N	109° 23' 4.765 W
4,400.00	0.00	0.00	4,264.54	-835.15	292.23	14,525,195.29	2,092,907.12	39° 59' 11.076 N	109° 23' 4.765 W
4,500.00	0.00	0.00	4,364.54	-835.15	292.23	14,525,195.29	2,092,907.12	39° 59' 11.076 N	109° 23' 4.765 W
4,600.00	0.00	0.00	4,464.54	-835.15	292.23	14,525,195.29	2,092,907.12	39° 59' 11.076 N	109° 23' 4.765 W
4,700.00	0.00	0.00	4,564.54	-835.15	292.23	14,525,195.29	2,092,907.12	39° 59' 11.076 N	109° 23' 4.765 W
4,800.00	0.00	0.00	4,664.54	-835.15	292.23	14,525,195.29	2,092,907.12	39° 59' 11.076 N	109° 23′ 4.765 W
4,900.00	0.00	0.00	4,764.54	-835.15	292.23	14,525,195.29	2,092,907.12	39° 59' 11.076 N	109° 23' 4.765 W



#### SDI

#### Survey Report - Geographic



Company: Kerr McGee Oil and Gas Onshore LP

Project: Uintah County, UT UTM12

Site: NBU 922-360 PAD

Well: NBU 922-36O4BS

Wellbore: OH

Design: PLAN #1 2-7-11 RHS

Local Co-ordinate Reference:

TVD Reference:

MD Reference:

Database:

Well NBU 922-36O4BS

GL 4968 & KB 4 @ 4972.00ft (ASSUMED)

GL 4968 & KB 4

@ 4972.00ft (ASSUMED)

North Reference: True

Survey Calculation Method:

Minimum Curvature
EDM5000-RobertS-Local

**Planned Survey** Measured Vertical Map Мар Depth Depth +F/-W Northing Easting Inclination +N/-S **Azimuth** (ft) (usft) (usft) (ft) (ft) (ft) Latitude Longitude (°) (°) 0.00 0.00 4,864.54 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 5,000.00 -835.15 292.23 0.00 0.00 4,964.54 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 5.100.00 -835.15 292.23 14.525.195.29 5.200.00 0.00 0.00 5,064.54 -835.15 292.23 14.525.195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 5,300.00 0.00 0.00 5,164.54 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 5.400.00 0.00 5.264.54 292.23 39° 59' 11.076 N 109° 23' 4.765 W 0.00 -835.1514,525,195.29 2.092.907.12 5,500.00 0.00 0.00 5,364.54 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 5,600.00 0.00 0.00 5,464.54 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 109° 23' 4.765 W 5.700.00 0.00 0.00 5.564.54 -835.15292.23 14.525.195.29 2.092.907.12 39° 59' 11.076 N 5,800.00 0.00 0.00 5,664.54 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 5,900.00 0.00 0.00 5,764.54 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 6,000.00 0.00 0.00 5.864.54 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 6,100.00 0.00 0.00 5,964.54 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 6,064.54 292.23 2,092,907.12 109° 23' 4.765 W 6,200.00 0.00 0.00 -835.15 14,525,195.29 39° 59' 11.076 N 6,300.00 0.00 0.00 6,164.54 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 0.00 6,264.54 292.23 39° 59' 11.076 N 109° 23' 4.765 W 6.400.00 0.00 -835.15 14.525.195.29 2.092.907.12 6.468.46 0.00 0.00 6,333.00 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W MESAVERDE 0.00 0.00 6,364.54 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 6.500.00 -835.156,600.00 0.00 0.00 6,464.54 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 6.700.00 0.00 0.00 6.564.54 -835.15 292.23 14,525,195.29 2.092.907.12 39° 59' 11.076 N 109° 23' 4.765 W 6,800.00 0.00 0.00 6.664.54 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 6,900.00 0.00 0.00 6,764.54 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 14.525,195.29 109° 23' 4.765 W 7.000.00 0.00 0.00 6.864.54 -835.15292.23 2,092,907.12 39° 59' 11.076 N 7,100.00 0.00 0.00 6,964.54 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 7,200.00 0.00 0.00 7,064.54 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 7.300.00 292.23 14,525,195.29 109° 23' 4.765 W 0.00 0.00 7.164.54 -835.152,092,907.12 39° 59' 11.076 N 7,400.00 0.00 0.00 7,264.54 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 0.00 0.00 7,364.54 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 7,500.00 7,600.00 0.00 0.00 7.464.54 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 0.00 0.00 7,564.54 -835.15 292.23 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 7.700.00 14.525.195.29 7.800.00 0.00 0.00 7.664.54 -835.15 292.23 14.525.195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 7,900.00 0.00 0.00 7,764.54 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 8.000.00 0.00 0.00 7.864.54 -835.15 292.23 14,525,195.29 39° 59' 11.076 N 109° 23' 4.765 W 2.092.907.12 8,100.00 0.00 0.00 7.964.54 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 8,200.00 0.00 0.00 8,064.54 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 109° 23' 4.765 W 8,300.00 0.00 0.00 8.164.54 -835.15292.23 2,092,907.12 39° 59' 11.076 N 14,525,195.29 8,400.00 0.00 0.00 8,264.54 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 8,500.00 0.00 0.00 8,364.54 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W 8.464.54 109° 23' 4.765 W 8.600.00 0.00 0.00 -835.15292.23 14,525,195.29 2.092.907.12 39° 59' 11.076 N 8.695.46 0.00 0.00 8,560.00 -835.15 292.23 14,525,195.29 2,092,907.12 39° 59' 11.076 N 109° 23' 4.765 W TD at 8695.46 - PBHL\_NBU 922-36O4BS

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
PBHL_NBU 922-36O4B	ter	0.00	8,560.00	-835.15	292.23	14,525,195.29	2,092,907.12	39° 59' 11.076 N	109° 23' 4.765 W



# SDI

#### Survey Report - Geographic



Kerr McGee Oil and Gas Onshore LP Company:

Uintah County, UT UTM12 Project:

NBU 922-360 PAD

Well: NBU 922-36O4BS

Wellbore:

Design: PLAN #1 2-7-11 RHS Local Co-ordinate Reference:

**TVD Reference:** 

MD Reference: North Reference: Well NBU 922-36O4BS

GL 4968 & KB 4

@ 4972.00ft (ASSUMED) GL 4968 & KB 4

@ 4972.00ft (ASSUMED)

True

**Survey Calculation Method:** Database:

Minimum Curvature EDM5000-RobertS-Local

**Casing Points** 

Site:

Vertical Measured Casing Hole Depth Diameter Diameter Depth (ft) (ft) (in) (in) Name

2,264.34 2,186.00 8 5/8" 8.625 11.000

**Formations** 

Measured Vertical Dip Depth Depth Direction Dip (ft) (ft) Name Lithology (°) (°) 1,111.82 1,101.00 GREEN RIVER 4,299.46 4,164.00 WASATCH 6,468.46 6,333.00 MESAVERDE

Plan Annotations				
Measu	red Vertica	al Local	Coordinates	
Dept (ft)	h Depth (ft)	+N/-S (ft)	+E/-W (ft)	Comment
, ,		300 (		0 Start Build 2.00
		280 -163		
	2877 2	761 -672	2 23	5 Start Drop -2.00
;	3877 3	741 -835	29	2 Start 4818.74 hold at 3876.71 MD
8	8695 8	560 -835	29	2 TD at 8695.46

Checked By:	Approved By:	Da	ate:

#### **NBU 922-36J1CS**

Surface: 1247' FSL 2113' FEL (SW/4SE/4) BHL: 2071' FSL 1809' FEL (NW/4SE/4)

#### **NBU 922-36J4BS**

Surface: 1254' FSL 2094' FEL (SW/4SE/4) BHL: 1740' FSL 1816' FEL (NW/4SE/4)

#### **NBU 922-36J4CS**

Surface: 1261' FSL 2075' FEL (SW/4SE/4) BHL: 1409' FSL 1816' FEL (NW/4SE/4)

#### NBU 922-36O1BS

Surface: 1257' FSL 2085' FEL (SW/4SE/4) BHL: 1078' FSL 1815' FEL (SW/4SE/4)

#### **NBU 922-36O4BS**

Surface: 1250' FSL 2103' FEL (SW/4SE/4) BHL: 415' FSL 1814' FEL (SW/4SE/4)

> Pad: NBU 922-360 Pad Section 36 T9S R22E Mineral Lease: ML-22650

Uintah County, Utah Operator: Kerr-McGee Oil & Gas Onshore LP

#### MULTI-POINT SURFACE USE PLAN of OPERATIONS (SUPO)

This SUPO contains surface operating procedures for Kerr-McGee Oil & Gas Onshore LP (KMG), a wholly owned subsidiary of Anadarko Petroleum Corporation (APC) pertaining to actions that involve the State of Utah School and Institutional Trust Lands Administration (SITLA) in the development of minerals leased to APC/KMG (including, but not limited to, APDs/SULAs/ROEs/ROWs and/or easements).

See associated Utah Division of Oil, Gas, and Mining (UDOGM) Form 3(s), plats, maps, and other attachments for site-specific information on projects represented herein.

In accordance with Utah Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling, these wells will be directionally drilled. Refer to Topo Map A for directions to the location and Topo Maps A and B for location of access roads within a 2-mile radius.

#### A. <u>Existing Roads</u>:

Existing roads consist of county roads and improved/unimproved lease roads. KMG will maintain existing roads in a condition that is the same as or better than before operations began and in a safe and usable

#### NBU 922-36J1CS / 36J4BS/ 36J4CS/ 36O1BS/ 36O4BS

Surface Use Plan of Operations Page 2

condition. Maintenance of existing roads will continue until final abandonment and reclamation of well pads and/or other facilities. The road maintenance may include, but is not limited to, blading, ditching, culvert installation/cleanout, surfacing, and dust control.

Typically, roads, gathering lines and electrical distribution lines will occupy common disturbance corridors and roadways will be used as working space. All disturbances located in the same corridor will overlap each other to the maximum extent possible; in no case will the maximum disturbance width of the access road and utility corridors exceed 50', unless otherwise approved.

#### B. <u>Planned Access Roads</u>:

No new access road is proposed. (see Topo Map B). Applicable Uintah County encroachment and/or pipeline crossing permits will be obtained prior to construction/development. No other pipelines will be crossed at this location.

If there are roads that are new or to be reconstructed, they will be located, designed, and maintained to meet the standards of SITLA and other commonly accepted Best Management Practices (BMPs). If a new road/corridor were to cross a water of the United States, KMG will adhere to the requirements of applicable Nationwide or Individual Permits of the Department of Army Corps of Engineers.

During the onsite, turnouts, major cut and fills, culverts, bridges, gates, cattle guards, low water crossings, or modifications needed to existing infrastructure/facilities were determined, as applicable, are typically shown on attached Exhibits and Topo maps.

#### C. <u>Location of Existing and Proposed Facilities</u>:

This pad will expand the existing pad for the NBU 922-36O. The NBU 922-36O well location is a vertical producing well according to Utah Division of Oil, Gas and Mining (UDOGM) records as of May 5, 2011.

Production facilities (see Well Pad Design Summary and Facilities Diagram):

Production facilities will be installed on the disturbed portion of the well pad and may include bermed components (typically excluding dehy's and/or separators) that contain fluids (i.e. production tanks, produced liquids tanks). The berms will be constructed of compacted subsoil or corrugated metal, impervious, designed to hold 110% of the capacity of the largest tank, and be independent of the back cut. All permanent (on-site six months or longer) above ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earth-tone color chosen at the onsite in coordination with SITLA.

Production tanks will be constructed, maintained, and operated to prevent unauthorized surface or subsurface discharges of liquids and to prevent livestock or wildlife entry. The tanks are not to be used for disposal of liquids from additional sources without prior approval of UDOGM.

#### **Gathering facilities:**

The following pipeline transmission facilities will apply if the well is productive (see Topo D):

The total gas gathering (steel line pipe with fusion bond epoxy coating) pipeline distances from the meter to the tie in point is  $\pm 2,230$ ' and the individual segments are broken up as follows:

- ±585' (0.11 miles) –New 6" buried gas pipeline from the meter to the edge of the pad. Please refer to Topo D2.
- $\pm 780$ ' (0.15 miles) –New 6" buried gas pipeline from the edge of pad to tie-in to the proposed 16" buried gas pipeline at the 36G intersection. Please refer to Topo D.
- ±865' (0.16 miles) –New 16" buried gas pipeline from the proposed 36G intersection to the proposed 36K intersection. Please refer to Topo D.

The total liquid gathering pipeline distance from the separator to the tie in point is  $\pm 2,340$ ' and the individual segments are broken up as follows:

- ±585' (0.11 miles) –New 6" buried liquid pipeline from the separator to the edge of the pad. Please refer to Topo D2.
- ±395' (0.07 miles) –New 6" buried liquid pipeline from the edge of pad to the East Jr. Compressor intersection. Please refer to Topo D2.
- ±385' (0.07 miles) –New 6" buried liquid pipeline from the East Jr. Compressor intersection to tie-in to the proposed 6" buried liquid pipeline at the 36G intersection. Please refer to Topo D.
- ±865' (0.16 miles) –New 6" buried liquid pipeline from the proposed 36G intersection to the proposed 36K intersection. Please refer to Topo D.
- $\pm 110$ ' (0.02 miles) –New 6" buried liquid pipeline from the East Jr. Compressor to the road intersection. Please refer to Topo D2.

The liquid gathering lines will be made of polyethylene or a composite polyethylene/steel or polyethylene/fiberglass that is not subject to internal or external pipe corrosion. The content of the produced fluids to be transferred by the liquid gathering system will be approximately 92% produced water and 8% condensate. Trunk line valve connections for the water gathering system will be below ground but accessible from the surface in order to prevent freezing during winter time.

The proposed pipelines will be buried and will include gas gathering and liquid gathering pipelines in the same trench. Where the pipeline is adjacent to the road or well pad, the road and/or well pad will be utilized for construction activities and staging. KMG requests a permanent 30' right-of-way adjacent to the road for life-of-project for maintenance, repairs, and/or upgrades, no additional right-of-way will be needed beyond the 30'. Where the pipeline is not adjacent to the road or well pad, KMG requests a temporary 45' construction right-of-way and 30' permanent right-of-way.

The proposed trench width for the pipeline would range from 18-48 inches and will be excavated to a depth of 48 to 60 inches of normal soil cover or 24 inches of cover in consolidated rock. During construction blasting may occur along the proposed right-of-way where trenching equipment cannot cut into the bedrock. Large debris and rocks removed from the earth during trenching and blasting that could not be returned to the trench would be distributed evenly and naturally in the project area. The proposed pipelines will be pressure tested

NBU 922-36J1CS / 36J4BS/ 36J4CS/ 36O1BS/ 36O4BS

Surface Use Plan of Operations Page 4

pneumatically (depending on size) or with fluids (either fresh or produced). If fluids are used, there will be no discharge to the surface.

Pipeline signs will be installed along the right-of-way to indicate the pipeline proximity and ownership, as well as to provide emergency contact phone numbers. Above ground valves, T's, and/or cathodic protection will be installed at various locations for connection, corrosion prevention and/or for safety purposes.

### D. <u>Location and Type of Water Supply</u>:

Water for drilling purposes will be obtained from one of the following sources:

- Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32 T4S R3E, Water User Claim number 43-8496, application number 53617.
- Price Water Pumping Inc. Green River and White River, various sources, Water Right Number 49-1659, application number: a35745.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

#### **E.** Source of Construction Materials:

Construction operations will typically be completed with native materials found on location. If needed, construction materials that must be imported to the site (mineral material aggregate, soils or materials suitable for fill/surfacing) will be obtained from a nearby permitted source and described in subsequent Sundry requests. No construction materials will be removed from State lands without prior approval from SITLA.

#### F. Methods of Handling Waste Materials:

Should the well be productive, produced water will be contained in a water tank and will be transported by pipeline and/or truck to an approved disposal sites facilities and/or Salt Water Disposal (SWD) injection well. Currently, those facilities are:

RNI in Sec. 5 T9S R22E

Ace Oilfield in Sec. 2 T6S R20E MC&MC in Sec. 12 T6S R19E Pipeline Facility in Sec. 36 T9S R20E

Goat Pasture Evaporation Pond in SW/4 Sec. 16 T10S R22E

Bonanza Evaporation Pond in Sec. 2 T10S R23E

Ouray #1 SWD in Sec. 1 T9S R21E NBU 159 SWD in Sec. 35 T9S R21E CIGE 112D SWD in Sec. 19 T9S R21E

NBU 922-36J1CS / 36J4BS/ 36J4CS/ 36O1BS/ 36O4BS

Surface Use Plan of Operations Page 5

CIGE 114 SWD in Sec. 34 T9S R21E NBU 921-34K SWD in Sec. 34 T9S R21E NBU 921-33F SWD in Sec. 33 T9S R21E NBU 921-34L SWD in Sec. 34 T9S R21E

Drill cuttings and/or fluids will be contained in the reserve/frac pit. Cuttings will be buried in pit(s) upon closure. Unless otherwise approved, no oil or other oil-based drilling additives, chromium/metals-based, or saline muds will be used during drilling. Only fresh water (as specified above), biodegradable polymer soap, bentonite clay, and/or non-toxic additives will be used in the mud system.

Pits will be constructed to minimize the accumulation of surface runoff. Should fluid hydrocarbons be encountered during drilling, completions or well testing, product will either be contained in test tanks on the well site or evacuated by vacuum trucks and transported to an approved disposal/sales facility. Should petroleum hydrocarbons unexpectedly be released into a pit, they will be removed as soon as practical but in no case will they remain longer than 72 hours unless an alternate is approved by SITLA. Should timely removal prove infeasible, the pit will be netted with mesh no larger than 1 inch until such time as hydrocarbons can be removed. Hydrocarbon removal will also take place prior to the closure of the pit, unless authorization is provided for disposal via alternative pit closure methods (e.g. solidification).

The reserve and/or fracture stimulation pit will be lined with a synthetic material 20-mil or thicker, The liner will be installed over smooth fill subgrade that is free of pockets, loose rocks, or other materials (i.e. sand, sifted dirt, bentonite, straw, etc.) that could damage the liner. Any additional pits necessary for subsequent operations, such as temporary flare or workover pits, will be contained within the originally approved well pad and disturbance boundaries. Such temporary pits will be backfilled and reclaimed within 180 days of completion of work at a well location.

For the protection of livestock and wildlife, all open pits and cellars will be fenced/covered to prevent wildlife or livestock entry. Total height of pit fencing will be at least 42 inches and corner posts will be cemented and/or braced in such a manner as to keep the fence tight at all times. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

Pits containing drilling cuttings, mud, and/or completions fluids will be allowed to dry. Any free fluids remaining after six (6) months from reaching total depth, date of completion, and/or determination of inactivity will be removed (as weather conditions allow) to an approved site and the pit reclaimed. Additional drying methods may include fly-ash solidification or sprinkler evaporation. Installation and operation of any sprinklers, pumps, and equipment will ensure that water spray or mist does not drift. Reserve pit liners will be cut off or folded as near to the mud surface as possible and as safety considerations allow and buried on location.

No garbage or non-exempt substances as defined by Resource Conservation and Recovery Act (RCRA)

# NBU 922-36J1CS / 36J4BS/ 36J4CS/ 36O1BS/ 36O4BS

Surface Use Plan of Operations Page 6

subtitle C will be placed in the reserve pit. All refuse generated during construction, drilling, completion, and well testing activities will be contained in an enclosed receptacle, removed from the drill locations promptly, and transported to an approved disposal facility.

Portable, self-contained chemical toilets and/or sewage processing facilities will be provided for human waste disposal. Upon completion of operations, or as required, the toilet holding tanks will be pumped and the contents disposed of in an approved sewage disposal facility. All applicable regulations pertaining to disposal of human and solid waste will be observed.

Any undesirable event, including accidental release of fluids, or release in excess of reportable quantities, will be managed according to the notification requirements of UDOGMs "Reporting Oil and Gas Undesirable Events" rule. Where State wells are participatory to a Federal agreement, according to NTL-3A, the appropriate Federal agencies will be notified.

# **Materials Management**

Hazardous materials above reportable quantities will not be produced by drilling or completing proposed wells or constructing the pipelines/facilities. The term "hazardous materials" as used here means: (1) any substance, pollutant, or containment listed as hazardous under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) of 1980, as amended 42 U.S.C. 9601 et seq., and the regulations issued under CERCLA; and (2) any hazardous waste as defined in RCRA of 1976, as amended. In addition, no extremely hazardous substance, as defined in 40 CFR 355, in threshold planning quantities, would be used, produced, stored, transported, or disposed of while producing any well.

Chemicals subject to reporting under Title III of the Superfund Amendments and Reauthorization Act (SARA) in quantities of 10,000 pounds or more may be produced and/or stored at production facilities and may be kept in limited quantities on drilling sites and well locations for short periods of time during drilling or completion activities.

# G. Ancillary Facilities:

None are anticipated.

# H. Well Site Layout (see Well Pad Design Summary):

The location, orientation and aerial extent of each drill pad, reserve/completion/flare pit, access road ingress/egress points, drilling rig, dikes/ditches, existing wells/infrastructure, proposed cuts and fills, and topsoil and spoil material stockpile locations are depicted on the exhibits for each project where applicable. Site-specific conditions may require slight deviation in actual equipment and facility layout; however, the area of disturbance, as described in the survey, will not be exceeded.

# NBU 922-36J1CS / 36J4BS/ 36J4CS/ 36O1BS/ 36O4BS

Surface Use Plan of Operations Page 7

Coordinates are provided in the National Spatial Reference System, North American Datum, 1927 (NAD27) or latest edition. Distances are depicted on each plat to the nearest two adjacent section lines.

# I. Plans for Reclamation of the Surface:

Surface reclamation will be undertaken in two phases: interim and final. Interim reclamation is conducted following well completion and extends through the period of production. This reclamation is for the area of the well pad that is not required for production activities. Final reclamation is conducted following well plugging/conversion and/or facility abandonment processes.

Reclamation activities in both phases may include but are not limited to: re-contouring or re-configuration of topographic surfaces, restoration of drainage systems, segregation of spoils materials, minimizing surface disturbance, re-evaluating backfill requirements, pit closure, topsoil redistribution, soil treatments, seeding and weed control.

#### **Interim Reclamation**

Interim reclamation includes pit closure, re-contouring (where possible), soil bed preparation, topsoil placement, seeding, and/or weed control.

Interim re-contouring involves bringing all construction material from cuts and fills back onto the well pad and site and reestablishing the natural contours where desirable and practical. Fill and stockpiled spoils no longer necessary to the operation will be spread on the cut slopes and covered with stockpiled topsoil. All stockpiled top soils will be used for interim reclamation where practical to maintain soil viability. Where possible, the land surface will be left "rough" after re-contouring to ensure that the maximum surface area will be available to support the reestablishment of vegetative cover.

A reserve pit, upon being allowed to dry, will be backfilled and compacted with cover materials that are void of any topsoil, vegetation, large stones, rocks or foreign objects. Soils that are moisture laden, saturated, or partially/completely frozen will not be used for backfill or cover. The pit area will be mounded to allow for settling and to promote positive surface drainage away from the pit.

#### **Final Reclamation**

Final reclamation will be performed for newly drilled unproductive wells and/or at the end of the life of a productive well. As soon as practical after the conclusion of drilling and testing operations, unproductive drill holes will be plugged and abandoned (P&A). Site and road reclamation will commence following plugging. In no case will reclamation at non-producing locations be initiated later than six (6) months from the date a well is plugged. A joint inspection of the disturbed area to be reclaimed may be requested by KMG. The primary purpose of this inspection will be to review the existing conditions, or agree upon a revised final reclamation and abandonment plan. A Notice of Intent to Abandon will be filed for final recommendations regarding surface reclamation.

NBU 922-36J1CS / 36J4BS/ 36J4CS/ 36O1BS/ 36O4BS

Surface Use Plan of Operations Page 8

After plugging, all wellhead equipment that is no longer needed will be removed, and the well site will be reclaimed. Final contouring will blend with and follow as closely as practical the natural terrain and contours of the original site and surrounding areas. After re-contouring, final grading will be conducted over the entire surface of the well site and access road. Where practical, the area will be ripped to a depth of 18 to 24 inches on 18 to 24-inch centers and surface materials will be pitted with small depressions to form longitudinal depressions 12 to 18 inches deep perpendicular to the natural flow of water.

All unnecessary surface equipment and structures (e.g. cattle guards) and water control structures (e.g. culverts, drainage pipes) not needed to facilitate successful reclamation will be removed during final reclamation. Roads that will be reclaimed will be ripped to a depth of 18 inches where practical, re-contoured to approximate the original contour of the ground and seeded.

Upon successfully completing reclamation of a P&A location, a Final Abandonment Notice will be submitted to UDOGM.

# **Seeding and Measures Common to Interim and Final Reclamation**

Reclaimed areas may be fenced to exclude grazing and encourage re-vegetation.

On slopes where severe erosion can become a problem and the use of machinery is not practical, seed will be hand broadcast and raked with twice the specified amount of seed. The slope will be stabilized using materials specifically designed to prevent erosion on steep slopes and hold seed in place so vegetation can become permanently established. These materials will include, but are not limited to, erosion control blankets and bonded fiber matrix at a rate to achieve a minimum of 80 percent soil coverage.

Seeding will occur year-round as conditions allow. Seed mixes appropriate to the native plant community as determined and specified for each project location based on the site specific soils will be used for revegetation. The site specific seed mix will be provided by SITLA.

# J. <u>Surface/Mineral Ownership</u>:

SITLA 675 East 500 South, Suite 500 Salt Lake City, UT 84102

# **K.** Other Information:

None

# NBU 922-36J1CS / 36J4BS/ 36J4CS/ 36O1BS/ 36O4BS

**Surface Use Plan of Operations** 

# Page 10

#### M. Lessee's or Operators' Representative & Certification:

Gina T. Becker Regulatory Analyst II Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6086

Tommy Thompson General Manager, Drilling Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6724

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage for State lease activities is provided by State Surety Bond 22013542, and for applicable Federal lease activities and pursuant to 43 CFR 3104, by Bureau of Land Management Nationwide Bond WYB000291.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that I have full knowledge of the State and Federal laws applicable to this operation; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

May 13, 2011

Date



JOE JOHNSON LANDMAN KERR-MCGEE ONSHORE OIL & GAS, L.P. 1099 18TH STREET, SUITE 1800 DENVER, CO 80202 720-929-6708 • FAX 720-929-7708 E-MAIL: JOE.JOHNSON@ANADARKO.COM

April 13, 2011

Ms. Diana Mason Division of Oil, Gas and Mining P.O. Box 145801 Salt Lake City, UT 84114-6100

Re: Directional Drilling R649-3-11

NBU 922-36O4BS

T9S-R22E

Section 36: SWSE/SWSE Surface: 1250' FSL, 2103' FEL Bottom Hole: 415' FSL, 1814' FEL

Uintah County, Utah

Dear Ms. Mason:

Pursuant to the filing of Kerr-McGee Oil & Gas Onshore LP's (Kerr-McGee) Application for Permit to Drill regarding the above referenced well, we are hereby submitting this letter in accordance with Oil & Gas Conservation Rule R649-3-11 pertaining to the Exception to Location and Siting of Wells.


- Kerr-McGee's NBU 922-36O4BS is located within the Natural Buttes Unit area.
- Kerr-McGee is permitting this well as a directional well in order to minimize surface disturbance. Locating the well at the surface location and directionally drilling from this location, Kerr-McGee will be able to utilize the existing road and pipelines in the area.
- Furthermore, Kerr-McGee certifies that it is the sole working interest owner within 460 feet of the entire
  directional well bore.

Therefore, based on the above stated information Kerr-McGee Oil & Gas Onshore LP requests the permit be granted pursuant to R649-3-11.

Sincerely,

KERR-MCGEE OIL & GAS ONSHORE LP

Joseph D. Johnson Landman



# **United States Department of the Interior**

# **BUREAU OF LAND MANAGEMENT**

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO: 3160 (UT-922)

May 20, 2011

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2011 Plan of Development Natural Buttes Unit

Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2011 within the Natural Buttes Unit, Uintah County, Utah.

API # WELL NAME LOCATION

(Proposed PZ WASATCH-MESA VERDE)

# NBU 922-36I PAD

43-047-51586	NBU	922-36H4BS BHL			_	0799 0494	
43-047-51587	NBU	922-36H4CS BHL			_	0792 0495	
43-047-51588	NBU	922-36I1CS BHL			_	0785 0494	
43-047-51589 NBU 922-36K PAI		922-36I4CS BHL			_	0805 0493	
		922-36K1BS BHL			_	1998 2148	
43-047-51591	NBU	922-36K1CS BHL				2015 2147	
43-047-51592	NBU	922-36K4BS BHL	 	 	 	2023 2147	
43-047-51593	NBU	922-36K4CS BHL				2006 2146	
43-047-51594	NBU	922-36L4CS BHL				1990 0821	

Page 2

API # WELL NAME LOCATION

(Proposed PZ WASATCH-MESA VERDE

NRII	922	-36N	PAD
NDU	JLL	-JUIN	FAU

NBU 922-36N PAI	)									
43-047-51595	NBU	922-36M1CS								
		BHL	Sec	36	T09S	R22E	0792	FSL	0816	FWL
12 047 51506	NIDII	000 201400	0	2.0	шоос	DOOR	1000	ПОТ	0070	T77.7T
43-047-51596	NBO	922-36M4CS			T095					
		рпг	sec	30	1095	RZZĒ	0132	LOL	0019	ГWL
43-047-51597	NRII	922-36N1BS	Sec	36	тпас	B22F	1088	FSI.	2379	FWT.
15 017 51557	INDO				T09S					
		2112	200	0 0	1030	11222	1200			
43-047-51598	NBU	922-36N4CS	Sec	36	T09S	R22E	1048	FSL	2379	FWL
		BHL	Sec	36	T09S	R22E	0190	FSL	2081	FWL
43-047-51599	NBU	922-3604CS	Sec	36	T09S	R22E	1058	FSL	2379	FWL
		BHL	Sec	36	T09S	R22E	0085	FSL	1814	FEL
NBU 922-360 PAI		000 007100	~	2.6	<b>TO 0 0</b>	D000	1045		0110	
43-04/-51600	NBU	922-36J1CS								
		RHT	sec	36	T09S	RZZE	2071	FSL	1809	FEL
13-017-51601	MRII	922-36J4BS	Sac	36	т∩ас	D22F	125/	FCI	2094	FFT
15 017 51001	INDO				T09S			_		
		DIIL	500	00	1030	11221	1,10	101	1010	
43-047-51602	NBU	922-36J4CS	Sec	36	T09S	R22E	1261	FSL	2075	FEL
		BHL	Sec	36	T09S	R22E	1409	FSL	1816	FEL
43-047-51603	NBU	922-3601BS	Sec	36	T09S	R22E	1257	FSL	2085	FEL
		BHL	Sec	36	T09S	R22E	1078	FSL	1815	FEL
43-047-51604	NBU	922-3604BS								
NDU 022 26D DAE	•	BHT	Sec	36	T09S	RZZE	0415	FSL	1814	FEL
NBU 922-36P PAI		922-36P1BS	202	36	π∩аς	D22F	1207	ECT	0606	CCT
45 047 51005	NDO				T09S					
		5115	DCC	50	1036	11221	1215	101	0195	1 1111
43-047-51606	NBU	922-36P1CS	Sec	36	T09S	R22E	1198	FSL	0611	FEL
		BHL	Sec	36	T09S	R22E	0911	FSL	0493	FEL
43-047-51607	NBU	922-36P4BS								
		BHL	Sec	36	T09S	R22E	0580	FSL	0493	FEL
10 015 51600		000 05-155	_						0.001	
43-04/-51608	NBU	922-36P4CS								
NBU 922-36B PAI	,	ВПГ	sec	36	T09S	RZZŁ	0243	FSL	0492	FEL
		922-36A1CS	Sec	36	T095	R22E	0678	FNT.	2273	FEI.
15 01, 51009	14110				T09S					
		2112		- 0					1	
43-047-51610	NBU	922-36B1CS	Sec	36	T09S	R22E	0674	FNL	2282	FEL
		BHL	Sec	36	T09S	R22E	0579	FNL	1821	FEL
43-047-51611	NBU	922-36B4BS								
		BHL	Sec	36	T09S	R22E	0905	Ŀ'NL	1828	Ͱ'EL

Page 3

API # WELL NAME LOCATION (Proposed PZ WASATCH-MESA VERDE BHL Sec 36 T09S R22E 1439 FNL 1861 FEL **NBU 922-36C PAD** BHL Sec 36 T09S R22E 0485 FNL 2152 FWL 43-047-51614 NBU 922-36C4BS Sec 36 T09S R22E 0706 FNL 1749 FWL BHL Sec 36 T09S R22E 0746 FNL 2153 FWL 43-047-51615 NBU 922-36F1BS Sec 36 T09S R22E 0718 FNL 1765 FWL BHL Sec 36 T09S R22E 1407 FNL 2151 FWL BHL Sec 36 T09S R22E 1738 FNL 2150 FWL **NBU 922-36D PAD** BHL Sec 36 T09S R22E 0579 FNL 0825 FWL 43-047-51618 NBU 922-36D4BS Sec 36 T09S R22E 1060 FNL 0971 FWL BHL Sec 36 T09S R22E 0910 FNL 0825 FWL 43-047-51619 NBU 922-36D4CS Sec 36 T09S R22E 1064 FNL 0990 FWL BHL Sec 36 T09S R22E 1241 FNL 0825 FWL 43-047-51620 NBU 922-36E1BS Sec 36 T09S R22E 1067 FNL 1000 FWL BHL Sec 36 T09S R22E 1572 FNL 0825 FWL **NBU 922-36E PAD** BHL Sec 36 T09S R22E 1903 FNL 0824 FWL BHL Sec 36 T09S R22E 2245 FNL 0818 FWL BHL Sec 36 T09S R22E 2565 FNL 0824 FWL BHL Sec 36 T09S R22E 2401 FSL 0824 FWL **NBU 922-36G3 PAD** 43-047-51625 NBU 922-36F4BS Sec 36 T09S R22E 2414 FNL 2443 FEL BHL Sec 36 T09S R22E 2070 FNL 2149 FWL 43-047-51626 NBU 922-36F4CS Sec 36 T09S R22E 2424 FNL 2445 FEL BHL Sec 36 T09S R22E 2401 FNL 2149 FWL 43-047-51627 NBU 922-36G4BS Sec 36 T09S R22E 2405 FNL 2441 FEL BHL Sec 36 T09S R22E 2235 FNL 1818 FEL 

BHL Sec 36 T09S R22E 2566 FNL 1818 FEL

Page 4

This office has no objection to permitting the wells at this time.

Digitally signed by Michael L. Coulthard Michael L. Coulthard

Management, ou=Branch of Minerals, email=Michael\_Coulthard@blm.gov, c=US
Date: 2011.05.23 07:16:05 -06'00'

bcc: File - Natural Buttes Unit

Division of Oil Gas and Mining

Central Files Agr. Sec. Chron Fluid Chron

MCoulthard:mc:5-20-11

From: Jim Davis

To: Bonner, Ed; Garrison, LaVonne; Hill, Brad; Mason, Diana

CC: Gina Becker; Lytle, Andy Date: 6/8/2011 3:00 PM

**Subject:** Kerr McGee APD approvals.

The following APDs have been approved by SITLA including arch and paleo clearance.

```
4304751586
             NBU 922-36H4BS
4304751587
             NBU 922-36H4CS
4304751588
             NBU 922-36I1CS
4304751589
             NBU 922-36I4CS
4304751590
             NBU 922-36K1BS
4304751591
             NBU 922-36K1CS
4304751592
             NBU 922-36K4BS
4304751593
             NBU 922-36K4CS
4304751594
             NBU 922-36L4CS
4304751595
             NBU 922-36M1CS
4304751596
             NBU 922-36M4CS
4304751597
             NBU 922-36N1BS
             NBU 922-36N4CS
4304751598
4304751599
             NBU 922-36O4CS
4304751600
             NBU 922-36J1CS
             NBU 922-36J4BS
4304751601
4304751602
             NBU 922-36J4CS
4304751603
             NBU 922-3601BS
4304751604
             NBU 922-36O4BS
4304751605
             NBU 922-36P1BS
4304751606
             NBU 922-36P1CS
4304751607
             NBU 922-36P4BS
4304751608
             NBU 922-36P4CS
4304751613
             NBU 922-36C1CS
4304751614
             NBU 922-36C4BS
4304751615
             NBU 922-36F1BS
             NBU 922-36F1CS
4304751616
             NBU 922-36D1CS
4304751617
4304751618
             NBU 922-36D4BS
4304751619
             NBU 922-36D4CS
4304751620
             NBU 922-36E1BS
4304751621
             NBU 922-36E1CS
4304751622
             NBU 922-36E4BS
4304751623
             NBU 922-36E4CS
4304751624
             NBU 922-36L1BS
4304751625
             NBU 922-36F4BS
4304751626
             NBU 922-36F4CS
4304751627
             NBU 922-36G4BS
4304751628
             NBU 922-36G4CS
```

Full paleo monitoring is a required condition for the approval of these APDs- as recommended in the paleo report.

```
4304751609 NBU 922-36A1CS
4304751610 NBU 922-36B1CS
4304751611 NBU 922-36B4BS
4304751612 NBU 922-36G1BS
```

Thanks.

-Jim


Jim Davis Utah Trust Lands Administration jimdavis1@utah.gov Phone: (801) 538-5156

# BOPE REVIEW KERR-MCGEE OIL & GAS ONSHORE, L.P. NBU 922-36O4BS 43047516040000

Well Name		KERR-MCGEE	OIL & GAS ONS	HORE, L.P. NB	U 922-36O4BS				
String		Surf	Prod						
Casing Size(")		8.625	4.500						
Setting Depth (TVD)		2116	8560						
Previous Shoe Setting Dept	th (TVD)	80	2116						
Max Mud Weight (ppg)		8.4	12.5						
BOPE Proposed (psi)		500	5000						
Casing Internal Yield (psi)		3390	7780						
Operators Max Anticipated	d Pressure (psi)	5478	12.3						
Calculations	Surf	String		8.625					
Max BHP (psi)	Suri		ng Depth*MW						
<b>u</b> /				1 224	BOPE Ade	equate For Drilling And Setting Casing at Depth?			
MASP (Gas) (psi)	Max	BHP-(0.12*	Setting Depth)	670	NO	air drill			
MASP (Gas/Mud) (psi)	Max	BHP-(0.22*5	Setting Depth)	458	YES	Ok			
					*Can Full	Expected Pressure Be Held At Previous Shoe?			
Pressure At Previous Shoe	Max BHP22*(Setting De	epth - Previou	s Shoe Depth)	476	NO	Reasonable for area			
Required Casing/BOPE Te	est Pressure=			2116	psi				
*Max Pressure Allowed @	Previous Casing Shoe=			80	psi *Ass	psi *Assumes 1psi/ft frac gradient			
Calculations	D.,	I C4		4,500					
Max BHP (psi)	Proc	1 String	ng Depth*MW						
мах він (ря)		.032 30111	ig Depui WW	5564	ROPE Ada	quate For Drilling And Setting Casing at Depth?			
MASP (Gas) (psi)	Max	BHP-(0.12*5	Setting Depth)	4537	YES YES	quare For Drining And Setting Casing at Depth.			
MASP (Gas/Mud) (psi)			Setting Depth)	1001	YES	ОК			
		(4,122		3061		Expected Pressure Be Held At Previous Shoe?			
Pressure At Previous Shoe	Max BHP22*(Setting De	epth - Previou	s Shoe Depth)	4146	NO	Reasonable			
Required Casing/BOPE Te	est Pressure=			5000	psi				
*Max Pressure Allowed @	Previous Casing Shoe=			2116	psi *Ass	umes 1psi/ft frac gradient			
Calmatiana		. •							
Calculations  Max BHP (psi)	S	tring 052*Sattir	ng Depth*MW		-				
мах він (ря)		.032 30111	ig Depui Wiw	<u> </u>	ROPE Ade	quate For Drilling And Setting Casing at Depth?			
MASP (Gas) (psi)	Max	BHP-(0.12*5	Setting Depth)	-	NO	quare for 21 ming 1 ma seeiing cusing at 2 span			
MASP (Gas/Mud) (psi)			Setting Depth)		NO				
, , ,		<u> </u>			'	Expected Pressure Be Held At Previous Shoe?			
Pressure At Previous Shoe	Max BHP22*(Setting De	epth - Previou	s Shoe Depth)		NO				
Required Casing/BOPE Te	est Pressure=				psi				
*Max Pressure Allowed @ Previous Casing Shoe=				psi *Ass	umes 1psi/ft frac gradient				
Calculations	S	tring			"				
Max BHP (psi)			ng Depth*MW		i				
W** /			C r	<u> </u>	BOPE Ade	equate For Drilling And Setting Casing at Depth?			
MASP (Gas) (psi)	Max	BHP-(0.12*5	Setting Depth)		NO				
MASP (Gas/Mud) (psi)	Max	BHP-(0.22*5	Setting Depth)	=	NO				
,		•		I.	<u> </u>	Expected Pressure Be Held At Previous Shoe?			
Pressure At Previous Shoe	Max BHP22*(Setting De	epth - Previou	s Shoe Depth)		NO				
Required Casing/BOPE Test Pressure=					psi				

*Max Pressure Allowed @ Previous Casing Shoe=	psi	*Assumes 1psi/ft frac gradient

# 43047516040000 NBU 922-36O4BS



Well name:

43047516040000 NBU 922-36O4BS

Operator:

KERR-MCGEE OIL & GAS ONSHORE, L.P.

String type:

Surface

Project ID:

43-047-51604

Location:

UINTAH

COUNTY

Minimum design factors: **Environment:** 

1.00

1.80 (J)

1.70 (J)

1.60 (J)

Collapse

Design parameters:

Mud weight: 8.400 ppg Design is based on evacuated pipe.

Collapse: Design factor 1.125

H2S considered? No 74 °F Surface temperature: 104 °F Bottom hole temperature:

Temperature gradient: 1.40 °F/100ft Minimum section length: 100 ft

Burst:

Design factor

Cement top:

1.082 ft

**Burst** 

Max anticipated surface

No backup mud specified.

pressure: Internal gradient:

Calculated BHP

1,927 psi 0.120 psi/ft

2,181 psi

Buttress:

Premium:

8 Round STC:

8 Round LTC:

Tension:

1.50 (J) Body yield: 1.50 (B)

Tension is based on air weight. Neutral point: 1,911 ft Directional Info - Build & Drop

Kick-off point 300 ft Departure at shoe: 477 ft

Maximum dogleg: 2 °/100ft 20° Inclination at shoe:

Re subsequent strings:

Next setting depth:

8,695 ft Next mud weight: 12.500 ppg Next setting BHP: 5,646 psi Fracture mud wt: 19.250 ppg

Fracture depth: Injection pressure: 2,190 ft 2,190 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	2190	8.625	28.00	I-55	LT&C	2116	2190	7.892	86724
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	923	1880	2.036	2181	3390	1.55	59.3	348	5.87 J

Prepared

Helen Sadik-Macdonald Div of Oil, Gas & Mining

Phone: 801 538-5357 FAX: 801-359-3940

Date: July 20,2011 Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 2116 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Well name:

43047516040000 NBU 922-36O4BS

Operator:

KERR-MCGEE OIL & GAS ONSHORE, L.P.

COUNTY

String type:

Project ID:

Production

Location:

UINTAH

43-047-51604

Design parameters:

Collapse

Mud weight: 12.500 ppg Design is based on evacuated pipe.

Minimum design factors:

Collapse:

Design factor 1.125 **Environment:** 

H2S considered? No 74 °F Surface temperature: Bottom hole temperature: 194 °F

Temperature gradient: 1.40 °F/100ft

Minimum section length:

100 ft

Burst:

Design factor 1.00 Cement top:

820 ft

**Burst** 

Max anticipated surface

pressure: Internal gradient: 3,675 psi 0.220 psi/ft

Calculated BHP 5,558 psi

No backup mud specified.

**Tension:** 

8 Round STC: 1.80 (J) 8 Round LTC: 1.80 (J) Buttress: 1.60 (J) 1.50 (J)

Premium: Body yield:

Directional Info - Build & Drop

Kick-off point 300 ft Departure at shoe: 885 ft Maximum dogleg: 2 °/100ft

Inclination at shoe:

0°

Tension is based on air weight.

Neutral point:

7,096 ft

1.60 (B)

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	8695	4.5	11.60	I-80	LT&C	8560	8695	3.875	114774
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	5558	6360	1.144	5558	7780	1.40	99.3	212	2.14 J

Prepared

Helen Sadik-Macdonald Div of Oil, Gas & Mining

Phone: 801 538-5357 FAX: 801-359-3940

Date: July 20,2011 Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 8560 ft, a mud weight of 12.5 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

# **ON-SITE PREDRILL EVALUATION**

# Utah Division of Oil, Gas and Mining

**Operator** KERR-MCGEE OIL & GAS ONSHORE, L.P.

Well Name NBU 922-36O4BS

API Number 43047516040000 APD No 3821 Field/Unit NATURAL BUTTES

**Location: 1/4,1/4** SWSE **Sec** 36 **Tw** 9.0S **Rng** 22.0E 1250 FSL 2103 FEL

GPS Coord (UTM) 637828 4427543 Surface Owner

# **Participants**

Floyd Bartlett (DOGM), Sheila Wopsock, Lovell Young, Gina Becker, Mark Koehn, Griz Oleen (Kerr McGee), Ben Williams (UDWR) and Mitch Batty, John Slaugh (Timberline Engineering and Land Surveying).

# Regional/Local Setting & Topography

The general area is in the southeast portion of the Natural Buttes Unit, which contains the White River and rugged drainages that drain into the White River. Topography is varied and frequently dissected by short draws or washes, which become overly steep as they approach the White River breaks or rim. Distance to the White River varies from <sup>3</sup>/<sub>4</sub> mile to 2 miles. The side drainages are dry except for ephemeral flows. No seeps or springs exist in the area. An occasional pond has been constructed to supply water for livestock and antelope. Vernal, Utah is approximately 42 air miles to the northwest. Access from Vernal is approximately 45.6 road miles following Utah State, Uintah County and oilfield development roads to the location.

Five additional gas wells will be added to and directionally drilled from the NBU 922-36O pad. They are the NBU 922-36J4CS, NBU 922-36O1BS, NBU 922-36J4BS, NBU 922-36O4BS and NBU 922-36J1CS. The pad contains the existing MBU 922-36O gas well. The site is within a moderately wide cove surrounded by steep, ledgy hills on all sides except to the east. The existing pad will be reoriented and significantly enlarged in all directions. A diversion is needed on the west to continue north around the stockpile to catch the short drainage from the west. On the east, catch the drainage from the south and divert it to the east and north around the pad cutting thru the topsoil pile or relocate this pile. This area may have to be reinforced with rock. A cut of 18.8 feet occurs at Corner 6. Maximum fill is 9.2 feet at Location Corner 2. Where the pad is cut into steep side slope behind the pit, the cut slope may be left at about ½:1 to reduce the amount of cutting and disturbance. Reserve pit corner A is in 3.1 feet of fill. With the proposed 15 foot outer bench, 2 feet of freeboard, a 30-mil liner and the spoils placed along this side, it should be stable. The existing pad shows no stability problems. Although significant excavation is required for enlarging the pad, no stability concerns exist. The selected site is the only suitable location in the immediate area.

Both the surface and minerals are owned by SITLA.

# Surface Use Plan

**Current Surface Use** 

Grazing Wildlfe Habitat Existing Well Pad

New Road Miles Well Pad Src Const Material Surface Formation

0 Width 352 Length 465 Onsite UNTA

**Ancillary Facilities** N

#### Waste Management Plan Adequate?

# **Environmental Parameters**

8/3/2011 Page 1

# Affected Floodplains and/or Wetlands N

#### Flora / Fauna

Area beyond the existing pad is poorly vegetated with blue bunch wheatgrass, Indian ricegrass. greasewood, cheatgrass, black sagebrush, broom snakeweed, globemallow, Sitanion hystrix, shadscale, rabbitbrush, loco weed, pepper weed, halogeton and annuals.

Sheep, deer, antelope, coyote, and other small mammals and birds.

# Soil Type and Characteristics

Soils are shallow and rocky. Soils are shallow and rocky.

**Erosion Issues** Y

**Sedimentation Issues** Y

Site Stability Issues N

**Drainage Diverson Required?** Y

Berm Required? N

**Erosion Sedimentation Control Required?** Y

Paleo Survey Run? Y Paleo Potental Observed? N Cultural Survey Run? Y Cultural Resources? N

#### **Reserve Pit**

Site-Specific Factors	Site R		
Distance to Groundwater (feet)	100 to 200	5	
Distance to Surface Water (feet)	>1000	0	
Dist. Nearest Municipal Well (ft)	>5280	0	
Distance to Other Wells (feet)		20	
Native Soil Type	Mod permeability	10	
Fluid Type	Fresh Water	5	
Drill Cuttings	Normal Rock	0	
<b>Annual Precipitation (inches)</b>		0	
Affected Populations			
<b>Presence Nearby Utility Conduits</b>	Not Present	0	
	Final Score	40	1 Sensitivity Level

# **Characteristics / Requirements**

The reserve pit is planned mostly in an area of cut in the southeast side of the location. Dimensions are 100' x 260' x 12' deep with 2' of freeboard. Corner A is within 3.4 feet of fill. With the proposed 15 foot outer bench, 2 feet of freeboard, a 30-mil liner and the spoils placed along this side, it should be stable.

Closed Loop Mud Required? N Liner Required? Y Liner Thickness 30 Pit Underlayment Required? N

# **Other Observations / Comments**

8/3/2011 Page 2

Floyd Bartlett 5/24/2011 **Evaluator Date / Time** 

8/3/2011 Page 3

# **Application for Permit to Drill Statement of Basis**

8/3/2011 Utah Division of Oil, Gas and Mining

Page 1

APD No	API WellNo			State	us W	ell Type	Surf Own	er CBM
3821	43047516040	000		SITI	LA G	W	S	No
Operator	KERR-MCGI	EE OIL &	GAS	S ONSHORE	E, L.P. Su	ırface Owner-APD		
Well Name	NBU 922-360	O4BS			Uı	nit	NATURA	L BUTTES
Field	NATURAL E	BUTTES			T	ype of Work	DRILL	
Location	SWSE 36	9S 22E	S	1250 FSL	2103 FEL	GPS Coord (UTM)	637816E	4427542N
0 1 . 04 4	4 CD ·							

# **Geologic Statement of Basis**

Kerr McGee proposes to set 2,190' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 3,200'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the proposed location. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. The production casing cement should be brought up above the base of the moderately saline ground water in order to isolate it from fresher waters up hole. The proposed casing and cement should adequately protect any usable ground water.

Brad Hill 6/21/2011 **APD Evaluator Date / Time** 

# **Surface Statement of Basis**

Floyd Bartlett (DOGM), Sheila Wopsock, Lovell Young, Gina Becker, Mark Koehn, Griz Oleen (Kerr McGee), Ben Williams (UDWR) and Mitch Batty, John Slaugh (Timberline Engineering and Land Surveying).

The general area is in the southeast portion of the Natural Buttes Unit, which contains the White River and rugged drainages that drain into the White River. Topography is varied and frequently dissected by short draws or washes, which become overly steep as they approach the White River breaks or rim. Distance to the White River varies from <sup>3</sup>/<sub>4</sub> mile to 2 miles. The side drainages are dry except for ephemeral flows. No seeps or springs exist in the area. An occasional pond has been constructed to supply water for livestock and antelope. Vernal, Utah is approximately 42 air miles to the northwest. Access from Vernal is approximately 45.6 road miles following Utah State, Uintah County and oilfield development roads to the location.

Five additional gas wells will be added to and directionally drilled from the NBU 922-36O pad. They are the NBU 922-36J4CS, NBU 922-36O1BS, NBU 922-36J4BS, NBU 922-36O4BS and NBU 922-36J1CS. The pad contains the existing MBU 922-36O gas well. The site is within a moderately wide cove surrounded by steep, ledgy hills on all sides except to the east. The existing pad will be reoriented and significantly enlarged in all directions. A diversion is needed on the west to continue north around the stockpile to catch the short drainage from the west. On the east, catch the drainage from the south and divert it to the east and north around the pad cutting thru the topsoil pile or relocate this pile. This area may have to be reinforced with rock. A cut of 18.8 feet occurs at Corner 6. Maximum fill is 9.2 feet at Location Corner 2. Where the pad is cut into steep side slope behind the pit, the cut slope may be left at about ½:1 to reduce the amount of cutting and disturbance. Reserve pit corner A is in 3.1 feet of fill. With the proposed 15 foot outer bench, 2 feet of freeboard, a 30-mil liner and the spoils placed along this side, it should be stable. The existing pad shows no stability problems. Although significant excavation is required for enlarging the pad, no stability concerns exist. The selected site is the only suitable location in the immediate area.

Both the surface and minerals are owned by SITLA. Ed Bonner and Jim Davis of SITLA were invited to attend the pre-site evaluation. Neither attended. SITLA is to be contacted for reclamation standards including a seed

# **Application for Permit to Drill Statement of Basis**

Utah Division of Oil, Gas and Mining

Page 2

mix to be used.

8/3/2011

Ben Williams of the Utah Division of Wildlife Resources attended the pre-site. Mr. Williams stated no wildlife values would be significantly affected by drilling and operating the additional wells at this location.

Floyd Bartlett 5/24/2011
Onsite Evaluator Date / Time

#### Conditions of Approval / Application for Permit to Drill

COMMISSIONS OF FEB	province in the second
Category	Condition
Pits	A synthetic liner with a minimum thickness of 30 mils with a double felt subliner shall be properly installed and maintained in the reserve pit.
Surface	Drainages adjacent to the proposed pad shall be diverted around the location. A diversion is needed on the west to continue north around the stockpile to catch the short drainage from the west. On the east, catch the drainage from the south and divert it to the east and north around the pad cutting thru the topsoil pile or relocate this pile.
Surface	The reserve pit shall be fenced upon completion of drilling operations.

# WORKSHEET APPLICATION FOR PERMIT TO DRILL

**APD RECEIVED:** 5/14/2011 **API NO. ASSIGNED:** 43047516040000

WELL NAME: NBU 922-3604BS

**OPERATOR:** KERR-MCGEE OIL & GAS ONSHORE, L.P. (N2995) **PHONE NUMBER:** 720 929-6086

**CONTACT:** Gina Becker

PROPOSED LOCATION: SWSE 36 090S 220E **Permit Tech Review:** 

> SURFACE: 1250 FSL 2103 FEL **Engineering Review:**

> **BOTTOM:** 0415 FSL 1814 FEL Geology Review:

**COUNTY: UINTAH** 

**LATITUDE: 39.98872 LONGITUDE:** -109.38582

**UTM SURF EASTINGS: 637816.00** NORTHINGS: 4427542.00

FIELD NAME: NATURAL BUTTES

LEASE TYPE: 3 - State

LEASE NUMBER: ML-22650 PROPOSED PRODUCING FORMATION(S): WASATCH-MESA VERDE

**SURFACE OWNER: 3 - State COALBED METHANE: NO** 

**RECEIVED AND/OR REVIEWED: LOCATION AND SITING:** 

✓ PLAT R649-2-3.

Unit: NATURAL BUTTES Bond: STATE/FEE - 22013542

**Potash** R649-3-2. General

Oil Shale 190-5

Oil Shale 190-3 R649-3-3. Exception

**Drilling Unit** Oil Shale 190-13

Board Cause No: Cause 173-14 Water Permit: Permit #43-8496

**Effective Date:** 12/2/1999 **RDCC Review:** 

Siting: Suspends General Siting **Fee Surface Agreement** 

✓ Intent to Commingle R649-3-11. Directional Drill


**Commingling Approved** 

**Comments:** Presite Completed

Stipulations:

3 - Commingling - ddoucet 5 - Statement of Basis - bhill 15 - Directional - dmason 17 - Oil Shale 190-5(b) - dmason 25 - Surface Casing - hmacdonald

API Well No: 43047516040000



# State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

# **Permit To Drill**

\*\*\*\*\*

Well Name: NBU 922-36O4BS **API Well Number:** 43047516040000

Lease Number: ML-22650 Surface Owner: STATE Approval Date: 8/3/2011

#### **Issued to:**

KERR-MCGEE OIL & GAS ONSHORE, L.P., P.O. Box 173779, Denver, CO 80217

# **Authority:**

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 173-14. The expected producing formation or pool is the WASATCH-MESA VERDE Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

#### **Duration:**

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

# **Commingle:**

In accordance with Board Cause No. 173-14, commingling of the production from the Wasatch formation and the Mesaverde formation in this well is allowed.

#### General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

# **Conditions of Approval:**

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operators shall ensure that the surface and or production casing is properly cemented over the entire oil shale section as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the division.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Surface casing shall be cemented to the surface.

API Well No: 43047516040000

# **Additional Approvals:**

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan contact Dustin Doucet
- Significant plug back of the well contact Dustin Doucet
- Plug and abandonment of the well contact Dustin Doucet

# **Notification Requirements:**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well contact Carol Daniels OR
- submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at http://oilgas.ogm.utah.gov
- 24 hours prior to testing blowout prevention equipment contact Dan Jarvis
- 24 hours prior to cementing or testing casing contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well contact Dan Jarvis

# **Contact Information:**

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 office
- Dustin Doucet 801-538-5281 office

801-733-0983 - after office hours

• Dan Jarvis 801-538-5338 - office

801-231-8956 - after office hours

# **Reporting Requirements:**

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) due within 5 days of spudding the well
- Monthly Status Report (Form 9) due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) due prior to implementation
- Written Notice of Emergency Changes (Form 9) due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) due prior to implementation
- Report of Water Encountered (Form 7) due within 30 days after completion
- Well Completion Report (Form 8) due within 30 days after completion or plugging

Approved By:

For John Rogers Associate Director, Oil & Gas

Print Form

# BLM - Vernal Field Office - Notification Form

Oper	ator KERR-McGEE OIL & GA	<u>S</u> Rig Name	e/# BUCK	KET RIG				
Submitted By ANDY LYTLE Phone Number 720.929.6100								
	Name/Number NBU 922-36C							
	Qtr <u>swse</u> Section 36		is R	ange 22F				
• •	e Serial Number ML 22650		<u>· · · · · · · · · · · · · · · · · · · </u>	<u> </u>				
	Number 4304751604			101				
WLI I	4304751604							
Spuc	<u>l Notice</u> – Spud is the initial	spudding o	f the wel	ll, not drilling				
out b	pelow a casing string.							
	Date/Time <u>10/06/2011</u>	10:30 HRS	АМ 🗌	РМ				
<u>Casir</u>	ng – Please report time casi	ng run star	ts, not ce	ementing				
	s. Surface Casing			RECEIVED				
	Intermediate Casing			OCT 0 4 2011				
H	Production Casing							
H	Liner			DIV. OF OIL, GAS & MINING				
	Other							
	Oti ICI							
	Date/Time <u>10/25/2011</u>	08:00 HRS	AM 🗌	PM				
BOPI	F							
	= Initial BOPE test at surface	casing noir	nt					
	BOPE test at intermediate							
	30 day BOPE test	casing point	<b>-</b>					
	Other							
	Other							
	Date/Time		AM 🗌	РМ				
Rem	arks ESTIMATED DATE AND TIME. PLEA	SE CONTACT KENN	Y GATHINGS	AT				
435 82	8 0986 OR LOVEL YOUNG AT 435 781 705	<b>31</b>						

	STATE OF UTAH		FORM 9
	DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINI		5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22650
SUND	RY NOTICES AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
Do not use this form for propo bottom-hole depth, reenter plu DRILL form for such proposals	existing wells below current e APPLICATION FOR PERMIT TO	7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES	
1. TYPE OF WELL Gas Well		8. WELL NAME and NUMBER: NBU 922-3604BS	
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONS	HORE, L.P.		9. API NUMBER: 43047516040000
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th S	PHON treet, Suite 600, Denver, CO, 80217 3779	<b>E NUMBER:</b> 720 929-6515 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1250 FSL 2103 FEL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSHI	IP, RANGE, MERIDIAN: Township: 09.0S Range: 22.0E Meridian: S		STATE: UTAH
11. CHE	CK APPROPRIATE BOXES TO INDICATE	NATURE OF NOTICE, REPORT,	OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
MIRU PETE MARTIN	CHANGE TO PREVIOUS PLANS  CHANGE WELL STATUS  DEEPEN  OPERATOR CHANGE  PRODUCTION START OR RESUME  REPERFORATE CURRENT FORMATION  TUBING REPAIR  WATER SHUTOFF  WILDCAT WELL DETERMINATION  DMPLETED OPERATIONS. Clearly show all pertited in the second state of the seco	ONDUCTOR HOLE TO 40'. LEADY MIX. SPUD WELL O S. A U Oil	·
NAME (PLEASE PRINT) Sheila Wopsock	<b>PHONE NUMBER</b> 435 781-7024	TITLE Regulatory Analyst	
SIGNATURE N/A	133 /01 /027	DATE 10/7/2011	
		· · · · · · · · · · · · · · · · · · ·	

# STATE OF UTAH **DEPARTMENT OF NATURAL RESOURCES** DIVISION OF OIL, GAS AND MINING

ENTITY ACTION FORM						
Operator:	KERR McGEE OIL & GAS ONSHORE LP		Operator Account Number:	N 2995		
Address:	1368 SOUTH 1200 EAST					
	city VERNAL					
	state UT	zip 84078	Phone Number:	(435) 781-7024		

Well 1

API Number	Well	Name	QQ	Sec	Twp	Rng	County
4304751604	NBU 922-36O4BS		SWSE	36	98	22E	UINTAH
Action Code	Current Entity Number	New Entity Number	S	pud Da	te		y Assignment fective Date
B	99999	2900	1	0/6/201	1	10	/14/11
	U PETE MARTIN BUCKI D WELL ON 10/06/2011	•	MVD				<del>/-/</del>

DHC. 3C 3C

Well 2

API Number	Well N	lame	QQ	Sec	Twp	Rng	County
4304751600	NBU 922-36J1CS		SWSE	36	98	22E	UINTAH
Action Code	Current Entity Number	New Entity Number	s	pud Da	te	1	ty Assignment fective Date
В	99999	2900	1	0/6/201	1	10	114/11
Comments: MIRU SPU	J PETE MARTIN BUCKE D WELL ON 10/06/2011	TRIG. NS7		- TOTAL MARKET STREET	· VWS	. 10 F.	<del>//4///</del>

Well 3

API Number	Well i	lame	QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	s	pud Da	le		y Assignment fective Date
omments:					1008-92-1		

#### **ACTION CODES:**

- A Establish new entity for new well (single well only)
- B Add new well to existing entity (group or unit well)
- C Re-assign well from one existing entity to another existing entity
- D Re-assign well from one existing entity to a new entity
- E Other (Explain in 'comments' section)

SHEILA WOPSOCK

Name (Please Print)

Title

Signature **REGULATORY ANALYST** 

10/7/2011 Date

**RECEIVED** 

(5/2000)

OCT 1 1 2011

	FORM 9			
	5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22650			
SUNDF	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
	sals to drill new wells, significantly deepen gged wells, or to drill horizontal laterals. Us		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES	
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-3604BS	
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONS	HORE, L.P.		9. API NUMBER: 43047516040000	
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th S	PHON treet, Suite 600, Denver, CO, 80217 3779	NE NUMBER: 720 929-6515 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1250 FSL 2103 FEL			COUNTY: UINTAH	
QTR/QTR, SECTION, TOWNSHI Qtr/Qtr: SWSE Section: 36	IP, RANGE, MERIDIAN: Township: 09.0S Range: 22.0E Meridian: S	5	STATE: UTAH	
11. CHE	CK APPROPRIATE BOXES TO INDICAT	E NATURE OF NOTICE, REPORT,	OR OTHER DATA	
TYPE OF SUBMISSION		TYPE OF ACTION		
MIRU AIR RIG ON C SURFACE CASING	□ ACIDIZE □ CHANGE TO PREVIOUS PLANS □ CHANGE WELL STATUS □ DEEPEN □ OPERATOR CHANGE □ PRODUCTION START OR RESUME □ REPERFORATE CURRENT FORMATION □ TUBING REPAIR □ WATER SHUTOFF □ WILDCAT WELL DETERMINATION  OMPLETED OPERATIONS. Clearly show all pertoperations. The Complete Surform of the Com	ACE HOLE TO 2397'. RAN ITING ON ROTARY RIG. ITH WELL COMPLETION A U		
NAME (PLEASE PRINT)	PHONE NUMBER	TITLE		
Jaime Scharnowske	720 929-6304	Regulartory Analyst  DATE		
<b>SIGNATURE</b> N/A		10/31/2011		

	FORM 9			
	5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22650			
SUND	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
Do not use this form for proposottom-hole depth, reenter plu DRILL form for such proposals.	sals to drill new wells, significantly deepen ex ugged wells, or to drill horizontal laterals. Use	isting wells below current APPLICATION FOR PERMIT TO	7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES	
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-3604BS	
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONS	HORE, L.P.		<b>9. API NUMBER:</b> 43047516040000	
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th S	PHONE treet, Suite 600, Denver, CO, 80217 3779	<b>NUMBER:</b> 720 929-6515 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1250 FSL 2103 FEL			COUNTY: UINTAH	
QTR/QTR, SECTION, TOWNSHI Qtr/Qtr: SWSE Section: 36	IP, RANGE, MERIDIAN: Township: 09.0S Range: 22.0E Meridian: S		STATE: UTAH	
11. CHE	CK APPROPRIATE BOXES TO INDICATE	NATURE OF NOTICE, REPORT	, OR OTHER DATA	
TYPE OF SUBMISSION		TYPE OF ACTION		
The operator reque DQX/LTC, the drillin	□ ACIDIZE  ✓ CHANGE TO PREVIOUS PLANS □ CHANGE WELL STATUS □ DEEPEN □ OPERATOR CHANGE □ PRODUCTION START OR RESUME □ REPERFORATE CURRENT FORMATION □ TUBING REPAIR □ WATER SHUTOFF □ WILDCAT WELL DETERMINATION  DIMPLETED OPERATIONS. Clearly show all pertinests changes to the production of g program to allow for the use of variance for FIT Requirements.  explanation. Thank you.	ent details including dates, depths, casing program to Ultra of a Closed Loop system Please see attached	,	
NAME (PLEASE PRINT) Jaime Scharnowske	<b>PHONE NUMBER</b> 720 929-6304	TITLE Regulartory Analyst		
SIGNATURE N/A		DATE 10/17/2011		

NBU 922-36O4BS Drilling Program
1 of 7

# Kerr-McGee Oil & Gas Onshore. L.P.

#### NBU 922-36O4BS

 Surface:
 1250 FSL / 2103 FEL
 SWSE

 BHL:
 415 FSL / 1814 FEL
 SWSE

Section 36 T9S R22E

Uintah County, Utah Mineral Lease: ML-22650

#### **ONSHORE ORDER NO. 1**

#### **DRILLING PROGRAM**

# 1. & 2. <u>Estimated Tops of Important Geologic Markers</u>: <u>Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations</u>:

<u>Formation</u>	<u>Depth</u>	<u>Resource</u>
Uinta	0 - Surface	
Green River	1,101'	
Birds Nest	1,369'	Water
Mahogany	1,736'	Water
Wasatch	4,164'	Gas
Mesaverde	6,333'	Gas
MVU2	7,343'	Gas
MVL1	7,924'	Gas
TVD	8,568'	
TD	8,695'	

# 3. <u>Pressure Control Equipment</u> (Schematic Attached)

Please refer to the attached Drilling Program

# 4. Proposed Casing & Cementing Program:

Please refer to the attached Drilling Program

# 5. **Drilling Fluids Program:**

Please refer to the attached Drilling Program

# 6. <u>Evaluation Program</u>:

Please refer to the attached Drilling Program

NBU 922-36O4BS Drilling Program

# 7. <u>Abnormal Conditions</u>:

Maximum anticipated bottom hole pressure calculated at 8568' TVD, approximately equals 5,484 psi 0.64 psi/ft = actual bottomhole gradient

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 3,587 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

#### 8. Anticipated Starting Dates:

Drilling is planned to commence immediately upon approval of this application.

#### 9. <u>Variances:</u>

Please refer to the attached Drilling Program. Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- · Blowout Prevention Equipment (BOPE) requirements;
- Mud program requirements; and
- Special drilling operation (surface equipment placement) requirements associated with air drilling.

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

#### **Background**

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

NBU 922-36O4BS Drilling Program 3 of 7

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 12 1/4 inch hole for the first 200 feet, then will drill a 11inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 11 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 8-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

# Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

#### Variance for Mud Material Requirements

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

#### Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and

NBU 922-36O4BS Drilling Program 4 of 7

on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

# Variance for FIT Requirements

KMG also respectfully requests a variance to Onshore Order 2, Section III, Part Bi, for the pressure integrity test (PIT, also known as a formation integrity test (FIT)). This well is not an exploratory well and is being drilled in an area where the formation integrity is well known. Additionally, when an FIT is run with the mud weight as required, the casing shoe frequently breaks down and causes subsequent lost circulation when drilling the entire depth of the well.

#### Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.

#### 10. Other Information:

Please refer to the attached Drilling Program.


Drilling Program


5 of 7



NBU 922-36O4BS

# KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM





Drilling Program

6 of 7



# KERR-McGEE OIL & GAS ONSHORE LP

# **DRILLING PROGRAM**

CASING PROGRAM								DESIGN FACTORS			
										LTC	DQX
	SIZE	INTE	RVAL		WT.	GR.	CPLG.	BURST	COLL	APSE	TENSION
CONDUCTOR	14"	0	-40'								
								3,390	1,880	348,000	N/A
SURFACE	8-5/8"	0	to	2,190	28.00	IJ-55	LTC	2.47	1.83	6.48	N/A
								7,780	6,350	223,000	267,035
PRODUCTION	4-1/2"	0	to	5,000	11.60	I-80	DQX	1.11	1.14		3.27
	4-1/2"	5,000	to	8,695'	11.60	I-80	LTC	1.11	1.14	6.43	

**Surface Casing:** 

NBU 922-36O4BS

(Burst Assumptions: TD = 12.5 ppg) 0.73 psi/ft = frac gradient @ surface shoe

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @ 7000 psi) 0.64 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

#### **CEMENT PROGRAM**

	FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80	1.15
Option 1		+ 0.25 pps flocele				
TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80	1.15
		+ 2% CaCl + 0.25 pps flocele				
SURFACE		NOTE: If well will circulate water	to surface,	option 2 w	II be utilized	
Option 2 LEAD	1,690'	65/35 Poz + 6% Gel + 10 pps gilsonite	160	35%	11.00	3.82
		+ 0.25 pps Flocele + 3% salt BWOW				
TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80	1.15
		+ 0.25 pps flocele				
TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80	1.15
PRODUCTION LEAD	3,655'	Premium Lite II +0.25 pps	270	20%	11.00	3.38
		celloflake + 5 pps gilsonite + 10% gel				
		+ 0.5% extender				
TAIL	5,040'	50/50 Poz/G + 10% salt + 2% gel	1,190	35%	14.30	1.31
		+ 0.1% R-3				

<sup>\*</sup>Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

## FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. No centralizers will be used.

#### ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.


DRILLING ENGINEER:		DATE:	
	Nick Spence / Danny Showers / Chad Loesel	_	
DRILLING SUPERINTENDENT:		DATE:	

Kenny Gathings / Lovel Young

<sup>\*</sup>Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

NBU 922-36O4BS Drilling Program 7 of 7

# EXHIBIT A NBU 922-3604BS



# SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK

# Requested Drilling Options:

Kerr-McGee will use either a closed loop drilling system that will require one pit and one cuttings storage area to be constructed on the drilling pad or a traditional drilling operation with one pit used for drilling and completion operations. The cuttings storage area will be used to contain only the de-watered drill cuttings and will be lined and bermed to prevent any liquid runoff. The drill cuttings will be buried in the completion pit once completion operations are completed according to traditional pit closure standards. The pit will be constructed to allow for completion operations. The completion operations pit will be lined with a synthetic material 20 mil or thicker and will be used for the completing of the wells on the pad or used as part of our Aandarko Completions Transportation System (ACTS). Using the closed loop drilling system will allow Kerr-McGee to decrease the amount of disturbance/footprint on location compared to a single large drilling/completions pit.

If Kerr-McGee does not use a closed loop drilling system, it will construct a traditional drilling/completions pit to contain drill cuttings and for use in completion operations. The pit will be lined with a synthetic material 20 mil or thicker. The drill cuttings will be buried in the pit using traditional pit closure standards.

	STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES		FORM 9	
	NG	5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22650		
SUND	N WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:		
Do not use this form for proposottom-hole depth, reenter plu DRILL form for such proposals.	7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES			
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: NBU 922-3604BS			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONS	HORE, L.P.		9. API NUMBER: 43047516040000	
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th S	PHONE Street, Suite 600, Denver, CO, 80217 3779	<b>NUMBER:</b> 720 929-6515 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1250 FSL 2103 FEL			COUNTY: UINTAH	
QTR/QTR, SECTION, TOWNSHI Qtr/Qtr: SWSE Section: 36	IP, RANGE, MERIDIAN: Township: 09.0S Range: 22.0E Meridian: S		STATE: UTAH	
11. CHE	CK APPROPRIATE BOXES TO INDICATE	NATURE OF NOTICE, REPORT	, OR OTHER DATA	
TYPE OF SUBMISSION		TYPE OF ACTION		
The operator reque DQX/LTC, the drillin	□ ACIDIZE  ✓ CHANGE TO PREVIOUS PLANS □ CHANGE WELL STATUS □ DEEPEN □ OPERATOR CHANGE □ PRODUCTION START OR RESUME □ REPERFORATE CURRENT FORMATION □ TUBING REPAIR □ WATER SHUTOFF □ WILDCAT WELL DETERMINATION  DIMPLETED OPERATIONS. Clearly show all pertine ests changes to the production of g program to allow for the use of variance for FIT Requirements.  explanation. Thank you.	ent details including dates, depths, casing program to Ultra of a Closed Loop system Please see attached	,	
NAME (PLEASE PRINT)	PHONE NUMBER	TITLE		
Jaime Scharnowske	720 929-6304	Regulartory Analyst		
SIGNATURE N/A		<b>DATE</b> 10/17/2011		

NBU 922-36O4BS Drilling Program
1 of 7

# Kerr-McGee Oil & Gas Onshore. L.P.

## NBU 922-36O4BS

 Surface:
 1250 FSL / 2103 FEL
 SWSE

 BHL:
 415 FSL / 1814 FEL
 SWSE

Section 36 T9S R22E

Uintah County, Utah Mineral Lease: ML-22650

#### **ONSHORE ORDER NO. 1**

## **DRILLING PROGRAM**

# 1. & 2. <u>Estimated Tops of Important Geologic Markers</u>: <u>Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations</u>:

<u>Formation</u>	<u>Depth</u>	<u>Resource</u>
Uinta	0 - Surface	
Green River	1,101'	
Birds Nest	1,369'	Water
Mahogany	1,736'	Water
Wasatch	4,164'	Gas
Mesaverde	6,333'	Gas
MVU2	7,343'	Gas
MVL1	7,924'	Gas
TVD	8,568'	
TD	8,695'	

# 3. <u>Pressure Control Equipment</u> (Schematic Attached)

Please refer to the attached Drilling Program

# 4. Proposed Casing & Cementing Program:

Please refer to the attached Drilling Program

# 5. **Drilling Fluids Program:**

Please refer to the attached Drilling Program

# 6. <u>Evaluation Program</u>:

Please refer to the attached Drilling Program

NBU 922-36O4BS Drilling Program

# 7. <u>Abnormal Conditions</u>:

Maximum anticipated bottom hole pressure calculated at 8568' TVD, approximately equals 5,484 psi 0.64 psi/ft = actual bottomhole gradient

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 3,587 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

## 8. Anticipated Starting Dates:

Drilling is planned to commence immediately upon approval of this application.

## 9. <u>Variances:</u>

Please refer to the attached Drilling Program. Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- · Blowout Prevention Equipment (BOPE) requirements;
- Mud program requirements; and
- Special drilling operation (surface equipment placement) requirements associated with air drilling.

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

## **Background**

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

NBU 922-36O4BS Drilling Program 3 of 7

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 12 1/4 inch hole for the first 200 feet, then will drill a 11inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 11 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 8-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

# Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

## Variance for Mud Material Requirements

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

#### Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and

NBU 922-36O4BS Drilling Program 4 of 7

on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

# Variance for FIT Requirements

KMG also respectfully requests a variance to Onshore Order 2, Section III, Part Bi, for the pressure integrity test (PIT, also known as a formation integrity test (FIT)). This well is not an exploratory well and is being drilled in an area where the formation integrity is well known. Additionally, when an FIT is run with the mud weight as required, the casing shoe frequently breaks down and causes subsequent lost circulation when drilling the entire depth of the well.

#### Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.

## 10. Other Information:

Please refer to the attached Drilling Program.


Drilling Program


5 of 7



NBU 922-36O4BS

# KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM





Drilling Program

6 of 7



# KERR-McGEE OIL & GAS ONSHORE LP

# **DRILLING PROGRAM**

CASING PROGRAM								DESIGN FACTORS			
										LTC	DQX
	SIZE	INTE	RVAL		WT.	GR.	CPLG.	BURST	COLL	APSE	TENSION
CONDUCTOR	14"	0	-40'								
								3,390	1,880	348,000	N/A
SURFACE	8-5/8"	0	to	2,190	28.00	IJ-55	LTC	2.47	1.83	6.48	N/A
								7,780	6,350	223,000	267,035
PRODUCTION	4-1/2"	0	to	5,000	11.60	I-80	DQX	1.11	1.14		3.27
	4-1/2"	5,000	to	8,695'	11.60	I-80	LTC	1.11	1.14	6.43	

**Surface Casing:** 

NBU 922-36O4BS

(Burst Assumptions: TD = 12.5 ppg) 0.73 psi/ft = frac gradient @ surface shoe

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @ 7000 psi) 0.64 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

#### **CEMENT PROGRAM**

	FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80	1.15
Option 1		+ 0.25 pps flocele				
TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80	1.15
		+ 2% CaCl + 0.25 pps flocele				
SURFACE		NOTE: If well will circulate water	to surface,	option 2 w	II be utilized	
Option 2 LEAD	1,690'	65/35 Poz + 6% Gel + 10 pps gilsonite	160	35%	11.00	3.82
		+ 0.25 pps Flocele + 3% salt BWOW				
TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80	1.15
		+ 0.25 pps flocele				
TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80	1.15
PRODUCTION LEAD	3,655'	Premium Lite II +0.25 pps	270	20%	11.00	3.38
		celloflake + 5 pps gilsonite + 10% gel				
		+ 0.5% extender				
TAIL	5,040'	50/50 Poz/G + 10% salt + 2% gel	1,190	35%	14.30	1.31
		+ 0.1% R-3				

<sup>\*</sup>Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

## FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. No centralizers will be used.

#### ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.


DRILLING ENGINEER:		DATE:	
	Nick Spence / Danny Showers / Chad Loesel	_	
DRILLING SUPERINTENDENT:		DATE:	

Kenny Gathings / Lovel Young

<sup>\*</sup>Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

NBU 922-36O4BS Drilling Program 7 of 7

# EXHIBIT A NBU 922-3604BS



# SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK

# Requested Drilling Options:

Kerr-McGee will use either a closed loop drilling system that will require one pit and one cuttings storage area to be constructed on the drilling pad or a traditional drilling operation with one pit used for drilling and completion operations. The cuttings storage area will be used to contain only the de-watered drill cuttings and will be lined and bermed to prevent any liquid runoff. The drill cuttings will be buried in the completion pit once completion operations are completed according to traditional pit closure standards. The pit will be constructed to allow for completion operations. The completion operations pit will be lined with a synthetic material 20 mil or thicker and will be used for the completing of the wells on the pad or used as part of our Aandarko Completions Transportation System (ACTS). Using the closed loop drilling system will allow Kerr-McGee to decrease the amount of disturbance/footprint on location compared to a single large drilling/completions pit.

If Kerr-McGee does not use a closed loop drilling system, it will construct a traditional drilling/completions pit to contain drill cuttings and for use in completion operations. The pit will be lined with a synthetic material 20 mil or thicker. The drill cuttings will be buried in the pit using traditional pit closure standards.

Sundry Number: 20916 API Well Number: 43047516040000

	STATE OF UTAH DEPARTMENT OF NATURAL RESOURCE		FORM 9			
	5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22650					
SUNDF	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:				
Do not use this form for proposottom-hole depth, reenter plu DRILL form for such proposals.	7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES					
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-3604BS			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONS	HORE, L.P.		<b>9. API NUMBER:</b> 43047516040000			
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th S	PHO treet, Suite 600, Denver, CO, 80217 3779	<b>NE NUMBER:</b> 720 929-6515 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1250 FSL 2103 FEL			COUNTY: UINTAH			
QTR/QTR, SECTION, TOWNSHI	IP, RANGE, MERIDIAN: Township: 09.0S Range: 22.0E Meridian:	S	STATE: UTAH			
11. CHE	CK APPROPRIATE BOXES TO INDICAT	E NATURE OF NOTICE, REPORT,	OR OTHER DATA			
TYPE OF SUBMISSION		TYPE OF ACTION				
MIRU ROTARY RIG. 2011. RAN 4-1 PRODUCTION CASING HRS. DETAILS O	CHANGE TO PREVIOUS PLANS CHANGE WELL STATUS DEEPEN OPERATOR CHANGE PRODUCTION START OR RESUME REPERFORATE CURRENT FORMATION TUBING REPAIR WATER SHUTOFF WILDCAT WELL DETERMINATION PMPLETED OPERATIONS. Clearly show all per FINISHED DRILLING FROM 23 /2" 11.6# I-80 PRODUCTION G. RELEASED ENSIGN RIG 139 OF CEMENT JOB WILL BE INCLU T. WELL IS WAITING ON FINA	397' TO 8720' ON DEC. 2, CASING. CEMENTED O ON DEC. 4, 2011 @ 12: <b>6</b> UDED WITH THE WELL L COMPLETION ACTIVI <b>TO</b>	ccepted by the Jtah Division of			
NAME (PLEASE PRINT) Jaime Scharnowske	PHONE NUMBER	TITLE Regulartory Analyst				
SIGNATURE	720 929-6304	DATE 12/5/2011				
N/A		12/3/2011				

# State of Utah - Notification Form

Operator Anadarko Petroleum Rig Name/# Ensign 139
Submitted By <u>KENNY MORRIS</u> Phone Number
435- 828-0984
Well Name/Number NBU 922-3604BS
Qtr/Qtr <u>SESW</u> Section <u>36</u> Township <u>9S</u> Range 22E
Lease Serial Number ML-22650
API Number43047516040000
<u>Casing</u> – Time casing run starts, not cementing times.
Production Casing Other
Date/Time <u>12/3/2011</u> <u>06:00</u> AM ⊠ PM □
BOPE
Initial BOPE test at surface casing point  Other
Date/Time AM DM PM D
RECEIVED
Rig Move DEC 0 2 2011
Location Tou
DIV. OF OIL, GAS & MINING
Date/Time AM PM D
Remarks WILL RUN 4.5 PROD CSG SATURDAY MORNING
12/3/2011

Sundry Number: 22433 API Well Number: 43047516040000

	STATE OF UTAH		FORM 9			
ι	DEPARTMENT OF NATURAL RESOURG DIVISION OF OIL, GAS, AND MII		5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22650			
SUNDR	Y NOTICES AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
Do not use this form for pro current bottom-hole depth, I FOR PERMIT TO DRILL form	7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES					
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-3604BS			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	ISHORE, L.P.		9. API NUMBER: 43047516040000			
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th	n Street, Suite 600, Denver, CO, 8021	<b>PHONE NUMBER:</b> 7 3779 720 929-0	9. FIELD and POOL or WILDCAT: 5NATERAL BUTTES			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1250 FSL 2103 FEL			COUNTY: UINTAH			
QTR/QTR, SECTION, TOWNSH	HIP, RANGE, MERIDIAN: 36 Township: 09.0S Range: 22.0E Merio	dian: S	STATE: UTAH			
11. CHECK	K APPROPRIATE BOXES TO INDICA	TE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA			
TYPE OF SUBMISSION		TYPE OF ACTION				
	ACIDIZE	ALTER CASING	CASING REPAIR			
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME			
	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE			
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	☐ NEW CONSTRUCTION			
	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK			
SPUD REPORT	✓ PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION			
Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON			
	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL			
DRILLING REPORT     Report Date:	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION			
1/21/2012	WILDCAT WELL DETERMINATION	OTHER	OTHER:			
THE SUBJECT WEL 1730 HRS. THE CHR	COMPLETED OPERATIONS. Clearly show L WAS PLACED ON PRODUC RONOLOGICAL WELL HISTOF TH THE WELL COMPLETION R	CTION ON 01/21/2012 AT RY WILL BE SUBMITTED	<u> </u>			
NAME (PLEASE PRINT) Sheila Wopsock	<b>PHONE NUME</b> 435 781-7024	BER TITLE Regulatory Analyst				
SIGNATURE N/A		<b>DATE</b> 1/23/2012				

				TMEN	ATE C TOF NA FOIL,	TURA	L RESC					(hi 5. L	ghlight c EASE DES	REPORT hanges) lignation ar			DRM 8 BER:
14/51													VIL-226	350 ALLOTTEE OF	R TRIF	RE NAME	
	L COM	PLET	ION	OR F	RECO	MPL	ETIC	ON RI	EPOF	RT AND	LOG	"	.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	ALLO I I LL OI	V IIVIE	DE NAME	
1a. TYPE OF WELL		OI! W		,	GAS WELL Z		DRY		ОТЬ	IER			INIT of CA UTU63	AGREEMENT 3047A	NAM	E	
b. TYPE OF WORK NEW WELL 2	HORIZ.	DE EN	EP-		RE- ENTRY	]	DIFF. RESVR.		ОТН	ER				E and NUMBE 22-3604			
KERR MC		_ & GA	S ON	SHOF	RE, L.P	·.							PI NUMBE 43047				
3. ADDRESS OF OF P.O.BOX 17	73779		PHONE NUMBER: (720) 929-63									10 F	IELD AND	POOL, OR W			
4. LOCATION OF W			31.046	00 FF								11.	QTR/QTR,	SECTION, TO	OWNS	HIP, RANG	E,
AT SURFACE:													NSE	36 98		22E S	
AT TOP PRODU	CING INTERV	AL REPOR	RTED BEL	ow: S	SWSE 4	428 F	SL 18	25 FE	L S36,	T9S, R	22E						
AT TOTAL DEPT	H: SWS	E 418 I	FSL 18	805 F	EL S36	s. T99	S. R22	Ē.					COUNTY		1:	3. STATE	
14. DATE SPUDDE		DATE T.			16. DATE			_ R1	tr p	y HS	$\sim$		JINTA	ATIONS (DF,			UTAH
10/6/2011		12/2/2	011		1/21	/2012			ABANDON	ED	READY TO PRODU	CE 🗸		68 GL	KKB,	RI, GL):	
18. TOTAL DEPTH:	0,7		1:	9. PLUG	BACK T.D		8,656		20. iF	MULTIPLE CO	OMPLETIONS, HOW	MANY? *		TH BRIDGE JG SET:	MD		*****
22. TYPE ELECTRIC	TVD 8.5		ICAL LOG	S RUN (	Submit con		8,530			23.					TVD		
CBL/GR/CC					•	y or each	<b>'</b>			WAS WEL	L CORED? RUN? NAL SURVEY?	NO NO NO	<u>✓</u> ×	ES 🗍	(Subm	nit analysis) nit report) nit copy)	
24. CASING AND LI	INER RECOR	O (Report a	ali strings	set in w	ell)												
HOLE SIZE	SIZE/GRA	DE	WEIGHT	(#/ft.)	TOP (I	MD)	вотто	M (MD)		CEMENTER EPTH	CEMENT TYPE & NO. OF SACKS	SLU VOLUM		CEMENT TO	)P **	AMOUNT	PULLED
20"	14"	STL	36.7		0		4	0			28						
11		IJ-55	28‡		0		2,4	407			900			0			
7 7/8"	4 1/2"	I-80	11.6	<b>3#</b>	0		8,6	699			1,440			2196	;		
							ļ										
									ļ								
05 7117110 7-00-					· ———		<u> </u>					<u> </u>				<u> </u>	
25. TUBING RECOF		ET (MED)	1									·					
2 3/8"	DEPTH S	<del></del>	PACKE	R SET (I	AD)	SIZE		DEPTH	SET (MD)	PACKE	R SET (MD)	SIZE	Di	PTH SET (M	D)	PACKER S	ET (MD)
26. PRODUCING IN	<del></del>	10	<u> </u>							27 DEDEC	RATION RECORD						
FORMATION		TOP (	(MD)	BOTTO	M (MD)	TOP	(TVD)	вотто	M (TVD)		L (Top/Bot - MD)	SIZE	NO. HOLE	S PE	REOR	ATION STA	TUS
(A) WASATC	Н	5,6	70		307		<u>,</u>			5,670	5,807	0.36	24	Open	_	Squeezed	<u> </u>
(B) MESAVE	RDE688		882	<u>-</u>	514					6.882	8,514	0.36	168	Open	=-	Squeezed	<del>                                     </del>
(C)	· · · · · · · · · · · · · · · · · · ·			,			· · · · · · · · · · · · · · · · · · ·			.,	5,011		1.00	Open		Squeezed	<del>-</del>
(D)														Open	=	Squeezed	
28. ACID, FRACTU	RE, TREATME	NT, CEME	NT SQUE	EZE, ET	).		· · · · · · · · · · · · · · · · · · ·						E				=
DEPTH	INTERVAL			·				· · · <u></u>	AM	OUNT AND T	YPE OF MATERIAL	· · · · · · · · · · · · · · · · · · ·		RECE	+∀	<del>LD</del>	
5670-8514			PUM	P 9,7	45 BB	LS S	LICK I	120 &	210,6	27 LBS	30/50 OTTA	WA SA	AND	FEB 2	R 2	ให้ว	<del>-i</del>
				rage		***			, -							- 146	
													DIV. O	OIL, GA	S&	MINING	
29. ENCLOSED AT	TACHMENTS:													30.	WELL	. STATUS:	

SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION

ELECTRICAL/MECHANICAL LOGS

GEOLOGIC REPORT

CORE ANALYSIS

DST REPORT

OTHER:

☑ DIRECTIONAL SURVEY

PROD

31.	INITIAL	PRODUCTION

## INTERVAL A (As shown in item #26)

DATE FIRST PR	ODUCED:	TEST DATE:		HOURS TESTED	):	TEST PRODUCTION	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
1/21/2012	·	1/24/2012		2	24	RATES: →	0	2,720	510	FLOWING
20/64	TBG. PRESS. 1,383	CSG. PRESS. 1,720	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL: 0	GAS - MCF: 2,720	WATER – BBL: 510	INTERVAL STATUS: PROD
				INT	ERVAL B (As sho	wn in item #26)			***	
DATE FIRST PR	ODUCED:	TEST DATE:		HOURS TESTED	HOURS TESTED:		OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS,	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS MCF:	WATER BBL:	INTERVAL STATUS:
				INT	ERVAL C (As sho	wn in item #26)	*****		<u> </u>	
DATE FIRST PR	ODUCED:	TEST DATE:		HOURS TESTED	);	TEST PRODUCTION RATES: →	OIL - BBL;	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL;	GAS - MCF:	WATER – BBL:	INTERVAL STATUS:
				INTI	ERVAL D (As sho	wn in item #26)			<u> </u>	
DATE FIRST PR	ODUCED:	TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:
32. DISPOSITIO	N OF GAS (Sold,	Used for Fuel, Ve	nted, Etc.)		•		<del> </del>	<u> </u>		I.

#### 33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth
				GREEN RIVER BIRD'S NEST MAHOGANY WASATCH MESAVERDE	1,143 1,423 1,937 4,298 6,492

35. ADDITIONAL REMARKS (Include plugging procedure)

The first 210'of the surface hole was drilled with a 12 ¼" bit. The remainder of surface hole was drilled with an 11" bit. Attached is the chronological well history, perforation report & final survey. DQX csg was run from surface to 5,026'; LTC csg was run from 5026' to 8699'.

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all availal	le records.
---	-------------

NAME (PLEASE PRINT) JAIME SCHARNOWSKE

TITLE REGULATORY ANALYST

SIGNATURE Jam Chameuse

DATE 2/23/2012

This report must be submitted within 30 days of

- · completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

Send to:

Utah Division of Oil, Gas and Mining 1594 West North Temple, Suite 1210

Box 145801 Salt Lake City, Utah 84114-5801 Phone: 801-538-5340

Fax: 801-359-3940

<sup>\*</sup> ITEM 20: Show the number of completions if production is measured separately from two or more formations.

<sup>\*\*</sup> ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

# **Operation Summary Report**

 Well: NBU 922-3604BS GREEN
 Spud Date: 10/25/2011

 Project: UTAH-UINTAH
 Site: NBU 922-360 PAD
 Rig Name No: ENSIGN 139/139, PROPETRO 12/12

 Event: DRILLING
 Start Date: 10/9/2011
 End Date: 12/4/2011

Active Datum: RKB @4,982.00usft (above Mean Sea

UWI: SW/SE/0/9/S/22/E/36/0/0/26/PM/S/1250/E/0/2103/0/0

Level)										
Date	S	Time tart-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation	
10/24/2011	0:01	- 0:01	0.00	MIRU	12	E	Р		10/31/2011 TOP OFF CMT	
	0:01	- 0:01	0.00	MIRU					TRIPPLE A CEMENT TOP OFF ON 10/31/2011	
	21:00	- 0:00	3.00	MIRU	01	С	P		SKID RIG 10' TO NBU 922-3604BS (WELL4 OF 5). INSTALL DIVERTOR HEAD AND BLUEY LINE. BUILD DITCH. SPOT IN RIG. SPOT IN CATWALK AND PIPE RACKS. RIG UP PIT PUMP. RIG UP PUMP. PRIME PUMP. INSPECT RIG. HELD PRE-SPUD SAFETY MEETING.	
10/25/2011	0:00	- 0:30	0.50	DRLSUR	06	A	Р		P/U MOTOR & 12 1/4 BIT SPUD 10/25/2011 @ 00:30	
	0:30	- 2:00	1.50	DRLSUR	02	D	Р		DRILL 12.25" HOLE 44'- 210'. (166', 83'/HR) RPM=45, WOB 5-15K. PSI ON/OFF 600/400. UP/DOWN/ ROT 20/20/20 K. DRAG 0 K. CIRC RESERVE W. 8.3# WATER. DRILL DOWN TO 210' W/ 6" COLLARS.	
	2:00	- 4:00	2.00	DRLSUR	06	A	P		POOH, PU, 11" BIT AND DIRECTIONAL TOOLS, TIH T/	
	4:00	- 14:30	10.50	DRLSUR	02	D	Р		DRILL FROM 210 T/1320 (1110' @ 106' PER HR) WOB 15K, PSI ON/OFF 1320/1105 UP/DWN/ROT 60/49/53 RPM 55	
	14:30	- 15:00	0.50	DRLSUR	05	ŕ	. <b>S</b> .		UNLOAD HOLE & CHECK FOR WATER IN UPPER ZONES (NO WATER)	
	15:00	- 17:00	2.00	DRLSUR	02	D	Р		DRILL FROM 1320 T/1520 (200' @ 100' PER HR) WOB 15K, PSI ON/OFF 1390/1255 UP/DWN/ROT 67/50/60 RPM 55	
	17:00	- 23:30	6.50	DRLSUR	06	В	S		POOH, L/D DIR. TOOLS & BIT. P/U CONE BIT & 4 DCs. RIH T/1070.	
	23:30	- 0:00	0.50	DRLSUR	03	E	X		WASH & REAM T/1520.	
10/26/2011	0:00	- 4:00	4.00	EVALPR	05	E	s		TAKE SAMPLES F/BIRDS NEST FORMATION	
	4:00	- 10:00	6.00	DRLSUR	06	Α	Р		POOH, PU DIR. TOOLS, RIH T/1520	
	10:00	- 10:30	0.50	DRLSUR	02	Ď	P		DRILL F/ 1520 T/1550 (50' @ 100' PER HR) WOB	
									15K, PSI ON/OFF 1390/1255 UP/DWN/ROT 67/50/60 RPM 55	
	10:30	- 11:30	1.00	DRLSUR	22	L	Z		PROBLEMS W/DIRECTIONAL MWD TOOL	
	11:30	- 20:00	8.50	DRLSUR	02	D	P		DRLG F/1550 T/2180 (630' @ 74' PER HR) WOB 20K, PSI ON/OFF 1540/1350, UP/DWN/ROT 78/59/68	
									RPM 50	
	20:00	- 0:00	4.00	DRLSUR	80	Α	Z		REMOVE & REPLACE HYDRAULIC LINE	
10/27/2011	0:00	- 3:00	3.00	DRLSUR	. 08	Α	Z		REPLACE HYDRAULIC LINES	
	3:00	- 6:30	3.50	DRLSUR	02	D	P		DRLG F/2180 T/2397 (217' @ 62' PER HR) WOB 20K, PSI ON/OFF 1540/1350, UP/DWN/ROT 78/59/68 RPM TD@06:30	
	6:30	- 8:30	2.00	DRLSUR	05	D	P		CIRC F/CSNG	
	8:30	- 12.30	4.00	DRLSUR	06	D	Р		LDDS, BHA & DIR. TOOLS	
	12:30	- 14:00	1.50	DRLSUR	12	Α	Р		MOVE PIPE RACKS AND CATWALK, PULL	
					en e		٠,		DIVERTER HEAD. RIG UP TO RUN CSG. AND MOVE CSG INTO POSITION TO P/U.	
	14:00	- 16:00	2.00	DRLSUR	12	С	P		RUN 54 JTS 8 5/8, 28# CSNG. LAND CSNG @ 16:00, SHOE SET @ 2397', BAFFLE SET @ 2351'	

# **Operation Summary Report**

 Well: NBU 922-3604BS GREEN
 Spud Date: 10/25/2011

 Project: UTAH-UINTAH
 Site: NBU 922-360 PAD
 Rig Name No: ENSIGN 139/139, PROPETRO 12/12

 Event: DRILLING
 Start Date: 10/9/2011
 End Date: 12/4/2011

 Event: DRILLING
 Start Date: 10/9/2011
 End Date: 12/4/2011

 Active Datum: RKB @4,982.00usft (above Mean Sea
 UWI: SW/SE/0/9/S/22/E/36/0/0/26/PM/S/1250/E/0/2103/0/0

Active Datum: Rk Level)	KB @4,9	982.00usft (a	bove Mean S	Sea	UWI: SW/SE/0/9/S/22/E/36/0/0/26/PM/S/1250/E/0/2103/0/0							
Date	St	Time lart-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation			
	16:00	- 16:30	0.50	DRLSUR	12	Α	P		HOLD SAFETY MEETING, RUN 200' OF 1". RIG DOWN RIG MOVE OFF WELL, REBUILD DITCH. RIG UP CEMENT TRUCK, 2" HARD LINES,. CEMENT			
	16:30	- 18:30	2.00	DRLSUR	12	Ē	P		PRESSURE TEST LINES TO 2000 PSI. PUMP 139			
									BBLS OF WATER AHEAD. PUMP 20 BBLS OF 8.3# GEL WATER AHEAD. PUMP (300 SX) 61.35 BBLS			
									OF 15.8# 1.15 YD 5 GAL/SK PREMIUM CEMENT W/ 2% CALC. DROP PLUG ON FLY. DISPLACE W/ 146.7			
									BBLS OF H20. NO CIRC THROUGH OUT. FINAL LIFT OF 400 PSI AT 4 BBL/MIN. BUMP PLUG W/750 PSI			
									HELD FOR 5 MIN. FLOAT DID NOT HOLD, PUMP (150 SX) 30.64 BBLS OF SAME TAIL CEMENT W/			
									4% CALC. DOWN BACKSIDE. SHUT DOWN AND CLEAN TRUCK. NO CEMENT TO SURFACE.			
	18:30	- 20:30	2,00	DRLSUR	13	Α	Р		WOC , PUMP (150 SX) 30.64 BBLS 15.8 CMT DOWN BACKSIDE. NO RETURNS TO SURFACE			
	20:30	- 22:30	2.00	DRLSUR	13	Α	Р		WOC , PUMP (150 SX) 30.64 BBLS 15.8 CMT DOWN BACKSIDE. NO RETURNS TO SURFACE			
	22:30	- 0:00	1.50	DRLSUR	13	Α	Р		WOC , PUMP (150 SX) 30.64 BBLS 15.8 CMT DOWN BACKSIDE. NO RETURNS TO SURFACE RELEASE RIG @ 00:00 10/28/2011			
	23:59	- 23:59	0.00	DRLSUR	12	E	P		TOP OFF CMT 10/31/2011			
11/28/2011		- 14:00	2.00	MIRU	01	С	Р		SKID ON,LEVEL DERRICK RURT,FLOW & FLARE LINES,CATWALK			
		- 15:00	1.00	MIRU	14	Α	P		NUBOP AND FUNCTION TEST BOP			
	15:00	- 18:00	3.00	PRPSPD	09	Α	P		CUT & SLIP DRLG LINE, PRE SPUD INSPECTION			
	18:00	- 22:00	4,00	PRPSPD	15	Α	P		BOP TEST W/ QUIK TEST, TEST FLOOR VALVES, RAMS, CHOKE, MANIFOLD, KILLLINE TO			
	22:00	- 22:30	0.50	PRPSPD	14	В	Р		5K,,ANNULAR 2.5K,CSG 1500 F/30 MIN,250 LOWS INSTALL WEARBUSHING			
	22:30	- 0:00	1,50	PRPSPD	06	Α	P		P/U BHA #1,SCRIBE DIRTOOLS TIH			
11/29/2011	0:00	- 3:00	3.00	PRPSPD	06	Α	P		TIH, LEVEL DERRICK, INSTALL ROT RUBBER,			
	3:00	- 4:00	1.00	DRLPRO	02	F	P		DRILL CEMENT & FE F/2284 TO 2407'			
	4:00	- 4:30	0.50	DRLPRO	02	D	Р		SPUD 7.875 HOLE DRILL F/2407 TO 2491AVG 168			
	4:30	- 5:00	0.50	DRLPRO	08	В	S		UNPLUG FLOWLINE JET LINE			
	5:00	- 11:30 - 12:00	6.50	DRLPRO	02	D	Р		DIRDRILL F/2491 TO 3397 =906 AVG 139 ,WOB 18/20,SPM 120,GPM 590,TRPM 132,TORQ 5/9K,SLIDE 125' 12%			
The state of the state of		- 0:00	0.50 12.00	DRLPRO	07	A	P s		RIG SERVICE			
ئىدى دەخ <b>ۇدۇر</b>				DRLPRO	02	D	Р		DIRDRILL F/3397 TO 5121=1723 AVG 143 ,WOB 18/20,SPM 120,GPM 590,BHRPM 132,TORQ 5/9K,SLIDE 60' 4%			
11/30/2011	0:00	- 13:00	13.00	DRLPRO	02	D	P		DIRDRILL F/5121 TO 6475 =1354 AVG 104 ,WOB 18/20,SPM 120,GPM 590,BHRPM 132,TORQ			
	13:00	- 15:30	2.50	DRLPRO	05	G	Р		5/9K, SLIDE 72 5% PUMP SWEEPS, DISPLACE HOLE W/10.9/42			
	15:30	- 16:00	0.50	DRLPRO	07	Α	Р		MUD,STORE WATER RIG SERVICE			
		- 0:00	8.00	DRLPRO	02	D	P		DIRDRILL F/6475 TO 6970 =495 AVG 62 ,WOB 18/20,SPM 120,GPM 590,BHRPM 132,TORQ 5/9K,SLIDE 3%			

# **Operation Summary Report**

 Well: NBU 922-3604BS GREEN
 Spud Date: 10/25/2011

 Project: UTAH-UINTAH
 Site: NBU 922-360 PAD
 Rig Name No: ENSIGN 139/139, PROPETRO 12/12

 Event: DRILLING
 Start Date: 10/9/2011
 End Date: 12/4/2011

Active Datum: RKB @4,982.00usft (above Mean Sea UWI: SW/SE/0/9/S/22/E/36/0/0/26/PM/S/1250/E/0/2103/0/0

Level)								
Date	200	Time art-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From Operation (usft)
12/1/2011	0:00	- 10:30	10.50	DRLPRO	02	D	P	DIRDRILL F/6970 TO 7561 =591 AVG 56 ,WOB 18/20,SPM 100,GPM 490,BHRPM 114,TORQ 8/12K,SLIDE 65' 9%,MW 10.8/42
	10:30	- 11:00	0.50	DRLPRO	07	Α	P	RIG SERVICE, FUNCTION BOP
	11:00	- 0:00	13.00	DRLPRO	02	D	Р	DIRDRILL F/7561 TO 8380 =819 AVG 63 ,WOB 18/20,SPM 100,GPM 490,BHRPM 114,TORQ 8/12K,SLIDE 0%,MW 11,4/42
12/2/2011	0:00	- 6:00	6.00	DRLPRO	02	D	P	DIRDRILL F/8380 TO TD 8720=340 AVG 56 ,WOB 18/20,SPM 100,GPM 490,BHRPM 114,TORQ 8/12K,SLIDE 0%,MW 11.5/42
	6:00	- 8:30	2.50	DRLPRO	05	С	P	FINAL SURVEY@8630 1.19DEG 144 AZI, ,FLOW CHECK,RAISE MW TO 11.6,CIRC BTMS UP F/ SHORTTRIP
	8:30	- 22:30	14.00	DRLPRO	06	E	P	PUMP OUT 10 STNDS, PUMP DRY PILL, SHORTRIP TO SHOE F/LOGS, TIGHT 6130, 4350-3980, BREAK CIRC
								4300 6400,SEVERAL TIGHT SPOTS OUT & IN
	22:30	- 0:00	1.50	DRLPRO	05	С	Р	CIRC BTMS UP F/ LOGS, 20 BBL GAIN 250PSI LOSS ON BTMS UP, BUT NO FLARE
12/3/2011	0:00	- 9:30	9.50	EVALPR	06	В	Р	TOOH F/ LOGS, PUMP OUT 15 STNDS, , TIGHT SPOT 6650,57903820, PULL WEARRING
	9:30	- 14:00	4.50	EVALPR	11	D	Р	SAFETY MT W/ HALCO R/U RUN TRIPLE COMBO TO LOGGERS DEPTH 8667
	14:00	- 0:00	10.00	CSG	12	C	P	SAFETY MT W/ FRANKS.R/U RUN 87 JTS 4.5" #11.6 I-80 AND 120 JT DQX TO SHOE DEPTH 8713'
12/4/2011	0:00	- 3:00	3.00	CSG	12	С	P	FINISH TORQ TURN DQX,SHOE SET @ 8713'
	3:00	- 4:00	1.00	CSG	05	Ď	P	CIRC BTMS UP F/CEMENT
	4:00	- 10:00	6.00	CSG	12	E	Р	PUMP 25 SPACER,400 SXLEAD 12.1# 2.21 YLD,1040 SX TAIL 1.31YLD #14.3,DISP 134BBLS FINALLIFT 2530,BUMPPLUG FLOATS HELD,20 BBL CEMENT BACK

# 1 General

## 1.1 Customer Information

Company	US ROCKIES REGION
Representative	
Address	

## 1.2 Well/Wellbore Information

Well	NBU 922-36O4BS GREEN	Wellbore No.	ОН
Well Name	NBU 922-3604BS	Wellbore Name	NBU 922-36O4BS
Report No.	1	Report Date	1/8/2012
Project	UTAH-UINTAH	Site	NBU 922-360 PAD
Rig Name/No.		Event	COMPLETION
Start Date	1/9/2012	End Date	
Spud Date	10/25/2011	Active Datum	RKB @4,982.00usft (above Mean Sea Level)
UWI	SW/SE/0/9/S/22/E/36/0/0/26/PM/S/1250/E/0/210	3/0/0	

## 1.3 General

Contractor	CASED HOLE SOLUTIONS	Job Method	PERFORATE	Supervisor	ED GUDAC
	PRODUCTION CASING	Conveyed Method	WIRELINE		

# 1.4 Initial Conditions

# 1.5 Summary

Fluid Type		Fluid Density	Gross in	terval	5,670.0 (usft)-8,514.0 (usft	Start Date/Time	1/16/2012 12:00AM
Surface Press		Estimate Res Press	No. of Int	ervals	32	End Date/Time	1/16/2012 12:00AM
TVD Fluid Top		Fluid Head	Total Sho	ots	192	Net Perforation Interval	56.00 (usft)
Hydrostatic Press		Press Difference	Avg Sho	Density	3.43 (shot/ft)	Final Surface Pressure	
Balance Cond	NEUTRAL					Final Press Date	

# 2 Intervals

# 2.1 Perforated Interval

Date Formation/ CCL@ (usft)	CCL-T MD Top MD S (usft) (u	Base Shot   usft) Density   (shot/ft)	Misfires/ Diamete Carr Type /Carr Manuf Add. Shot r (in)	Carr Phasing Charge Desc/Ch Size (") Manufacture	
1/16/2012 WASATCH/ 12:00AM	5,670.0 5	5,672.0 4.00	0.360 EXP/	3.375 90.00	23.00 PRODUCTIO

## 2.1 Perforated Interval (Continued)


Date	Formation/	CCL@		MD Top		Shot		nete	Carr Type /Carr Manuf	Carr	Phasing	Charge Desc/Charge	Charge	Reason	Misrun
	Reservoir	(usft)	(usft)	(usft)	(usft)	Density (shot/ft)		r n)		Size (in)	()	Manufacturer	Weight (gram)		
1/16/2012 12:00AM	WASATCH/		1(45(5), 1	5,736.0	5,738.0	4.00		).360	EXP/	3.375	90.00			PRODUCTIO N	1
1/16/2012 12:00AM	WASATCH/			5,805.0	5,807.0	4.00	(	).360	EXP/	3.375	90.00		23,00	PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			6,882.0	6,884.0	3.00	(	).360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			6,926.0	6,928.0	3.00	(	).360	EXP/	3.375	120.00		23.00	PRODUCTIO N	:
1/16/2012 12:00AM	MESA VERDE/			6,963.0	6,965.0	3.00	(	).360	EXP/	3.375	120.00		23.00	PRODUCTIO N	:
1/16/2012 12:00AM	MESA VERDE/	: : : :		7,030.0	7,031.0	3.00	C	).360	EXP/	3.375	120.00	:	23.00	PRODUCTIO N	:
1/16/2012 12:00AM	MESA VERDE/			7,087.0	7,088.0	3.00	C	360	EXP/	3.375	120.00	!	23.00	PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			7,199.0	7,201.0	3.00	. 0	.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			7,246.0	7,248.0	3.00	0	.360 [	EXP/	3.375	120.00	,	23.00	PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			7,321.0	7,324.0	3.00	O	.360 I	EXP/	3.375	120.00		23.00	PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			7,369.0	7,370.0	3.00	0	.360 E	EXP/	3.375	120.00	:		PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			7,480.0	7,482.0	3.00	0	.360 E	EXP/	3.375	120.00			PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			7,516.0	7,518.0	3.00	0	.360 E	EXP/	3.375	120.00		23.00	PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			7,549.0	7,550.0	3.00	0	.360 E	EXP/	3.375	120.00	:	23.00	PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			7,581.0	7,584.0	3.00	0	.360 E	EXP/	3.375	120.00	i :		PRODUCTIO N	:
1/16/2012 12:00AM	MESA VERDE/			7,642.0	7,644.0	4.00	0	.360 E	EXP/	3.375	90.00			PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			7,736.0	7,738.0	4.00	0	.360 E	EXP/	3.375	90.00			PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			7,762.0	7,764.0	4.00	0	360 E	EXP/	3.375	90.00	:		PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			7,860.0	7,861.0	3.00	0.	.360 E	EXP/	3.375	120.00			PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			7,904.0	7,906.0	3.00	0.	360 E	EXP/	3.375	120.00			PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			7,920.0	7,922.0	3.00	0.	360 E	XP/	3.375	120.00			PRODUCTIO N	

## 2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir	CCL@ (usft)	CCL-T S (usft)	MD Top (usft)	MD Base (usft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diamete r (in)	Carr Type /Carr Manuf	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
1/16/2012 12:00AM	MESA VERDE/			7,960.0	7,961.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			7,978.0	7,979.0	3.00		0.360	EXP/	3.375	120.00			PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			8,007.0	8,008.0	3.00		0.360	EXP/	3.375	120.00			PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			8,052.0	8,053.0	4.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			8,075.0	8,076.0	4.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			8,110.0	8,112.0	4.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			8,170.0	8,172.0	4.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			8,392.0	8,394.0	4.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			8,416.0	8,417.0	4.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	
1/16/2012 12:00AM	MESA VERDE/			8,511.0	8,514.0	4.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	

# 3 Plots

## 3.1 Wellbore Schematic



					Operation	n Summar	y Report	
Well: NBU 922-	3604BS GRE	EN		and the second s	and the second s	and the state of t	Spud Date: 10/2	25/2011
Project: UTAH-	UINTAH			Site: NBI	J 922-360 PAD	)		Rig Name No: ROYAL WELL SERVICE/3
Event: COMPL	ETION			Start Dat	e: 1/9/2012			End Date:
Active Datum: F	RKB @4,982.0	Ousft (at	ove Mean Se			/0/9/S/22/E/36/0	/0/26/PM/S/125	
Level)		`						
Date	Tim Start-l	Estate of the	Duration (hr)	Phase	Code Sui		MD From (usft)	Operation
10/25/2011	-							V Prince Control of the Control of t
1/9/2012	12:00 -	14:00	2.00	COMP	33	<b>P</b>		FILL SURFACE CSG. MIRU B&C QUICK TEST. PSI TEST T/ 1000 PSI. HELD FOR 15 MIN LOST 17 PSI. PSI TEST T/ 3500 PSI. HELD FOR 15 MIN LOST 21
								PSI. 1ST PSI TEST T/ 7000 PSI. HELD FOR 30 MIN LOST
								63 PSI. NO COMMUNICATION OR MIGRATION WITH
								SURFACE CSG BLEED OFF PSI. MOVE T/ NEXT WELL.
1/13/2012 1/16/2012		12:30 8:00	1.50	COMP	37 48	P		SMIFW PERF STG 1)PU 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 DEG PHASING. RIH PERF AS PER PERF DESIGN. POOH. SMIFW
	8:00 - 4	18:30	10.50	СОМР	36 B	P		PERF & FRAC FOLLOWING WELL AS PER DESIGN W/ 30/50 MESH SAND & SLK WTR. ALL CBP'S ARE HALIBURTON 8K CBP'S. REFER TO STIM PJR FOR FLIUD, SAND AND CHEMICL VOLUME PUM'D
								FRAC STG #1] WHP=745#, BRK DN PERFS=4,980#, @=4.1 BPM, INJ RT=52.3, INJ PSI=5,96#, INITIAL ISIP=2,673#, INITIAL FG=.75, FINAL ISIP=2,675#, FINAL FG=.76, AVERAGE RATE=50.7, AVERAGE PRESSURE=5,132#, MAX RATE=53.4, MAX PRESSURE=6,486#, NET PRESSURE INCREASE=2#, 22/24 90% CALC PERFS OPEN. X OVER TO WIRE LINE
								PERF STG #2] P/U RIH W/ HALIBURTON 8K CBP & PERF GUN, SET CBP @=8,202', PERF MESAVERDE USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS PERSAY IN PROCEDURE, X OVER TO FRAC CREW
								FRAC STG #2] WHP=1,510#, BRK DN PERFS=5,076#, @=1.8 BPM, INJ RT=39.6, INJ PSI=5,776#, INITIAL ISIP=2,722#, INITIAL FG=.77, FINAL ISIP=2,777#, FINAL FG=.78, AVERAGE RATE=48.5, AVERAGE PRESSURE=5,659#, MAX RATE=52.9, MAX PRESSURE=6,733#, NET PRESSURE INCREASE=2#, 15/24 63% CALC PERFS OPEN. X OVER TO WIRE LINE
1/17/2012	7:00 -	7:15	0.25	СОМР	48	P		PERF STG #3] P/U RIH W/ HALIBURTON 8K CBP & PERF GUN, SET CBP @=8,038', PERF MESAVERDE USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS PERSAY IN PROCEDURE, X OVER TO FRAC CREW. SWIFN. HSM, SLIPS / TRIPS / FALLS

Well: NBU 922-3	604BS GREEN			2.20 1 1 2.20 1 No. 20 1 1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2			Spud Date: 10/	/25/2011
Project: UTAH-L			Site: NR	U 922-36O	DAD		Opud Date. 10/	
Event: COMPLE				· · · · · · · · · · · · · · · · · · ·				Rig Name No: ROYAL WELL SERVICE/3
				te: 1/9/201				End Date:
evel)	KB @4,982.00usft (a	above Mean Se	a	UWI: SW/SE/0/9/S/22/E/36/0/0/26/PM/S/125			6/0/0/26/PM/S/12	50/E/0/2103/0/0
Date	Time	Duration	Phase	Code	Sub	P/U	MD From	Operation .
	Start-End	(hr)			Code	3	(usft)	
	7:15 - 17:30	10.25	COMP	36	В	P		FRAC STG #3] WHP=1,660#, BRK DN
								PERFS=4,074#, @=4.6 BPM, INJ RT=50.5, INJ
								PSI=5,731#, INITIAL ISIP=2,422#, INITIAL FG=.74,
								FINAL ISIP=2,777#, FINAL FG=.78, AVERAGE
								RATE=48.5, AVERAGE PRESSURE=5,022#, MAX
	11							RATE=53.1, MAX PRESSURE=6,370#, NET
				٠.				PRESSURE INCREASE=407#, 20/24 83% CALC
								PERFS OPEN. X OVER TO WIRE LINE
								PERF STG #4] P/U RIH W/ HALIBURTON 8K CBP &
								PERF GUN, SET CBP @=7,794', PERF MESAVERDE
								USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE, AS
								PERSAY IN PROCEDURE, X OVER TO FRAC CREW
								FRAC STG #4] WHP=2,100#, BRK DN
								PERFS=2,917#, @=4.6 BPM, INJ RT=48.3, INJ
								PSI=5,981#, INITIAL ISIP=2,288#, INITIAL FG=.74,
								FINAL ISIP=1,984#, FINAL FG=.70, AVERAGE
								RATE=49.6, AVERAGE PRESSURE=5,142#, MAX
								RATE=51.2, MAX PRESSURE=5,995#, NET
								PRESSURE INCREASE=-304#, 17/24 70% CALC
								PERFS OPEN. X OVER TO WIRE LINE
								PERF STG #5] P/U RIH W/ HALIBURTON 8K CBP &
								PERF GUN, SET CBP @=7,614', PERF MESAVERDE
								USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS
								PERSAY IN PROCEDURE, X OVER TO FRAC CREW
								FRAC STG #5] WHP=1,050#, BRK DN
								PERFS=6,010#, @=1.8 BPM, INJ RT=48.2, INJ
								PSI=5,658#, INITIAL ISIP=1,903#, INITIAL FG=.69,
								FINAL ISIP=2,172#, FINAL FG=.73, AVERAGE
								RATE=50.7, AVERAGE PRESSURE=4,562#, MAX
								RATE=52, MAX PRESSURE=6,640#, NET PRESSURE
								INCREASE=269#, 17/24 69% CALC PERFS OPEN. X
								OVER TO WIRE LINE
								PEDE CTO #01 DAI DIVINA
								PERF STG #6] P/U RIH W/ HALIBURTON 8K CBP &
								PERF GUN, SET CBP @=7,400', PERF MESAVERDE
								USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS
								PERSAY IN PROCEDURE, X OVER TO FRAC CREW.
4/49/0040	7.00		00:					SWIFN
1/18/2012	7:00 - 7:15	0.25	COMP	48		Ρ		HSM, R/D

					EGION	
Well: NBU 922-36O4BS GREEN				W.	Spud Date: 10/	QE/0044
Project: UTAH-UINTAH	Site: NR	U 922-360	) PAD		Spud Date: 10/	
				т		Rig Name No: ROYAL WELL SERVICE/3
Event: COMPLETION		te: 1/9/201				End Date:
Active Datum: RKB @4,982.00usft (above Mean Level)	Sea	UWI: SI	N/SE/0/9/	S/22/E/3	36/0/0/26/PM/S/12	50/E/0/2103/0/0
Date Time Duration Start-End (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
7:15 - 7:15 0.00	COMP	36	B	P	(USI)	FRAC STG #6] WHP=1,400#, BRK DN PERFS=4,634#, @=4.6 BPM, INJ RT=52.4, INJ PSI=5,040#, INITIAL ISIP=2,114#, INITIAL FG=.73, FINAL ISIP=2,263#, FINAL FG=.75, AVERAGE RATE=52.1, AVERAGE PRESSURE=4,469#, MAX RATE=52.8, MAX PRESSURE=5,702#, NET PRESSURE INCREASE=149#, 23/24 94% CALC PERFS OPEN. X OVER TO WIRE LINE  PERF STG #7] P/U RIH W/ HALIBURTON 8K CBP & PERF GUN, SET CBP @=7,118*, PERF MESAVERDE USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS PERSAY IN PROCEDURE, X OVER TO FRAC CREW  FRAC STG #7] WHP=1,020#, BRK DN PERFS=4,171#, @=4.5 BPM, INJ RT=36.6, INJ PSI=6,034#, INITIAL ISIP=1,894#, INITIAL FG=.71, FINAL ISIP=2,407#, FINAL FG=.78, AVERAGE RATE=48.9, AVERAGE PRESSURE=5,472#, MAX RATE=53.2, MAX PRESSURE=6,731#, NET PRESSURE INCREASE=513#, 14/24 60% CALC PERFS OPEN. X OVER TO WIRE LINE  PERF STG #8] P/U RIH W/ HALIBURTON 8K CBP & PERF GUN, SET CBP @=5,837", PERF MESAVERDE USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS PERSAY IN PROCEDURE, X OVER TO FRAC CREW  FRAC STG #8] WHP=425#, BRK DN PERFS=2,012#, @=3.8 BPM, INJ RT=52.8, INJ PSI=4,139#, INITIAL ISIP=1,075#, INITIAL FG=.63, FINAL ISIP=1,483#, FINAL FG=.70, AVERAGE RATE=51.5, AVERAGE PRESSURE=3,996#, MAX RATE=52.9, MAX PRESSURE=4,925#, NET PRESSURE INCREASE=408#, 14/24 60% CALC PERFS OPEN. X OVER TO WIRE LINE  P/U RIH W/ HALIBURTON 8K CBP, SET FOR TOP KILL @=5,620
1/21/2012 7:00 - 7:15 0.25	COMP	48		Р		TOTAL FLUID PUMP'D=9,745 BBLS TOTAL SAND PUMP'D=210,672# SAFETY = JSA.

Well: NBU 922-36O4BS GREEN		
		Spud Date: 10/25/2011
Project: UTAH-UINTAH	Site: NBU 922-360 PAD	Rig Name No: ROYAL WELL SERVICE/3
Event: COMPLETION	Start Date: 1/9/2012	End Date:
Active Datum: RKB @4,982.00usft (above Mear Level)	Sea UWI: SW/SE/0/9/S/2	2/E/36/0/0/26/PM/S/1250/E/0/2103/0/0
Date Time Duration Start-End (hr)	Phase Code Sub F	P/U MD From Operation (usft)
7:15 - 18:00 10.75		P SICP= 0#. MIRU. NDWH. NUBOP. P/U & RIH W/ 177  JTS 2-3/8" L-80 4.7# TBNG + XN + POBS + 3-7/8"  BIT. T/U ON FIRST CBP @ 5620'. R/U PUMP & TEST  BOP'S GOOD @ 3000#. P/U SWIVEL. BREAK CIRC.  T/U ON KILL CBP & BEGIN D/O AS FOLLOWS:
		CBP #1) DRLG OUT BAKER 8K CBP @ 5620' IN 6 MIN. 0 LBS DIFF. PSI. RIH, TAG SND @ 5819'. C/O 18' OF SND. FCP = 0 PSI.
		CBP #2) DRLG OUT BAKER 8K CBP @ 5837" IN 8 MIN. 400 LBS DIFF. PSI. RIH, TAG SND @ 7072 '. C/O 46' OF SND. FCP = 30 PSI.
		CBP #3) DRLG OUT BAKER 8K CBP @ 7118' IN 12 MIN. 400 LBS DIFF. PSI. RIH, TAG SND @ 7383'. C/O 17' OF SND. FCP = 140 PSI.
		CBP #4) DRLG OUT BAKER 8K CBP @ 7400' IN 8 MIN. 200 LBS DIFF. PSI. RIH, TAG SND @ 7595'. C/O 19' OF SND. FCP = 400 PSI.
		CBP #5) DRLG OUT BAKER 8K CBP @ 7614' IN 7 MIN. 100 LBS DIFF. PSI. RIH, TAG SND @ 7774'. C/O 20' OF SND. FCP = 490 PSI.
		CBP #6) DRLG OUT BAKER 8K CBP @ 7794' IN 7 MIN. 200 LBS DIFF. PSI. RIH, TAG SND @ 8021'. C/O 17' OF SND. FCP = 560 PSI.
		CBP #7) DRLG OUT BAKER 8K CBP @ 8038' IN 5 MIN. 100 LBS DIFF. PSI. RIH, TAG SND @8173'. C/O 29' OF SND. FCP = 560 PSI.
		CBP #8) DRLG OUT BAKER 8K CBP @ 8202' IN 7 MIN. 300 LBS DIFF. PSI. RIH, TAG SND @ 8375'. C/O TO 8631' W/ 272 JTS + BHA. FCP = 650 PSI.
		L/D 20 JTS TBNG. LAND WELL AS FOLLOWS:
		KB=14 HANGER=.83' 252 JTS. 2-3/8" N-80 4.7# TBNG =7992.61' XN = 1.34' POBS = 1.68' EOT @ 8010.46'
1/24/2012 7:00 -	PROD 50	NDBOP. NUWH. TEST FLOW LINES ( GOOD ) @ 2500 PSI. DROP BALL & PUMP OFF BIT. RDMO. WELL TURNED OVER TO FB CREW @ 1700 W/ CP= 2125#. TP= 1450#.  TWLTR = 8145 BBLS  WELL IP'D ON 1/24/12 - 2720 MCFD, 0 BOPD, 510 BWPD, CP 1720 #, FTP 1383#, CK 20/64", LP 70#, 24




Project: Uintah County, UT UTM12 Site: NBU 922-360 PAD Well: NBU 922-36O4BS

Wellbore: OH Design: OH




WELL DETAILS: NBU 922-3604BS GL 4968 & KB 14 @ 4982.00ft (ENSIGN 139) +N/-S 0.00 Northing 14526025.01 Easting 2092599.82 Latittude Longitude 109° 23' 8.520 W 39° 59' 19.331 N






Azimuths to True North Magnetic North: 11.079

Magnetic Field Strength: 52373.7snT Dip Angle: 65.89° Date: 2011/02/07 Model: IGRF2010





## PROJECT DETAILS: Uintah County, UT UTM12

Geodetic System: Universal Transverse Mercator (US Survey Feet)
Datum: NAD 1927 - Western US
Ellipsoid: Clarke 1866

Zone: Zone 12N (114 W to 108 W) Location: SECTION 36 T9S R22E System Datum: Mean Sea Level

Design: OH (NBU 922-36O4BS/OH)

Created By: RobertScott Date: 15:01, January 03 2012



# **Kerr McGee Oil and Gas Onshore LP**

Uintah County, UT UTM12 NBU 922-360 PAD NBU 922-3604BS

OH

Design: OH

# **Standard Survey Report**

03 January, 2012







Company:

Kerr McGee Oil and Gas Onshore LP

Project: Site: Well:

Uintah County, UT UTM12 NBU 922-360 PAD

NBU 922-36O4BS

Wellbore: Design:

OH ОН Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference: Survey Calculation Method:

Database:

Well NBU 922-36O4BS

GL 4968 & KB 14 @ 4982.00ft (ENSIGN 139) GL 4968 & KB 14 @ 4982.00ft (ENSIGN 139)

Minimum Curvature EDM5000-RobertS-Local

Project Uintah County, UT UTM12

Map System: Geo Datum: Map Zone:

Universal Transverse Mercator (US Survey Feet)

NAD 1927 - Western US

Zone 12N (114 W to 108 W)

System Datum:

Mean Sea Level

Site NBU 922-360 PAD, SECTION 36 T9S R22E

Site Position: From:

Lat/Long

Northing: Easting:

14,526,021.20 usft

Latitude: Longitude: 39° 59' 19.295 N

**Position Uncertainty:** 

0.00 ft

2,092,590.64 usft

Slot Radius:

13.200 in

**Grid Convergence:** 

109° 23' 8,639 W 1.04 °

Well NBU 922-36O4BS, 1250 FSL 2103 FEL

Well Position

+N/-S +E/-W 0.00 ft 0.00 ft

Northing: Easting:

14,526,025.01 usft 2,092,599.82 usft Latitude: Longitude:

39° 59' 19.331 N 109° 23' 8.520 W

**Position Uncertainty** 

0.00 ft

Wellhead Elevation:

fŧ

**Ground Level:** 

4,968.00 ft

0.00

	IGRF2010 2011/0	02/07 11.07	65.89	52,374
Magnetics Mod	el Name Sample Date	e Declination (°)	Dip Angle F (°)	ield Strength (nT)
Wellbore OH	oka (149. Julya, Halis helisa kapitalish pereje salah dari			

Design ОН **Audit Notes:** 

Version:

1.0

2,432.00

Phase:

**ACTUAL** 

Tie On Depth:

Vertical Section: Depth From (TVD) +N/-S +E/-W Direction (ft) (ft) **(°)** 0.00 0.00 0.00 161.04

Survey Program Date 2012/01/03 From To (ft) **(ft)** Survey (Wellbore)

10.00 2,380.00 Survey #1 SDI MWD SURFACE (OH)

**Tool Name** MWD SDI 8,720.00 Survey #2 SDI MWD PRODUCTION (OH) MWD SDI

Description

MWD - Standard ver 1.0.1 MWD - Standard ver 1.0.1

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
10.00	0.00	0.00	10.00	0.00	0.00	0.00	0.00	0.00	0.00
191.00	0.88	46.31	190.99	0.96	1.01	-0.58	0.49	0.49	0.00
FIRST SDI N	NWD SURFACE	SURVEY							
276.00	0.70	117.15	275.99	1.17	1.94	-0.48	1.09	-0.21	83.34
360.00	1.85	168.57	359.97	-0.39	2.66	1.23	1.80	1.37	61.21
450.00	3.52	178.77	449.86	-4.58	3.01	5.31	1.92	1.86	11.33
540.00	5.06	175.55	539.61	-11.30	3.38	11.78	1.73	1.71	-3.58
630.00	6.26	169.31	629.17	-20.07	4.60	20.48	1.50	1.33	-6.93
720.00	7.75	162.73	718.50	-30,69	7.31	31.40	1.88	1.66	-7.31





Company:

Kerr McGee Oil and Gas Onshore LP

Project: Site: Well:

Uintah County, UT UTM12

NBU 922-360 PAD NBU 922-3604BS

Wellbore: Design:

ОН OH Local Co-ordinate Reference:

TVD Reference: MD Reference:

North Reference:

Survey Calculation Method:

Database:

Well NBU 922-36O4BS

GL 4968 & KB 14 @ 4982.00ft (ENSIGN 139) GL 4968 & KB 14 @ 4982.00ft (ENSIGN 139)

True

Minimum Curvature

EDM5000-RobertS-Local

Measured			Vertical			Vertical	Dogleg	Build	Turn
Depth (ft)	Inclination (°)	Azimuth (°)	Depth (ft)	+N/-S (ft)	+E/-W (ft)	Section (ft)	Rate (°/100ft)	Rate (°/100ft)	Rate (°/100ft)
810.00	9.27	158.68	807.51	-43.24	11.75	44.71	1.81	1.69	-4.50
900.00	10.82	162.23	896.12	-58.04	16.96	60.40	1.85	1.72	3,94
990.00	12.40	162.38	984.28	-75.29	22.46	78.51	1.76	1.76	0.17
1,080.00	13.65	161.98	1,071.96	-94.60	28.67	98.79	1.39	1.39	-0.44
1,170.00	14.79	162.95	1,159.20	-115.68	35.33	120,89	1.29	1.27	1,08
1,260.00	16.47	161.81	1,245.87	-138.79	42.68	145.13	1.90	1.87	-1.27
1,350.00	19.05	159.25	1,331.58	-164,65	51.87	172.57	2.99	2.87	-2,84
1,440.00	20.51	157.80	1,416.27	-192.98	63.03	202.99	1.71	1.62	-1.61
1,530.00	20.62	157.53	1,500.53	-222.23	75.04	234.55	0.16	0.12	-0.30
1,620.00	21,80	156.41	1,584.43	-252.19	87.79	267.03	1.39	1,31	-1.24
1,710.00	20.66	156.55	1,668.32	-282.07	100.80	299.51	1.27	-1.27	0.16
1,800.00	19.06	156.58	1,752.97	-310.12	112,95	330.00	1.78	-1.78	0.03
1,890.00	19.99	159.95	1,837.79	-338.06	124.07	360.03	1.62	1.03	3.74
1,980.00	19.69	163.69	1,922.46	-367.06	133.60	390.56	1.45	-0.33	4.16
2,070.00	20.41	163.65	2,007.00	-396.67	142.28	421.38	0.80	0.80	-0.04
2,160.00	18.99	165.03	2,091.73	-425.88	150.48	451.67	1.66	-1.58	1.53
2,250.00	18.89	163.69	2,176.86	-454.01	158.35	480.83	0.50	-0,11	-1.49
2,380.00	19.93	164.42	2,299.47	-495.55	170.21	523.97	0.82	0.80	0.56
LAST SDI M	WD SURFACE S	URVEY							
2,432.00	19.61	163.61	2,348.40	-512.46	175.06	541.53	0.81	-0.62	-1.56
	WD PRODUCTION	ON SURVEY							
2,522.00	19.17	161.31	2,433.30	-540.94	184.05	571.40	0.98	-0.49	-2.56
2,613.00	18.66	158.45	2,519.39	-568.64	194.19	600.88	1.16	-0.56	-3.14
2,704.00	18.04	161.57	2,605.76	-595.55	203.99	629.51	1.28	-0.68	3.43
2,794.00	18.48	160.32	2,691.23	-622.20	213.20	657.71	0,65	0.49	-1.39
2,885.00	18.11	159.68	2,777.63	-649.04	222.97	686.27	0.46	-0.41	-0.70
2,975.00	17.74	161.11	2,863.26	-675.13	232.27	713.97	0.64	-0.41	1.59
3,066.00	15,08	157.64	2,950.55	-699.20	241.26	739.65	3,11	-2.92	-3.81
3,156.00	12.65	158.61	3,037.92	-719.21	249.31	761.19	2.71	<b>-</b> 2.70	1.08
3,247.00	11.87	158.51	3,126.84	-737.20	256.37	780.50	0.86	-0.86	-0.11
3,337.00	9.67	163.02	3,215.26	-753.04	261.97	797.30	2.62	-2.44	5.01
3,428.00	8.40 7.86	164.30	3,305.12	-766.75	266,00	811.57	1.41	-1.40	1.41
3,518.00	7.86	165.72	3,394.22	-779.04	269,30	824.27	0.64	-0.60	1.58
3,609.00	6.13	166.51	3,484.54	-789.80	271.97	835.31	1.90	-1.90	0.87
3,699.00	5.02	162.23	3,574.11	-798.22	274.29	844.03	1.32	-1.23	<del>-4</del> .76
3,790.00	4.30	164.12	3,664.81	-805.29	276.44	851.42	0.81	-0.79	2.08
3,880.00	2.68	172.22	3,754.64	-810.62	277.65	856.85	1.88	-1.80	9.00
3,971.00	1.82	177.57	3,845.57	-814.17	278.00	860.32	0.97	-0.95	5.88
4,061.00	0.98	150.02	3,935.54	-816.27	278.44	862.45	1.17	-0.93	-30.61
4,152.00	0.73	163.48	4,026.53	-817.50	278.99	863.79	0.35	-0.27	14.79
4,242.00	0.44	155.99	4,116.53	-818.36	279.30	864.71	0.33	-0.32	-8.32
4,333.00 4,423.00	0.77	170.90	4,207.52	-819.29	279.54	865.66	0.40	0.36	16.38





Company:

Kerr McGee Oil and Gas Onshore LP

Project:

Uintah County, UT UTM12

Site: Well: NBU 922-360 PAD NBU 922-3604BS

Wellbore: Design: ОН ОН Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference:

Survey Calculation Method: Database:

Well NBU 922-36O4BS

GL 4968 & KB 14 @ 4982.00ft (ENSIGN 139)

GL 4968 & KB 14 @ 4982.00ft (ENSIGN 139)

Minimum Curvature

EDM5000-RobertS-Local

Measured			Vertical			Vertical	Dogleg	Build	Turn
Depth (ft)	Inclination (°)	Azimuth (°)	Depth (ft)	+N/-S (ft)	+E/-W (ft)	Section (ft)	Rate (°/100ft)	Rate (°/100ft)	Rate (°/100ft)
4,514.00	1.06	195,77	4,388.51	-821.61	278.87	867.64	0.49	0.43	-15.81
4,605.00	0.27	45.23	4,479.50	-822.27	278.80	868.24	1.43	-0.87	-165,43
4,695.00	0.62	34.17	4,569.50	-821.72	279.22	867.86	0.40	0.39	-12.29
4,785.00	0.25	138.70	4,659.50	-821.46	279.62	867.74	0.80	-0.41	116,14
4,876.00	0.37	128.68	4,750.50	-821.79	279.98	868.18	0.14	0.13	-11.01
4,967.00	0.61	171.70	4,841.49	-822.46	280.28	868.90	0.46	0.26	47.27
5,057.00	0.62	179.89	4,931.49	-823.42	280.35	869,83	0.10	0.01	9.10
5,148.00	0.62	189.98	5,022.48	-824.39	280.27	870.73	0.12	0.00	11.09
5,238.00	0.85	169.90	5,112.48	-825,53	280.30	871.81	0.38	0.26	-22.31
5,329.00	0.91	290.11	5,203.47	-825.95	279.74	872.03	1.68	0.07	132.10
5,419.00	0.82	295.66	5,293.46	-825.42	278.49	871.12	0.14	-0.10	6.17
5,510.00	0.70	280.18	5,384.45	-825.04	277.36	870,40	0.26	-0.13	-17.01
5,601.00	1.32	16.60	5,475.44	-823.94	277.11	869.27	1.72	0.68	105.96
5,691.00	1.32	22.04	5,565.42	-821.99	277.79	867.65	0.14	0.00	6.04
5,782.00	0.54	19.62	5,656.41	-820.61	278.33	866.52	0.86	-0.86	-2.66
5,872.00	0.27	55.79	5,746.40	-820.09	278,65	866.13	0.40	-0.30	40.19
5,963.00	0.18	72.88	5,837.40	-819.93	278.96	866.08	0.12	-0.10	18.78
6,053.00	0.35	60.28	5,927.40	-819.75	279.34	866.03	0.20	0.19	-14.00
6,144.00	0.63	128.28	6,018.40	-819.92	279.97	866.40	0.65	0.31	74.73
6,234.00	0.88	138.24	6,108.39	-820.74	280.82	867.46	0.31	0.28	11.07
6,325.00	0.17	113.38	6,199.39	-821.32	281.41	868.19	0.80	-0.78	-27.32
6,415.00	0.79	47.62	6,289.38	-820.95	281.99	868.03	0.82	0.69	-73.07
6,506.00	0.42	141.54	6,380.38	-820.79	282.66	868.10	1.01	-0.41	103.21
6,596.00	0.79	119.53	6,470.37	-821.36	283.40	868.87	0.48	0.41	-24.46
6,687.00	0.61	108.67	6,561.37	-821.82	284.41	869.64	0.24	-0.20	-11.93
6,778.00	0.88	137.05	6,652.36	-822,49	285.34	870,57	0.49	0.30	31.19
6,868.00	0.76	132.81	6,742.35	-823.40	286.25	871.73	0.15	-0.13	-4.71
6,959.00	1.16	109.70	6,833.34	-824.12	287.56	872.84	0.60	0.44	-25.40
7,049.00	0.97	128.92	6,923.32	-824.91	289.01	874.05	0.45	-0.21	21.36
7,139.00	0.59	267.63	7,013.32	-825.40	289.14	874.57	1.63	-0.42	154.12
7,230.00	0.34	211.86	7,104.32	-825.65	288.53	874.60	0.54	-0.27	-61.29
7,320.00	1.23	191.30	7,194.31	-826.83	288.20	875.61	1.02	0.99	-22.84
7,411.00	1.44	180.94	7,285.28	-828.93	287.99	877.52	0.35	0.23	-11.38
7,501.00	0.70	204.44	7,375.27	-830.56	287.75	878.99	0.94	-0.82	26.11
7,592.00	0.83	357.76	7,466.26	-830.41	287.49	878.76	1.64	0.14	168.48
7,682.00	0.49	6.95	7,556.26	-829.37	287.51	877.79	0.39	-0.38	10.21
7,773.00	0.83	63.74	7,647.25	-828.69	288.15	877.36	0.76	0.37	62.41
7,863.00	0.28	7.27	7,737.25	-828.19	288.76	877.08	0.79	-0.61	-62.74
7,953.00	0.19	244.19	7,827.25	-828.03	288.66	876.90	0.46	-0.10	-136.76
8,044.00	0.37	3.43	7,918.25	-827.81	288.54	876.64	0.54	0.20	131.03
8,134.00	0.26	56.32	8,008.25	-827.40	288.72	876.32	0.33	-0.12	58.77
8,225.00	0.71	93.85	8,099.24	-827.33	289.46	876.49	0.58	0.49	41.24
8,315.00	1.00	118.76	8,189.23	-827.74	290.70	877.29	0.52	0.32	27.68





Company:

Kerr McGee Oil and Gas Onshore LP

Project: Site: Well:

Uintah County, UT UTM12 NBU 922-360 PAD

NBU 922-36O4BS

Wellbore: Design:

ОН ОН Local Co-ordinate Reference:

TVD Reference:

MD Reference: North Reference: Well NBU 922-36O4BS

GL 4968 & KB 14 @ 4982.00ft (ENSIGN 139)

GL 4968 & KB 14 @ 4982.00ft (ENSIGN 139)

Minimum Curvature

**Survey Calculation Method:** Database: EDM5000-RobertS-Local

Measured			Vertical			Vertical	Dogleg	Build	Turn
Depth in (ft)	clination (°)	Azimuth (°)	Depth (ft)	+N/-S (ft)	+E/-W (ft)	Section (ft)	Rate (°/100ft)	Rate (°/100ft)	Rate (°/100ft)
8,496.00	1.43	113.42	8,370.19	-828.93	294.34	879.59	0.39	0.22	14.12
8,587.00	1.42	124.07	8,461.16	-830.02	296.32	881.26	0.29	-0.01	11.70
8,661.00	1.19	144.56	8,535.15	-831.15	297.52	882.73	0.70	-0.31	27.69
LAST SDI MWD	PRODUCTIO	N SURVEY							27.00
8,720.00	1.19	144.56	8.594.13	-832.15	298.23	883.90	0.00	0.00	0.00

Design Annotations  Measured  Depth  (ft)	Vertical Depth (ft)	Local Coord	+E/-W	
191.00 2,380.00	190.99 2,299.47	(ft) 0.96 -495.55	<b>(ft)</b> 1.01 170.21	Comment  FIRST SDI MWD SURFACE SURVEY  LAST SDI MWD SURFACE SURVEY

1		
Checked By:	Amman and Dec	
Officered by.	Approved By:	Date:



# **Kerr McGee Oil and Gas Onshore LP**

Uintah County, UT UTM12 NBU 922-360 PAD NBU 922-3604BS

OH

Design: OH

# **Survey Report - Geographic**

03 January, 2012





# SDI Survey Report - Geographic



Company:

Kerr McGee Oil and Gas Onshore LP

Project:

Uintah County, UT UTM12

Site: Well: NBU 922-360 PAD NBU 922-36O4BS

Wellbore: Design:

ÓН OH Local Co-ordinate Reference:

TVD Reference:

Well NBU 922-36O4BS GL 4968 & KB 14 @ 4982,00ft (ENSIGN 139)

MD Reference:

GL 4968 & KB 14 @ 4982.00ft (ENSIGN 139)

North Reference:

Survey Calculation Method: Database:

Minimum Curvature EDM5000-RobertS-Local

Map System:

Uintah County, UT UTM12

Universal Transverse Mercator (US Survey Feet) NAD 1927 - Western US

Geo Datum: Map Zone:

Project

Zone 12N (114 W to 108 W)

System Datum:

Mean Sea Level

Site

From:

NBU 922-360 PAD, SECTION 36 T9S R22E

Site Position:

Lat/Long

Northing: Easting:

14,526,021.20 usft

Latitude:

39° 59' 19.295 N

**Position Uncertainty:** 

2,092,590.64 usft

Longitude:

0.00 ft

Slot Radius:

13.200 in

Grid Convergence:

109° 23' 8.639 W

1.04°

Well

NBU 922-36O4BS, 1250 FSL 2103 FEL

Well Position

0.00 ft 0.00 ft

Northing: Easting:

14,526,025.01 usft 2,092,599.82 usft Latitude: Longitude:

39° 59' 19,331 N 109° 23' 8.520 W

**Position Uncertainty** 

0.00 ft

Wellhead Elevation:

ft

Ground Level:

4,968.00 ft

Wellbore

OH

+N/-S

+E/-W

Magnetics

**Model Name** 

Sample Date

Declination (°)

Dip Angle (°)

Field Strength

(nT)

161.04

**IGRF2010** 

2011/02/07

0.00

11.07

65.89

52.374

Design

Audit Notes:

Version:

1.0

OН

Phase:

**ACTUAL** 

Tie On Depth:

0.00

Vertical Section:

Depth From (TVD)

+N/-S

+E/-W

Direction

0.00

(ft) 0.00

(°)

Survey Program From

(ft)

To (ft)

Survey (Wellbore)

Date

**Tool Name** 

Description

10.00 2,432.00 2,380.00 Survey #1 SDI MWD SURFACE (OH) 8,720.00 Survey #2 SDI MWD PRODUCTION (OH)

2012/01/03

MWD SDI MWD SDI

MWD - Standard ver 1.0.1 MWD - Standard ver 1.0.1

Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
0.00	0.00	0.00	0.00	0.00	0.00	14,526,025.01	2,092,599.82	39° 59' 19.331 N	109° 23' 8.520 W
10.00	0.00	0.00	10.00	0.00	0.00	14,526,025.01	2,092,599.82	39° 59' 19,331 N	109° 23' 8.520 W
191.00	0.88	46.31	190.99	0.96	1.01	14,526,025.99	2,092,600.81	39° 59' 19.340 N	109° 23' 8.507 W
FIRST SI	DI MWD SURF	ACE SURVE	Y						
276.00	0.70	117.15	275.99	1.17	1.94	14,526,026.22	2,092,601.74	39° 59' 19.342 N	109° 23' 8,495 W
360.00	1.85	168.57	359.97	-0.39	2.66	14,526,024.67	2,092,602.49	39° 59' 19.327 N	109° 23' 8.486 W
450.00	3.52	178.77	449.86	-4.58	3,01	14,526,020.49	2,092,602.91	39° 59' 19.286 N	109° 23' 8.481 W
540.00	5.06	175.55	539.61	-11.30	3.38	14,526,013.78	2,092,603.40	39° 59' 19,219 N	109° 23' 8.477 W
630.00	6.26	169.31	629.17	-20.07	4.60	14,526,005.02	2,092,604.78	39° 59' 19.132 N	109° 23' 8.461 W
720.00	7.75	162.73	718.50	-30.69	7.31	14,525,994.46	2,092,607.68	39° 59' 19.027 N	109° 23' 8.426 W
810.00	9.27	158.68	807.51	-43.24	11.75	14,525,981.99	2,092,612.35	39° 59' 18.903 N	109° 23′ 8.369 W



# **SDI**Survey Report - Geographic



Company:

Kerr McGee Oil and Gas Onshore LP

Project: Site: Well: Uintah County, UT UTM12

NBU 922-360 PAD NBU 922-3604BS

Wellbore: OH
Design: OH

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Database:

Well NBU 922-36O4BS

GL 4968 & KB 14 @ 4982.00ft (ENSIGN 139) GL 4968 & KB 14 @ 4982.00ft (ENSIGN 139)

True

Minimum Curvature EDM5000-RobertS-Local

urvey					Side Stra				0753754565656
Measured			Vertical			Мар	Мар		
Depth (ft)	Inclination (°)	Azimuth (°)	Depth (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	1.44.5	
900,00	10.82	162,23	896.12		PAGE PIONENCIES			Latitude	Longitude
990.00	12.40	162.23	984.28	-58.04 75.20	16.96	14,525,967.29	2,092,617.83	39° 59′ 18.757 N	109° 23' 8.302
1,080.00	13.65	161.98		-75.29	22.46	14,525,950.14	2,092,623.64	39° 59′ 18.587 N	109° 23' 8.231
1,170.00	14.79	162.95	1,071.96	-94.60	28.67	14,525,930.94	2,092,630.20	39° 59' 18.396 N	109° 23′ 8.152
1,260.00	16.47	162.95	1,159.20 1,245.87	-115.68 -138.79	35.33	14,525,909.99	2,092,637.24	39° 59' 18,187 N	109° 23' 8.066
1,350.00	19.05	159.25	1,245.67	-136.79 -164.65	42.68	14,525,887.02	2,092,645.01	39° 59' 17.959 N	109° 23' 7.972
1,440.00	20.51	157.80	1,416.27	-192.98	51.87	14,525,861.33	2,092,654.66	39° 59' 17.703 N	109° 23' 7.854
1,530.00	20.62	157.53	1,500.53	-192.96	63.03	14,525,833.20	2,092,666.33	39° 59' 17.423 N	109° 23' 7.710
1,620.00	21.80	156.41	1,584.43	-222.23 -252.19	75.04	14,525,804.18	2,092,678.88	39° 59' 17.134 N	109° 23′ 7.556
1,710.00	20.66	156,55	1,668.32	-282.19 -282.07	87.79	14,525,774.46	2,092,692.16	39° 59' 16.838 N	109° 23' 7.392
1,800.00	19.06	156.58	1,752.97	-202.07 -310.12	100.80	14,525,744.81	2,092,705.71	39° 59' 16.543 N	109° 23' 7.225
1,890.00	19.99	159.95	1,732.97	-310,12 -338,06	112.95	14,525,716.99	2,092,718.37	39° 59′ 16.266 N	109° 23' 7.069
1,980.00	19.69	163.69			124.07	14,525,689.26	2,092,729.99	39° 59′ 15.989 N	109° 23′ 6.926
2,070.00	20,41	163.65	1,922.46	-367.06	133.60	14,525,660.43	2,092,740.05	39° 59′ 15.703 N	109° 23′ 6.803
2,160.00	18.99	165,03	2,007.00	-396.67	142.28	14,525,630.98	2,092,749.26	39° 59' 15.410 N	109° 23' 6.692
2,160.00	18.89	163.69	2,091.73	-425,88 454,04	150.48	14,525,601.93	2,092,757,99	39° 59' 15.121 N	109° 23' 6,586
2,380.00			2,176.86	-454.01	158.35	14,525,573.95	2,092,766.37	39° 59' 14.843 N	109° 23' 6.485
	19.93	164.42	2,299.47	-495.55	170.21	14,525,532,63	2,092,778.98	39° 59' 14.433 N	109° 23' 6.333
	I MWD SURF								
2,432.00 FIRST SI	19.61 <b>DI MWD PRO</b> I	163.61 DUCTION SUI	2,348.40 RVEY	-512.46	175.06	14,525,515.81	2,092,784.13	39° 59' 14.266 N	109° 23' 6.27
2,522.00	19.17	161.31	2,433,30	-540.94	184.05	14,525,487.49	2,092,793,64	39° 59' 13.984 N	109° 23' 6.15
2,613.00	18,66	158.45	2,519.39	-568.64	194.19	14,525,459.98	2,092,804.27	39° 59' 13.710 N	109° 23' 6.025
2,704.00	18.04	161,57	2,605.76	-595.55	203.99	14,525,433,26	2,092,814.56	39° 59' 13.444 N	109° 23' 5.899
2,794.00	18.48	160.32	2,691.23	-622.20	213.20	14,525,406.78	2,092,824.25	39° 59' 13.181 N	
2,885.00	18.11	159.68	2,777.63	-649.04	222.97	14,525,380.12	2,092,834.51	39° 59' 12.916 N	109° 23′ 5.78′
2,975.00	17.74	161.11	2,863.26	-675.13	232.27	14,525,354.20	2,092,844.27	39° 59' 12.658 N	109° 23' 5.655
3,066.00	15.08	157.64	2,950,55	-699,20	241.26	14,525,330.29	2,092,853.70	39° 59' 12.420 N	109° 23' 5,536
3,156.00	12,65	158.61	3,037,92	-719.21	249.31	14,525,310.44	2,092,862.11	39° 59' 12.222 N	109° 23' 5.420 109° 23' 5.317
3,247.00	11.87	158.51	3,126.84	-737.20	256.37	14,525,292.58	2,092,869.50	39° 59' 12.044 N	
3,337.00	9.67	163.02	3,215.26	-753.04	261.97	14,525,276.84	2,092,875.38	39° 59' 11.888 N	109° 23' 5,226
3,428.00	8.40	164.30	3,305.12	-766.75	266.00	14,525,263.21	2,092,879.66		109° 23' 5.154
3,518.00	7.86	165.72	3,394.22	-779.04	269.30	14,525,250.98	2,092,883.18	39° 59′ 11.752 N	109° 23' 5.102
3,609.00	6.13	166.51	3,484.54	-789.80	271.97	14,525,240.27		39° 59' 11.631 N	109° 23' 5.060
3,699.00	5.02	162.23	3,574.11	-798.22	274.29	14,525,231.89	2,092,886.04	39° 59' 11.524 N	109° 23' 5,026
3,790.00	4.30	164.12	3,664.81	-805.29	276.44	14,525,224.86	2,092,888.52	39° 59' 11.441 N	109° 23' 4.996
3,880.00	2.68	172.22	3,754.64	-810.62	277.65	14,525,224,86	2,092,890.80	39° 59' 11.371 N	109° 23' 4.968
3,971.00	1.82	177.57	3,845.57	-814.17	278.00		2,092,892.10	39° 59' 11.318 N	109° 23' 4.95
4,061.00	0.98	150.02	3,935.54	-816.27	278.00 278.44	14,525,216.01 14,525,213.92	2,092,892.51	39° 59' 11.283 N	109° 23' 4.948
4,152.00	0.73	163,48	4,026.53	-817.50	278.99		2,092,893.00	39° 59' 11.263 N	109° 23' 4.942
4,242.00	0.44	155.99	4,116.53	-818.36	279.30	14,525,212.70	2,092,893.57	39° 59' 11.251 N	109° 23' 4.93
4,333.00	0.77	170.90	4,207.52	-819.29	279.54 279.54	14,525,211.84	2,092,893.89	39° 59' 11.242 N	109° 23' 4.931
4,423.00	0.67	210.16	4,297.52	-820.34		14,525,210.92	2,092,894.15	39° 59' 11.233 N	109° 23' 4.928
4,514.00	1.06	195.77	4,388.51		279.37	14,525,209.87	2,092,894.00	39° 59' 11.222 N	109° 23' 4,930
4,605.00	0.27		4,479.50	-821.61	278.87	14,525,208.59	2,092,893.52	39° 59' 11.210 N	109° 23′ 4.937
4,695.00	0.27	45.23	,	-822,27 821,72	278.80	14,525,207.93	2,092,893.46	39° 59' 11,203 N	109° 23' 4.938
4,785.00	0.62	34.17 138.70	4,569.50	-821.72 921.46	279.22	14,525,208.49	2,092,893.87	39° 59' 11,209 N	109° 23' 4.932
			4,659.50	-821.46 821.70	279.62	14,525,208.75	2,092,894.27	39° 59' 11.211 N	109° 23' 4.927
4,876.00	0.37	128.68	4,750.50	-821.79	279.98	14,525,208.43	2,092,894.64	39° 59' 11.208 N	109° 23' 4.923
4,967.00	0.61	171.70	4,841.49	-822.46	280.28	14,525,207.77	2,092,894.95	39° 59' 11.201 N	109° 23' 4.919
5,057.00	0.62	179.89	4,931.49	-823.42	280.35	14,525,206.81	2,092,895.04	39° 59' 11.192 N	109° 23' 4.918
5,148.00	0.62	189.98	5,022.48	-824.39	280.27	14,525,205,83	2,092,894.97	39° 59' 11,182 N	109° 23′ 4.919
5,238.00	0.85	169.90	5,112.48	-825.53	280.30	14,525,204.69	2,092,895.02	39° 59' 11.171 N	109° 23′ 4.918
5,329.00	0.91	290.11	5,203.47	-825.95	279.74	14,525,204.27	2,092,894.47	39° 59' 11.167 N	109° 23' 4.926
5,419.00	0.82	295,66	5,293.46	-825.42	278.49	14,525,204.77	2,092,893.21	39° 59' 11.172 N	109° 23′ 4.942
5,510.00	0.70	280.18	5,384.45	-825.04	277.36	14,525,205,13	2,092,892.07	39° 59' 11.176 N	109° 23' 4,956
5,601.00	1.32	16.60	5,475.44	-823.94	277.11	14,525,206.23	2,092,891,80	39° 59' 11.187 N	109° 23' 4,959



# **SDI**Survey Report - Geographic



Company:

Kerr McGee Oil and Gas Onshore LP

Project:

Uintah County, UT UTM12

 Site:
 NBU 922-360 PAD

 Well:
 NBU 922-3604BS

Wellbore: Design: ОН ОН Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference: Survey Calculation Method:

Database:

Well NBU 922-36O4BS

GL 4968 & KB 14 @ 4982.00ft (ENSIGN 139) GL 4968 & KB 14 @ 4982.00ft (ENSIGN 139)

True

Minimum Curvature

EDM5000-RobertS-Local

									Carlotte Carlotte
leasured Depth	Inclination	Azimuth	Vertical Depth			Map	Мар		
(ft)	(°)	(°)	(ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
5,691.00	1.32	22,04	5,565.42	-821.99	277,79	14,525,208,19	2,092,892,45	39° 59' 11,206 N	109° 23' 4.95
5,782.00	0.54	19.62	5,656.41	-820.61	278.33	14,525,209.58	2,092,892.96	39° 59' 11.220 N	109° 23' 4.94
5,872.00	0.27	55.79	5,746.40	-820.09	278.65	14,525,210.10	2,092,893,27	39° 59' 11.225 N	109° 23' 4.94
5,963.00	0.18	72.88	5,837.40	-819.93	278.96	14,525,210.27	2,092,893,58	39° 59' 11.226 N	109° 23' 4.93
6,053.00	0.35	60.28	5,927.40	-819,75	279,34	14,525,210,46	2,092,893.95	39° 59' 11,228 N	109° 23' 4,93
6,144.00	0.63	128.28	6,018.40	-819.92	279.97	14,525,210,30	2,092,894,59	39° 59' 11.227 N	109° 23′ 4.92
6,234.00	0.88	138.24	6,108.39	-820.74	280.82	14,525,209,49	2,092,895,45	39° 59' 11.218 N	109° 23' 4.91
6,325.00	0.17	113.38	6,199.39	-821.32	281.41	14,525,208.92	2,092,896.05	39° 59' 11.213 N	109 23 4.91 109° 23' 4.90
6,415.00	0.79	47.62	6,289.38	-820.95	281.99	14,525,209,30	2,092,896.63	39° 59' 11.216 N	109° 23' 4.89
6,506.00	0.42	141.54	6,380.38	-820,79	282.66	14,525,209,47	2,092,897,30	39° 59' 11.218 N	109° 23' 4.88
6,596.00	0.79	119.53	6,470.37	-821.36	283.40	14,525,208,92	2,092,898.05	39° 59' 11.212 N	109 23 4.87
6,687.00	0.61	108.67	6,561.37	-821.82	284,41	14,525,208.48	2,092,899,06	39° 59' 11.208 N	109° 23' 4.86
6,778.00	0.88	137.05	6,652.36	-822,49	285.34	14,525,207.83	2,092,900.01	39° 59' 11.201 N	109° 23' 4.85
6,868.00	0.76	132.81	6,742.35	-823,40	286.25	14,525,206,93	2,092,900.94	39° 59' 11.192 N	109° 23' 4.84
6,959.00	1.16	109.70	6.833.34	-824.12	287.56	14,525,206.24	2,092,902.26	39° 59' 11.185 N	109 23 4.82 109° 23' 4.82
7,049.00	0.97	128.92	6,923,32	-824.91	289,01	14,525,205.48	2,092,903,72	39° 59' 11.177 N	109° 23' 4.8
7,139.00	0.59	267.63	7,013.32	-825,40	289.14	14,525,204.98	2,092,903.86	39° 59' 11.172 N	109° 23' 4.86
7,230.00	0.34	211.86	7,104.32	-825.65	288.53	14,525,204.72	2,092,903.26	39° 59' 11.170 N	109 23 4.8°
7,320.00	1.23	191.30	7,194.31	-826.83	288.20	14,525,203,54	2,092,902.95	39° 59' 11.158 N	109 23 4.6 109° 23' 4.8'
7,411.00	1,44	180.94	7,285.28	-828.93	287.99	14,525,201.44	2,092,902.78	39° 59' 11.138 N	109 23 4.8 109° 23' 4.82
7,501.00	0.70	204.44	7,375,27	-830,56	287.75	14,525,199,80	2,092,902,76	39° 59' 11.121 N	109 23 4.82 109° 23' 4.82
7,592.00	0.83	357.76	7,466.26	-830,41	287.49	14,525,199.95	2,092,902.30	39° 59' 11.123 N	109 23 4.82 109° 23' 4.82
7,682.00	0.49	6.95	7,556.26	-829,37	287.51	14,525,200.98	2,092,902.30	39° 59' 11.133 N	
7,773.00	0.83	63.74	7,647.25	-828.69	288.15	14,525,201.67	2,092,902.93	39° 59' 11.140 N	109° 23' 4.82
7,863.00	0.28	7.27	7,737.25	-828,19	288.76	14,525,202.19	2,092,903.53	39° 59' 11.145 N	109° 23' 4.81
7,953.00	0.19	244.19	7,827.25	-828,03	288.66	14,525,202.34	2,092,903.42	39° 59' 11,146 N	109° 23' 4.8° 109° 23' 4.8°
8,044.00	0.37	3.43	7,918,25	-827.81	288.54	14,525,202.57	2,092,903,42	39° 59' 11.149 N	
8,134.00	0.26	56.32	8,008,25	-827.40	288.72	14,525,202.97	2,092,903.48	39° 59' 11,153 N	109° 23' 4.8′ 109° 23' 4.8′
8,225.00	0.71	93.85	8,099.24	-827.33	289.46	14,525,203.06	2,092,903.48	39° 59' 11.153 N	109 23 4.8 109° 23' 4.80
8,315.00	1.00	118.76	8,189.23	-827.74	290.70	14,525,203.67	2,092,904.21	39° 59' 11.149 N	
8,406.00	1.23	100.71	8,280.22	-828.31	292.36	14,525,202.14	2,092,905.47	39° 59' 11.144 N	109° 23' 4.78
8,496.00	1.43	113.42	8,370.19	-828,93	294.34	14,525,201.55	2,092,907.13	39° 59' 11.137 N	109° 23' 4.76
8,587.00	1.42	124.07	8,461,16	-830.02	296.32	14,525,200.50	2,092,911.12	39° 59' 11.127 N	109° 23′ 4.73
8,661.00	1.19	144.56	8,535.15	-831.15	297.52	14,525,199.38	2,092,912.34	39° 59' 11.127 N	109° 23' 4.7′
	I MWD PROD		•	30,1,0	201.02	1-1,020,100.00	2,002,012,04	Ja Ja II.IION	109° 23' 4.69
8,720.00	1,19	144.56	8,594.13	-832.15	298.23	14,525,198,40	2,092,913,07	30° 50' 11 106 N	4000 001 4 00
•	JECTION TO		0,000	-002.10	200.20	17,020,100,40	2,082,813.07	39° 59' 11.106 N	109° 23' 4.68

Design Annotations  Measured  Depth	Vertical Depth	Local Coord	inates +E/-W	
<b>(R)</b> 191.00	<b>(ft)</b> 190.99	<b>(ft)</b> 0.96	<b>(ft)</b> 1.01	Comment FIRST SDI MWD SURFACE SURVEY
2,380.00	2,299.47	-495.55	170.21	LAST SDI MWD SURFACE SURVEY
2,432.00	2,348.40	-512.46	175.06	FIRST SDI MWD PRODUCTION SURVEY
8,661.00	8,535.15	-831.15	297.52	LAST SDI MWD PRODUCTION SURVEY
8,720.00	8,594.13	-832.15	298.23	SDI PROJECTION TO BIT

			·
Checked By:	Approved By:	С	Date: